


Periodic Bathymetry Survey Report

June 2010 Multibeam Survey

October 2010



Prepared for:
Cooperating Parties Group
New Jersey

Document No.: 60145884.C300

Contents

Introduction	1
--------------------	---

List of Figures

Periodic Bathymetric Survey.....	3
----------------------------------	---

List of Attachments

1. Hydrographic Survey Report For Spring 2010 Lower Passaic River Newark, NJ prepared by Gahagan & Bryant Associates, Inc (GBA).
2. Bathymetric Survey Field Report: Site Visit Summary of Findings June 8-11, 2010 And June 23, 2010, Lower Passaic River, Newark, NJ prepared by AECOM.
3. Review of Hydrographic Survey Report prepared by Gahagan & Bryant Associates, Inc (GBA) for Spring 2010, Lower Passaic River, Newark, NJ, submitted September 30, 2010 prepared by AECOM.

Introduction

The 2010 Bathymetric Survey was performed under the specifications of the "Quality Assurance Project Plan (QAPP) for Lower Passaic River Restoration Project: Periodic Bathymetric Surveys, Revision 2 (May 2010). This survey is the third in a series of periodic multibeam bathymetric surveys performed by the Cooperating Parties Group (CPG) as part of the Lower Passaic River Remedial Investigation (RI) and Feasibility Study (FS). The survey was performed by Gahagan & Bryant Associates, Inc (GBA) between June 8-23, 2010 accordance with the specifications of the USEPA-approved QAPP. The survey (Figure 1) was conducted in the river miles 0 to 14 of the Lower Passaic River Study Area (LPRSA). GBA conducted the two previous multibeam surveys in 2007 and 2008 over the same extent of the LPRSA. AECOM performed oversight on behalf of the CPG during the 2010 survey and reviewed the report submittal. CDM provided oversight on behalf of the USEPA.

The 2010 Bathymetric Survey was performed by the CPG at the direction of USEPA to address the following study questions identified by USEPA:

"Can morphologic features (e.g. depositional bars, deep channels) be identified as stable or unstable after large events?

- By examining existing persistent morphologic features (e.g. depositional bars, deep channels, smooth channels) in 2007 and 2008 surveys, the 2010 survey can yield deviations from these persistent features after a large event.
- Large scale bed roughness features on the order of 0.5 m or more, due to macro organic material, trees, sand waves, other debris, could either be removed or formed during large events. Comparison of the 2008 and 2010 surveys could yield both quantitative and qualitative information on these features.

Where are possible depositional areas located in the LPRSA after a large event?

- Formation of large scale depositional features either in-channel or on point bars due to increased sediment loads during large events is a possibility. These features would be readily identified in the 2010 survey.

Can unstable areas of sediments after a large event be identified?

- Large persistent linear channelized features are evident in the 2007 and 2008 surveys in the vicinity of the pilot dredging region. Changes or formation of such features during a large event would be evidence of scouring. The size and magnitude of these features can be compared in order to better inform the quantification of sediment stability in the river."


The precision and accuracy of the data were collected consistent with Engineering and Design - Hydrographic Surveying (EM 1110-2-1003; US Army Corps of Engineers 2002 [modified 2004]). The raw and processed data have been reviewed to ensure that the requirements of the USEPA-approved QAPP have been met. The data collected during this survey meets the data quality objectives to address the above study questions, with consideration to the uncertainty inherent in these data and specified in the QAPP. Specifically, depth difference maps produced with this survey and previous bathymetric surveys provide qualitative comparisons only, and depth

differences of ± 0.3 m are within the range of uncertainty and should be removed from evaluation and considered in all interpretations of these data (See Worksheet #9 of the QAPP for additional detail on data use objectives).

No interpretations of the survey results are included in this report and its attachments. Data analysis and interpretation of this survey as well as its relationship to other surveys will be conducted as part of the LPRSA CSM development, sediment stability analyses, Lower Passaic River/Newark Bay Modeling Program, and other components of the LPRSA RI/FS.

The following documents are attached:

1. Hydrographic Survey Report For Spring 2010 Lower Passaic River Newark, NJ prepared by Gahagan & Bryant Associates, Inc (GBA).
2. Bathymetric Survey Field Report: Site Visit Summary of Findings June 8-11, 2010 And June 23, 2010, Lower Passaic River, Newark, NJ prepared by AECOM.
3. Review of Hydrographic Survey Report prepared by Gahagan & Bryant Associates, Inc (GBA) for Spring 2010, Lower Passaic River, Newark, NJ, submitted September 30, 2010 prepared by AECOM.



References

AECOM 2010. Quality Assurance Project Plan for Lower Passaic River Restoration Project: Periodic Bathymetric Surveys, Revision 2. AECOM, Inc. , May 2010.

HYDROGRAPHIC SURVEY REPORT

FOR

Spring 2010

Lower Passaic River

Newark, NJ

Submitted:
October 19, 2010

Prepared by:



Gahagan & Bryant Associates, Inc.
5803-D Kennett Pike, Centreville Square
Wilmington, Delaware 19807

TABLE OF CONTENTS

1.0	INTRODUCTION	1
2.0	SURVEY SETUP AND CONTROL	1
3.0	HYDROGRAPHIC SURVEY	2
4.0	DATA PROCESSING AND COLLECTION.....	4
5.0	QUALITY CONTROL/QUALITY ASSURANCE.....	9
6.0	DAILY OVERVIEW OF SURVEY OPERATIONS	19
7.0	CONTACT INFORMATION.....	22

APPENDICES

- APPENDIX 1: Control Information
- APPENDIX 2: 0.5 ft Contour Drawings
- APPENDIX 3: Thirteen Single Beam Cross Sections
- APPENDIX 4: Copy of Field Notes
- APPENDIX 5: Compact Disk including: Survey Report, AutoCad Drawings,
Hypack Files, Field Notes, ASCII Data, Trackplots, Intensity Data,
Sidescan Data

1.0 INTRODUCTION

Gahagan & Bryant Associates (GBA) has performed two previous hydrographic surveys of the Lower Passaic River in September 2007 and November 2008. The high flow event of March 2010 prompted the EPA to request an additional multibeam survey of the lower 14 River Miles of the Passaic River. This survey was performed with the same methodologies as the previous two surveys.

2.0 SURVEY SETUP AND CONTROL

On June 5, 2010, four vertical control points were recovered and/or situated at various points along both sides of the Passaic River by GBA survey technicians. Tide gauges were set near these control points for the purpose of providing daily QA/QC checks of the accuracy of RTK derived water surface elevations used to provide real-time tide corrections during the hydrographic survey.

Static GPS observations were made on the ground control points utilizing four Ashtech Locus L1 receivers. In addition, four control monuments listed in the National Geodetic Survey (NGS) database were observed to establish the horizontal and vertical positions of the site benchmarks.

Listed hereafter are the NGS control monuments used in this survey. The values shown are NAD 83 (horizontal) and NAVD 88 (vertical).

NGS PID	NAME	LAT	LON	ELEV	H/V
AI7796	01392590 A	N 40°43'58.61588"	W 074°09'13.731 44	11.67'	H/V
KV3414	G101	N 40°47'49.60797"	W 074°08'17.21832"	14 .24'	H/V
KV6837	9 C 1	N 40°39'46.13811"	W 074°07'56.83589"		H
	188.12-A*			188.47'	V

NOTE* 188.12-A is a MAG Nail Set near KV0135, designated as "188.12 NJGS". A closed level loop was performed between KV0135 and the MAG Nail. GPS observations were performed from 188.12-A.)

The project control, NAD 83 & NAVD 88 values and descriptions are listed as follows:

NAME	NORTHING	EASTING	ELEV.	DESCRIPTION
01392590 A	692097.663	588059.003	11.670	AI7796 Steel Rod
G101	715490.263	592312.818	14.240	KV3414 Disk
9 C 1	666572.729	594085.074	7.202	KV6837 Disk
188.12-A	732846.821	606378.233	188.470	MNS NEAR 188.12 NJGS
PORT 1	695188.398	597847.469	8.961	Sheared Metal Bolt
PATH	701845.995	585643.039	5.705	PSE&G Disk "PRO4"
NUTLEY 2	720714.538	592028.699	7.952	TPS NEAR NUTLEY
CPG2	733825.441	597109.293	7.936	TPS NEAR CPG1

Tide gauges were established via closed level runs from the static GPS control points. The NGS VERTCON program was utilized in adjusting the NAVD 88 vertical values to NGVD 29 datum. The tide gauges and values are listed as follows:

GAUGE	NAVD 88 ELEV	NGVD 29 ELEV	DESCRIPTION
PORT 2	8.89'	10.01'	Mark on SE corner of concrete
PATH 3	6.11'	7.23'	Triangle cut on concrete wall ES of river
NUTLEY	8.73'	9.85'	Mark on conc. Wall on WS of river
CPG1	8.18'	9.30'	Triangle cut on top of steel bulkhead

3.0 HYDROGRAPHIC SURVEY

All work conducted during the hydrographic survey was performed in accordance with the Quality Assurance Project Plan (QAPP) for Lower Passaic River Restoration Project: Periodic Bathymetric Surveys, Revision 2 (AECOM, May 2010).

Multi-beam Survey

GBA performed a multi-beam survey that extended from the mouth of the Lower Passaic River at RM 0.0 to RM 14, which is the upriver limit of effective multi-beam coverage. The multi-beam survey covered the main channel prism and all depths greater than (-) 6.0 feet NGVD, residing within the confines of the riverbanks. GBA's survey maintained a buffer of approx. 75 feet around all bridges and in-water structures, as these areas were covered in the Fall 2007 survey. GBA planned and conducted our survey lines and data collection to ensure 100% bottom coverage. We primarily used only the multi-beam survey data collected within the confines of the primary 90 degree cone (nadir to 45 degrees both port and starboard) for the processing of final survey results and deliverables. In shallow areas (less than 10 feet) there were small data gaps due to the shallow water depth. GBA made every effort to minimize the data gaps. Sufficient data were collected to clearly define 0.5 foot contour intervals. GBA met all requirements outlined within the Corps of Engineers Hydrographic Survey Manual EM 1110-2-1003, dated January 1, 2002 as augmented by April 1, 2004 updates to Chapter 11 for multi-beam surveying. GBA met standards for multi-beam surveys conducted for Navigation and Dredging Support Surveys in soft bottom materials.

Single Beam Survey

GBA surveyed the thirteen (13) selected transects as surveyed during the Fall 2008 survey event. These transects extended from RM 1.6 to RM 8.0 and met all requirements outlined within the Corps of Engineers Hydrographic Survey Manual.

Survey Equipment

GBA utilized equipment identical to the equipment used on the 2007 and 2008 surveys and included the following components:

Multi-beam equipment

1. • The Multi-beam data collection system consisted of a Reson 8101 SeaBat system operating at +/- 240 kHz, with a total beam angle of 210 degrees. Each individual beam angle measures 1.5 degrees X 1.5 degrees. The 8101 was upgraded to include Reson's backscatter and side scan software options. The Reson's 8101 transmitter and receiver (transducer) is permanently mounted on a bow deployable arm, designed by GBA to best suit the shallow draft requirement of this project plus ensure the stability of the transducer
2. Primary horizontal and vertical positioning was accomplished by utilizing a Trimble DSM232 RTK rover/receiver with a CDMA cell phone modem. RTK corrections were obtained via the CDMA modem from a permanent CORS (Continuously Operating Reference System) site located at the New Jersey Institute of Technology (NJIT) in Newark, NJ. See attached specifics on the NJIT site and Station Description for NJI2, which is the NGS control point utilized for the NJIT CORS site. This method of positioning was chosen in lieu of establishing our own transmitting base stations at numerous control points due to the security issue and also it allowed us to spend more time collecting multi-beam data. GBA also utilized the aforementioned positioning methods, as it replicated the 2007 and 2008 surveys. . The NJIT CORS Station and the DSM232 was used for all horizontal and vertical positioning, included water surface elevations/tide.
3. GBA utilized the most recent version of Hypack/Hysweep (2010) for data collection and editing and collect and process all data on high speed PC-based data collection platforms.
4. Inertial Positioning was accomplished by utilizing an Applanix – TSS POSMV.
5. Heave/pitch/roll/yaw compensation was accomplished with the TSS POSMV.
6. The method for determining water surface elevations (tide levels) was the same methodology used on the Fall 2007 and Fall 2008 surveys. Analog visual tide gauges were set at the same tidal gauging locations used for the 2007 and 2008 Fall surveys. Control information for these points were re-confirmed with Static GPS prior to the commencement of the hydrographic survey. Real time tides were obtained by using GPS in the RTK mode and these RTK elevations were checked and verified and compared to the analog tide gauges numerous times during the course of a survey day to ensure the accuracy required is met or exceeded.

7. The survey vessel Sea Fix is a 25 foot aluminum hulled vessel constructed by Thomas Marine in 1997. It is powered by twin 175 HP outboard motors with an onboard power generating system to operate the survey equipment. This is the same vessel that was utilized on the 2007 and 2008 surveys.

Single beam equipment

1. GBA utilized an Odom Mark III operating at 200/33 kHz (+/- 10 %) with a 3.5 degree beam angle transducer.
2. GPS positioning equipment were the same as item 2 above for multi-beam positioning.
3. Data collection system and software were identical to the systems identified in item 3 above.
4. Water surface/tide elevations were obtained utilizing the same methods described in paragraph 6 above.

For the Spring 2010 survey, both the multi-beam and single beam surveys were conducted from the same vessel.

4.0 DATA PROCESSING AND COLLECTION

GBA made all efforts to ensure that the multi-beam data collected provided 100% bottom coverage. This was the case the majority of the time, but shallow water depths was the limiting factor on some of the survey lines and 100% overlap was not possible in the shallower depths as referenced in GBA's initial proposal and subsequent conversations with Ms. Greenblatt.

Multi-beam survey deliverables

Deliverables from the Multi-beam survey shall include:

1. Report documenting how the survey was performed, what equipment was used, who performed the survey, how data was processed and how QC requirements were met.

A. Report documenting how the survey was performed.

The majority of the information in reference to the conduct of the survey is embedded within other portions of GBA's submission. Please see Equipment List, Overview of Multi-beam Daily Survey Reports and Overview of Quality Control and Quality Assurance Procedures.

A brief overview is as follows:

GBA installed the Reson 8101 on the Sea Fix at our Baltimore Office and performed pre-mobilization system checks between June 1-4, 2010, GBA survey team departed for the Passaic River on June 5, 2010. Multi-beam patch testing

and QA/QC test were initiated immediately. Survey lines were established based upon channel coordinates to best obtain 200% bottom coverage. The multi-beam survey commenced on June 9, 2010 and concluded on June 23, 2010.

B. Equipment used: Please see Equipment List

C. Who performed the survey: Please see below

The primary field survey team consisted of:

Mr. Edward DeAngelo, Scientist/Survey Manager/Lead Project Surveyor
Please see attached resume for Mr. DeAngelo
Mr. Travis Schmidt, USCG Licensed Vessel Captain
Mr. William Carroll, PLS MD/DE/VA/WV/PA
Mr. Paul Seaboldt, PLS NY/CA
Mr. Blair Carlson, PE Washington Survey Technician

Office data processing personnel:

Mr. Edward DeAngelo, See above
Mr. John Drake, GBA Engineer and CAD Specialist
Ms. Jayne McClure, GBA Engineer and Multi-beam Processing Specialist
Project Manager: Douglas Moore, PLS/ACSM Certified Hydrographer – Survey Division Manager

D. How data was processed and how QC requirements were met

QC/QA for all GBA survey projects commence immediately upon receipt of surveying contract. Preliminary QC/QA procedures for the 2010 Passaic River Project were the same used during the 2007 and 2008 surveys. The procedures were provided to all field and office personnel involved with the project on May 24, and updated on June 3, 2010. These procedures were primary in our ongoing data collection and review process for the project. All procedures outlined in the August 22, 2007 Overview of Quality Control and Quality Assurance Procedures for the Passaic River Multi-beam Survey were followed and performed during the conduct of the survey. Please see the following pages in reference to our preliminary and ongoing QC/QA efforts.

**GAHAGAN & BRYANT UPDATED QUALITY CONTROL/QUALITY ASSURANCE
OVERVIEW**

PASSAIC RIVER MULTI-BEAM SURVEY-MAY/ JUNE/JULY 2010

The intent of this document is to provide minimum performance standards to conduct the multi-beam and single beam surveys generated and proposed by GBA on the Lower Passaic River during the period referenced above.

GBA shall follow and meet all requirements as indicated within the confines of the U.S. Army Corps of Engineers Hydrographic Survey Manual EM 1110-2-1113, dated January 1, 2002 and as augmented by updates to Chapter 11 Multi-beam Surveying for Navigation and Dredging Support Surveys for Soft Bottom Materials.

Additional QC/QA procedures shall be implemented if required during the conduct of the survey if conditions warrant.

**TASKS TO BE PERFORMED AT BALTIMORE'S GBA OFFICE BEFORE
MOBILIZATION**

- *Mechanically prepare vessel, trailer and tow vehicle*
- *Inspect all resident required safety equipment and ensure operational status*

SURVEY RELATED PROCEDURES

- *Verify operational status of all survey related equipment, including software and hardware*
- *Verify offsets of all surveying equipment*
- *Measure and verify plate check and bar check lines*
- *Perform internal calibration test (bucket test) on Sound Velocity Profiler*
- *Verify acoustic constants on both single beam and multi-beam transducers*
- *Ensure 210 degree 8101 head is onboard and all beams are functional, including backscatter*
- *Perform latency test on single beam system*
- *Verify static draft index marks are visible for daily static draft visual tests*
- *Perform Patch Test*
- *Conduct full Performance Test, as outlined within the Corps Hydro Manual – Chapter 11*

Strive to obtain results commensurate with Hard Bottom standards, although our Proposal references Soft Bottom Standards

See the following criteria:

Hard Bottom : Max. allowable bias = <0.1 feet Maximum outlier = 1.0 feet

Soft Bottom: Max. allowable bias = < 0.2 feet Maximum outlier = 1.0 feet

PRELIMINARY ONSITE QC/QA PERFORMANCE CHECKS

The following tasks shall be performed onsite prior to the commencement of any survey related tasks on the Lower Passaic River, either single beam or multi-beam.

- **Patch Test**
- **Performance Test**

Performance Tests shall be conducted prior to, at the half way point of the collection of survey data and at the conclusion of the field survey data collection process(Total of a minimum of 3 Performance Tests). The results shall minimally meet Soft Bottom Standards while striving to meet Hard Bottom Standards. If feasible, all Performance Tests shall be conducted in an area provided by the NYD Corps Engineers. This area is constantly utilized by the Corps for their QC/QA Performance Tests and is modeled very accurately. If it is not possible to use the Corps Site, an additional area shall be selected to meet project requirements.

NOTE: All Performance Tests conducted for both multi-beam and single beam shall be initially conducted using the CORS network corrections. Additionally, the same lines shall be re-run in both single beam and multi-beam mode using the GBA RTK base station set on verified control. This procedure shall be repeated each time a Performance Test is performed to document the quality of the corrections over the time period of the survey.

- *All existing horizontal and vertical control that was utilized on previous surveys (2007 & 2008) shall be verified for status and published x/y/z values shall be compared to real time values obtained by RTK methods utilizing CORS corrections from NJIT Base Station. Check in observations shall be observed on multiple monuments using both GBA RTK and CORS systems and values compared to each system including previously determined X/Y/Z values.*

Static observations shall be made on a specific control point by both systems for approx. 15 to 30 minutes and results compared. Additional control shall be utilized and or established as required to meet survey standards.

- **Any additional QC/QA procedures as deemed appropriate by the Survey Project Manager.**
- **ALL PROCEDURES AND THE RESULTS THERE OF SHALL BE CLEARLY DOCUMENTED IN HARD COPY AND DIGITAL FORMAT.**

DAILY QC/QA PROCEDURES

NOTE: DAILY SURVEY QC/QA PROCEDURES SHALL FOLLOW MANDATES IN CORPS HYDROGRAPHIC SURVEY MANUAL AND SHALL INCLUDE BUT NOT LIMITED TO THE FOLLOWING:

- **Sound Velocity Profiles at the beginning, midpoint and end of the survey day**

- *Vertical positioning checks at the beginning, midpoint and end of the survey day, horizontal positioning checks at the beginning and end of the survey day.*
- *Sufficient single beam survey lines to augment and verify the multi-beam survey data. It is suggested that these cross lines be surveyed approx. every 1000 feet perpendicular to the channel alignment.*
- *All survey data shall be uploaded on a daily basis to an independent GBA QC/QA Expert to ensure the validity of the survey data, verify area coverage and provide acceptance of the data collected and generate areas that require additional survey data if necessary.*

ALL QC/QA PROCEDURES, INCLUDING THOSE CONDUCTED IN BALTIMORE, ONSITE PRELIMINARY QC/QA AND DAILY QC/QA CHECKS SHALL BE CLEARLY DOCUMENTED BY THE ONSITE SURVEYOR IN CHARGE FOR FUTURE REFERENCE.

ADDITIONAL ONSITE QC/QA PROCEDURES SHALL BE IMPLEMENTED AS REQUIRED TO ENSURE ACCURACY REQUIREMENTS ARE MET OR EXCEEDED

Additional Field QC/QA Procedures

On a ongoing basis, during or immediately following the conduct of the multi-beam field data collection efforts, the Lead Surveyor on site evaluated the quality of the collected data based upon coverage, overlap, minimum elevation obtained, comparison of depths on overlapping swaths, data gaps, positioning accuracy, comparison of water surface readings (set tide gauges versus RTK GPS) and made immediate onsite decisions as to the accuracy and validity of data and discern if any areas needed to be re-surveyed.

Overview of Office Processing Procedures

The initial processing of the multi-beam data was performed on site, by Mr. DeAngelo to ensure that all accuracy and coverage issues were satisfied. The multi-beam data was then transferred to GBA's Houston Offices for final processing. We utilized the personnel at these offices due to the fact that they are very familiar with multi-beam data collection and post processing and also in order to meet our projected delivery schedule for the multi-beam data.

The raw data was reviewed for obvious outliers and then processed through all phases with Hysweep software. Hypack/Hysweep multibeam processing is broken into three phases. In Phase 1 raw data files are opened and the parameters for the application of ancillary data (motion, tide, speed of sound, etc) is defined. At this stage the tide values that applied to each raw can be reviewed with erroneous RTK spike removed (as under bridges), heave, pitch & roll is reviewed prior to application to sounds, and finally GPS position holidays can be edited out of the database.

In Phase 2 of multibeam data processing or Sweep Editing, ancillary sensor data is applied to the soundings and individual passes of sounding data. Sounding points can be edited manually or by automatic filters based on angle/offset from nadir; Min/Max depth values; and beam quality.

The final phase of multibeam processing is Area Based. During this phase a series of overlapping multibeam are binned to a regularly spaced matrix. In the final phase, overlap of adjacent sweeps are evaluated to ensure that the bottom profiles align correctly. Additional point reduction was performed to remove flyer points based on statistical analysis of the soundings in each cell of a 3ft x3ft matrix. Final data points files were generated from the phase as A) All sounding points, B) Average sounding for 1ft x 1ft matrix, and C) Average sounding for a 3ft x 3ft matrix.


Overlapping swaths were reviewed and compared for coverage, depth repeatability, accuracy and gaps. Field QC processes were reviewed and tide readings compared and applied to the raw data. GBA's initial single beam cross-section surveys were overlaid with the multi-beam data to ensure accuracy of the data sets. Once the multi-beam data was edited and verified it was formulated into final products, such as contours and binned data. Contours were generated at 0.5 ft intervals and are provided in AutoCad DWG files.

5.0 QUALITY CONTROL/QUALITY ASSURANCE

Prior to the start of the Lower Passaic River Spring 2010 hydrographic survey, GBA performed several quality assurance and quality control procedures. In addition to physically verifying all horizontal and vertical offsets for positioning and sounding equipment the survey crew performed a complete systems operation check in Baltimore Harbor prior to mobilization to NJ.

Sound Velocity Profiles

The sound velocity profiler calibration was verified as per the method proscribed in the US Army Corps of Engineers Engineering and Design Manual EM 1110-2-1003. The profiler was set in a distilled -water bath using ice to vary the water temperature. Observed sound velocity measurements and water temperature



Throughout each survey day, GBA surveyors performed several velocity casts to ensure that tidal variation did not significantly effect the sounding data.

RTK Corrections

To ensure the accuracy and precision of the Leica SmartNet RTK corrections that were received from the NJIT CORS station. GBA used Static GPS observations tied to local NGS monuments to confirm the horizontal and vertical positions of control points set by GBA during the 2007 surveys. Using a back pack rover, GBA made RTK point observations at both NGS monuments and GBA set points receiving corrections from not only the NJIT CORS station as a "single-base" setup but also from the Keystone Keynet VRS service as an independent check. All checks were within tolerances for RTK GPS of +/- 0.5 ft.

Daily checks of the RTK position system were performed by logging the vessel position at the dock at the beginning and end of each day to ensure no horizontal changes. RTK Tides were checked three times; beginning, middle, end by comparing the computed to RTK Tides to analog tide readings at Port, Path, Nutley, and/or CPG dock. All RTK tides checks agreed with analog readings.

Patch Tests

Patch tests; used to determine and correct system bias' for Pitch, Roll, and Yaw, were performed prior to and immediately following the Spring 2010 Hydrographic Survey of the Passaic River. Patch tests were performed in Newark Bay where there was sufficient water depth in the maintained channels for the Roll bias test, and sufficient bottom elevation change/slope to perform the Pitch, Yaw, and Latency tests. Below are the results from the

Results from the June 8, 2010 Pre Survey Patch Test in Newark Bay
Roll - 6/08/2010



Pitch - 6/08/2010

GPS Latency Pitch Roll Yaw

Test Settings and Results

Angle/Time Step	1.00	Adjustment	0.00
Number of Steps	21	Initial Offset	0.70
Cell Size	3.0	Final Offset	0.70

Sonar Head Selection

☒ Head 1
☐ Head 2
☐ Both

Cross Sections: Patch Test Result

Depth Error

Manual Cross Section Vertical Adjustment 0.0 < Previous Next >

Survey

Time and Date	08:58:32 06/08/2010	Project	100608_PatchMB
Boat	Sea Fix	Area	Newark Bay
Surveyor	ECD		

Coarse Steps Medium Steps Fine Steps Start Pitch Test Close

Save Test Patch Test History (Beta)...

Yaw - 6/08/2010

GPS Latency Pitch Roll Yaw

Test Settings and Results

Angle/Time Step	0.50	Adjustment	0.00
Number of Steps	21	Initial Offset	-2.30
Cell Size	3.0	Final Offset	-2.30

Sonar Head Selection

☒ Head 1
☐ Head 2
☐ Both

Cross Sections: Patch Test Result

Depth Error

Manual Cross Section Vertical Adjustment 0.0 < Previous Next >


Survey

Time and Date	08:57:25 06/08/2010	Project	100608_PatchMB
Boat	Sea Fix	Area	Newark Bay
Surveyor	ECD		

Coarse Steps Medium Steps Fine Steps Start Yaw Test Close

Save Test Patch Test History (Beta)...

Latency - 6/08/2010




Results from the June 23, 2010 Post Survey Patch Test in Newark Bay


Roll - 6/23/2010




Pitch - 6/23/2010



Yaw - 6/23/2010



Latency - 6/23/2010




Performance Tests

The multibeam performance test consists of two parts: 1) Beam Angle Test and 2) Single Beam test. The Beam Angle Test compares multibeam check lines to a reference surface and estimates the depth accuracy of the multibeam system at different angle limits. The estimated accuracy can be used to determine if the multibeam system meets survey specifications. Similarly, the Single Beam test provides a statistical comparison of single beam cross-sections to a reference multibeam surface.


Three Performance tests were performed to document the accuracy of the hydrographic survey system. Tests were done prior to survey operations on June 8, 2010, approximately the mid-point of the survey on June 17, 2010 and at the completion of the survey on June 23, 2010. The repeatable results of all the Performance tests show that survey system remained stable in its accuracy and precision through the course of the survey operations.

June 8 2010 Performance Tests

Singlebeam-Multibeam Performance test




Beam Angle




June 17 2010 Performance Tests

Singlebeam-Multibeam Performance test




Beam Angle




June 23 2010 Performance Tests

Singlebeam-Multibeam Performance test




Beam Angle



Single-beam Cross-check Lines

Throughout the course of the survey operations, Gahagan and Bryant collected single beam cross-sections as an checks to compare against multibeam data. Dailey cross check lines spaced at ~500ft intervals and overlain on the multibeam. Below is a typical cross-section showing the consistent correlation between the survey technologies which adds confidence to the 2010 multibeam dataset.



6.0 DAILY OVERVIEW OF SURVEY OPERATIONS

The following information is representative of GBA's Daily Surveying Activities in reference to the multi-beam survey of the Passaic River from mile marker 0 to 14

Week of May 31, 2010

System checks and vessel repairs were performed in Baltimore

June 5, 2010

Survey team, consisting of party chief Ed DeAngelo, USCG Licensed Vessel Captain Travis Schmidt and Surveyor William Carroll mobilized from Baltimore MD to Carteret, New Jersey (4 hours). Survey Vessel SeaFix is launched and moored at the Elizabeth City Marina. Reconnaissance and RTK checks are performed at local NGS monumentation and GBA established control points from 2007. RTK checks were performed using two independent sources of RTK Corrections: 1) Leica Smartnet (NJIT) used for the 2007 & 2008 surveys; and 2) Keystone KeyNet VRS.

June 6, 2010

GBA performed a series of static GPS sessions to tie further the horizontal and vertical position for GBA set monuments, Port, Path, Nutley, CPG to local NGS monuments. These control points were used as RTK tide check points through out the survey operations. Mr. Carroll departed to the job site and returned to Maryland to process the Static GPS sessions

June 7, 2010

Mr. Paul Seaboldt joined the survey crew in NJ. Final system calibrations and equipment offsets were confirmed. GBA performed a preliminary Patch Test in Newark Bay to confirm that all survey systems were fully operational.

June 8, 2010

Jason Magalan from Sea Engineering and John Gaskin from AECOM joined the survey team. Final Patch and Performance Tests were conducted in Newark Bay. Additional testing was also done by collecting multi-beam and single beam data in a reference area of the Hudson River that is constantly utilized by the NYD for their QC/QA checks.

June 9, 2010

Final checking of the GBA Trimble GPS systems using corrections from Leica Smartnet service NJIT CORS station was performed at NGS Monument AI7779. A tide board was installed adjacent at RM 2.25 in the vicinity of reference point PORT that will be utilized for daily tide checks during surveys of the lower half of the river. Multi-beam survey operations commenced. Area A01 adjacent to the Hess Oil tank facility at the mouth of the Passaic River was completed

June 10, 2010

Survey data were collected in Areas A02, A03, A04 RM 1.5 was completed on the evening high tide, with shallow water areas on the eastern side of A02 & A03 remaining

June 11, 2010

Jason Magalan departed the survey area this date. Survey data were collected in Areas A02-A07. The shallow ends of Areas A02 & A03 were completed, while center stretches of areas A05, A06, and A07 were surveyed during lower tide levels. Single beam cross-sections 59 and 78 were surveyed this day.

June 12, 2010

John Gaskin departed for Houston. Survey Areas A05-A07 were completed (RM 2.25 complete) while center sections of Areas A08 and B01 were surveyed (underneath the RR Bridge and NJ Turnpike Bridge (RM 2.5). Single beam cross –lines 59, 78, and 104 were surveyed this date.

June 13, 2010

Areas A08, B01 and B02 were completed RM (3.25) and center sections of Area B03 were surveyed (RM 3.4). Single beam cross-sections 104, and 148 were surveyed this date.

June 14, 2010

No surveys were performed on this date for due to mechanical repairs and maintenance.

June 15, 2010

Survey data were collected in Areas B03 thru B06. All areas were completed up the Jackson St Bridge (RM 4.3). Single beam cross-sections 148, 153, 178, and 192 were surveyed this date.

June 16, 2010

Survey data were collected in Areas B07 thru C02. All sections between the Jackson St Bridge and the Bridge St. have been completed (~RM 5.5). Single beam cross-sections 204, and 235 were surveyed this date.

June 17, 2010

Mid Survey Multibeam performance test was conducted in Newark Bay. Survey data were collected in Areas C03 – C08 completing up to RM 7.0.

June 18, 2010

Additional survey data collected underneath the Clay St bridge in Area C04. Areas C09 through D01 . To complete the upper sections of the river, the survey vessel SeaFix was moored at the CPG floating dock on Madison Street, East Rutherford (RM 13)

June 19, 2010

Additional lines were surveyed in Area D01. Areas D02 through D04 (RM 8.6) were completed. During the afternoon high tide, shallow edges of Areas D06 through D09 (~RM 9.7).were surveyed

June 20, 2010

–Completed additional edge in area D05 on the south side of the Bellville Bridge. Survey sections D06 through F01 were completed the Park Ave Bridge (~ RM 10.3)

June 21, 2010

Resurveyed area F01 based on the review of the previous days suggested that multi-pathing GPS returns from adjacent building adversely affected the sounding data. Cleaned up some data caps in E01 and completed Areas F02 through G04

June 22, 2010

Completed surveys of Areas H01 through H09. While performing near shoreline surveys during the evening high tide, the multibeam transducer head bumped a rock projecting from the bottom during a slow speed turn. The bottom profile in the upper reaches of the river were not suitable for a complete patch test, but the Roll component was immediately tested by running reciprocal passes in the center of the channel. Based on those results ; a small change in the Roll bias was applied to the system configuration and survey operations resumed. Note* final close patch tests conducted the following day 6/23/10 in Newark Bay confirmed these settings.

June 23, 2010

Mr. John Gaskin from AECOM joined the survey crew this day. They completed the regular survey of by finishing Areas H10 through H12. Additional reference points were observed near AECOM's water level gages at the Myrtle Ave Bridge near RM 13.5 and at the abandoned Rail Road Crossing near RM 1. Additional survey data were collected in A05 and A08 and final Patch and Performance tests were performed in Newark Bay

June 24, 2010

Survey equipment was secured and Survey Crew and vessel demobilized to Baltimore MD

7.0 CONTACT INFORMATION

Gahagan & Bryant Associates, Inc.
5803 Kennett Pike, Suite D
Centerville Square
Wilmington, DE 19807
Office: (302) 652-4948
Fax: (302) 655-9218

Survey Manager:

Douglas Moore email: dcmoore@gba-inc.com

Technical Project Manager:

Edward DeAngelo email: edeangelo@gba-inc.com

APPENDIX 1

Control Monuments

9C1

NGS PID# KV6837

New Jersey Geodetic Survey (NJGS) Disk – stamped 9 C 1 1992

New Jersey State Plane NAD 83 Horizontal Coordinates (feet)

 Northing 666,572.73 Easting 594,085.07

Vertical Elevation (Observed)

 NAVD 88 = 7.202' NGVD 29 = 7.202'

Situated in the Bayonne, New Jersey City Park, this control monument is located 95.4 feet northwest of the southwesternmost corner of the chainlink fence surrounding the tennis courts. It is further located 8 feet northeast of the edge of a paved parking lot situated on the southern end of the City Park, near Newark Bay. Static GPS observations were performed from here to help establish horizontal positioning for the survey project.



188.12 NJGS

NGS PID# KV0135

Chiseled Cross in marble sill

New Jersey State Plane NAD 83 Horizontal Coordinates (feet) ***SCALED***

 Northing 732799 Easting 606324

Vertical Elevation

 NAVD 88 = 187.48'

 NGVD 29 = 188.50'

Situated in Woodridge, New Jersey, this control point is a chiseled cross on top of a marble sill of a basement window found along the southeasternmost side of the Mount Pleasant School building, located at the southwest corner of the intersection of Union and Hackensack Streets. A closed level loop was run from this point to 188.12A for Static GPS observations.



188.12-A

Locally Set Control Point

MAG Nail Set

New Jersey State Plane NAD 83 Horizontal Coordinates (feet)

 Northing 732846.821 Easting 606378.233

Vertical Elevation (Observed)

 NAVD 88 = 188.470' NGVD 29 = 188.49'

Situated in Woodridge, New Jersey, this control point is a MAG Nail set in the expansion joint of a 7' wide concrete sidewalk along the southeast side of Humboldt Avenue. It is located directly across the street from the Woodridge Fire Department and is measured 55.8' southwest of utility pole #60667-WB. It is further measured 68.9' northeast from an unidentified utility pole. A closed level loop was run to this point from 188.12 NJGS to establish a vertical control for static GPS observations.



01392590 A (AI7796)

NGS PID# AI7796

New Jersey Geodetic Survey (NJGS) Cover – stamped 01392590 1997 (steel rod in casing)

New Jersey State Plane NAD 83 Horizontal Coordinates (feet)

Northing	692,097.66	Easting	588,059.00
----------	------------	---------	------------

Vertical Elevation

NAVD 88 = 11.67'	NGVD 29 = 12.78'
------------------	------------------

Situated in the city of Newark, New Jersey, this control point is a steel rod buried in the ground and encased with a lid as stamped above. The marker is located on the east side of Raymond Avenue at the intersection of Van Buren Street. It is measured 32' northeasterly from a light pole and 21' southeasterly from a concrete wall situated on the east side of a concrete walk leading northerly along the exit ramp from Raymond Avenue. Static GPS observations were made from this point to establish horizontal and vertical positioning for the survey project.




CPG

Locally Set Control Point
Triangle carved on top of steel bulkhead
Vertical Elevation (Observed)
NAVD 88 = 8.18'

NGVD 29 = 9.19'

Situated in Wallington, New Jersey, this control point is a triangle chiseled into the top of a steel bulkhead along the east side of the Passaic River. The bulkhead is located on the west side of a parking lot for a business center located on the west side of Madison Street. The mark is measured 17.3' northerly from a light pole and is adjacent to a floating dock. A closed level loop was run from CPG2, situated just north of this point, where static GPS observations were made.



CPG2

Locally Set Control Point

MAG Nail Set

New Jersey State Plane NAD 83 Horizontal Coordinates (feet)

 Northing 733825.441 Easting 597109.293

Vertical Elevation (Observed)

 NAVD 88 = 7.936' NGVD 29 = 8.950'

Situated in Wallington, New Jersey, this control point is a MAG Nail set into asphalt near a steel bulkhead along the east side of the Passaic River. The bulkhead is located on the west side of a parking lot for a business center located on the west side of Madison Street. The mark is measured 8.6' northerly from a light pole and is situated along the west side of a guard rail. Static GPS observations were made at this point and a closed level loop was run to control point CPG situated just south of this location.



G101

NGS PID# KV3414

National Geodetic Survey (NGS) Disk – stamped G 101 1979

New Jersey State Plane NAD 83 Horizontal Coordinates (feet)

 Northing 715490.263 Easting 592312.818

Vertical Elevation

 NAVD 88 = 14.24' NGVD 29 = 15.29'

Situated in North Arlington, New Jersey, this control monument is located along the southeast side of River Road in the front yard of house #352. It is further located 2.0' southwest of the southwesternmost side of an asphalt driveway leading to house #354. The mark is measured 6.7' east of utility pole #A60351 NA and 12.2' northwest of the guy anchor attached to the pole. Static GPS observations were made from this point to establish horizontal and vertical positioning for the survey project.



Nutley

Locally Set Control Point

Mark at edge of Concrete Wall

Vertical Elevation (Observed)

NAVD 88 = 8.73'

NGVD 29 = 9.77'

Situated in Nutley, New Jersey, this control point is a mark chiseled on top of a concrete wall along the eastern edge as it abuts the west side of the Passaic River. The concrete wall is situated along the west side of a parking area for a boat ramp. Boat Ramp is located just north of Park Avenue where it connects with the Kingsland Avenue Bridge leading to the east side of the river. A closed level loop was run from Nutley2, situated south of this point, where static GPS observations were made.



Nutley 2

Locally Set Control Point

Capped Iron Pin Set

New Jersey State Plane NAD 83 Horizontal Coordinates (feet)

Northing	720714.538	Easting	592028.699
----------	------------	---------	------------

Vertical Elevation (Observed)

NAVD 88 = 7.952'	NGVD 29 = 8.992'
------------------	------------------

Situated in Nutley, New Jersey, this control point is a capped iron pin set in a gravel parking lot and boat ramp situated along the west side of the Passaic River. Boat Ramp is located just north of Park Avenue where it connects to the Kingsland Avenue Bridge leading to the east side of the river. The point is located 3' westerly from the west edge of a concrete wall along the river and 3' northwesterly of a concrete curb. Static GPS observations were made at this point and a closed level loop was run to control point Nutley situated just north of this position.



Path

PSE & G Disk – stamped PRO 4 (Passaic River Outfall #4)
New Jersey State Plane NAD 83 Horizontal Coordinates (feet)
 Northing 701845.995 Easting 585643.039
Vertical Elevation (Observed)
 NAVD 88 = 5.705' NGVD 29 = 6.791'

Situated in Kearney, New Jersey, this control point is a PSE & G control disk embedded in a concrete flume leading westward from a parking lot into the east side of the Passaic River. The parking lot is situated south of a PathMark grocery store located along the west side of Passaic Avenue. The point is measured 7'0" northerly from the south edge of the concrete flume and 3.5' easterly from a guard rail. Static GPS observations were made here and a closed level loop was run to PATH 3 situated north of this position.



Path 3

Locally Set Control Point

Triangle cut chiseled on top of concrete bulkhead

Vertical Elevation (Observed)

NAVD 88 = 6.105'

NGVD 29 = 7.191'

Situated in Kearney, New Jersey, this control point is a triangle cut chiseled into the top of a concrete bulkhead situated along the east side of the Passaic River. The mark is located to the rear of a PathMark grocery store located on the west side of Passaic Avenue and is measured 35' northeasterly of a large cleat and 20' southwesterly of another large cleat. It is further measured 14.5' northwesterly of the westernmost corner of a storm drain.



Port1

Locally Set Control Point

Sheared Metal Bolt

New Jersey State Plane NAD 83 Horizontal Coordinates (feet)

 Northing 720714.538 Easting 592028.699

Vertical Elevation (Observed)


 NAVD 88 = 8.96' NGVD 29 = 10.08'

Situated near Kearney, New Jersey, this control point is a sheared metal bolt located on a concrete dauphin situated in the Passaic River west of a New York-New Jersey Shipping Authority facility located at the westernmost end of Pennsylvania Avenue. It is measured 6.6' northeast of the southwest side of the dauphin. It is further measured 5.3 feet northwest of the southeast side of the dauphin. Static GPD observations were made here and a closed level loop was run to Port2 situated along the southeasternmost edge of the dauphin.



APPENDIX 2

0.5ft Contour plots of Multibeam Data



PASSAIC RIVER CHANNEL COORDINATES NEW JERSEY 2900 (NAD83)		
POINTS	NORTHING	EASTING
L1	682542.887	597361.513
P2	684590.032	596672.900
P3	686153.214	596612.480
P4	686534.479	596618.000
P5	688517.796	596958.499
1A	690982.349	597710.661
L2	692533.543	597681.148
S2	684644.754	596970.983
S3	686156.819	596912.537
S4	686506.746	596917.650
S5	688446.365	597250.941
5c	690910.916	598002.492
6c	692220.027	598245.986
7	693351.681	598417.051
8	694256.342	598336.009
9	695039.548	597919.516
10	695446.436	597207.736
11	695741.718	596621.785
12	695750.454	595469.021
13	695507.670	593138.941
14	695163.223	597168.401
19new	694755.021	591428.294
15a	694407.610	591095.796
16c	693279.203	590551.391
17c	693052.604	590327.812
17c	692828.831	590046.095
17a	692650.726	589601.402
18	692471.444	587650.574
18b	692172.128	587649.390
17b	692382.719	589966.756
16b2	692591.112	590682.327
15c	694231.561	591342.524
15d	694516.760	591615.482
14b2	694908.360	597292.724
13b	695212.727	593202.789
12b	695450.364	595483.472
11c	695444.181	596298.984
11a	695329.867	596772.228
10b	695182.076	597065.749
9a	694733.869	597742.319
8b	694169.105	598042.649
7b	693360.847	598115.056
2a	692269.886	597950.142
19	692510.765	587070.412
20	692651.290	586748.897
21	692802.987	586474.247
23	693692.635	585745.200
24	694842.681	584876.381
25	697350.452	584828.042
26	699351.781	585117.775
27	701029.575	585356.576
27a	701355.763	585388.391
28	702495.693	585923.986
29	703393.838	586579.723
29a	703417.421	586547.419
30	704101.299	587081.482
31	704847.519	587323.246
31b	704862.551	587124.380

PASSAIC RIVER CHANNEL COORDINATES NEW JERSEY 2900 (NAD83)		
POINTS	NORTHING	EASTING
30b	704196.485	586902.122
29b	703535.406	586385.820
29c	703570.721	586337.450
28b	702649.365	585664.759
27d	701463.740	585107.272
27e	701083.910	585000.954
26b	699389.199	584820.091
25b	697363.002	584526.768
24b	696489.036	584579.699
23b	693565.378	584570.383
21b	692560.228	584293.195
20b	692378.086	584624.145
19b	692236.119	587001.711
32	705723.717	587354.325
33	708145.567	587536.429
34	707947.745	589132.861
34a	707958.669	589119.803
35	708709.886	589584.829
36	709048.052	589640.225
37	709870.310	589530.674
38	710645.885	589493.325
39	711131.038	589580.724
40	712811.013	590385.769
41	713791.993	591108.369
41b	713872.363	590981.285
40b	712889.182	590257.064
39b	711175.483	589414.966
38b	710652.581	589342.864
37b	709856.774	589381.165
36b	709050.320	589488.610
35a	708903.215	589464.512
34a	708114.608	589443.944
33a	707003.330	588029.103
33b	706254.212	587365.509
32b	705768.419	587135.802
U1	695148.721	597728.538
U2	694888.297	597579.665
21A	693003.099	586291.353
22A	693410.916	585926.424
23c	693408.204	585571.485
23D	693297.666	585760.281
21D	693080.065	585944.315
21c	692799.038	586051.065
101b	740121.286	599929.871
101	740250.293	600006.378
100b	739849.961	600387.393
100	739962.037	600492.449
99	739403.421	600874.558
98b	739100.713	600728.890
98b	738794.278	600781.592
98	738798.594	600931.841
97	737683.849	600690.987
96	737033.296	600857.790
95	736772.744	600438.733
94	736652.194	600249.150
75b	735123.472	597271.287
74b	735791.335	597378.271
73x	735135.471	597338.616

PASSAIC RIVER CHANNEL COORDINATES NEW JERSEY 2900 (NAD83)		
POINTS	NORTHING	EASTING
72x	733670.754	596848.894
69x	732155.318	596580.549
83	738324.076	598073.089
84	738336.665	598653.014
85	73217.934	598653.014
86	737988.914	599154.542
87	737849.232	599225.160
88	737579.468	599271.344
89	737314.355	599237.523
90	737029.410	599258.280
91	736859.642	599338.751
92	736655.365	599594.251
93	736590.942	599799.382
97b	737712.558	600741.560
96b	737108.185	600525.649
95b	736886.928	600338.780
94b	736796.378	600196.378
93b	736744.079	599812.349
92b	736790.049	599665.979
91b	736955.168	599459.439
90b	737068.288	599405.833
89b	737210.275	599368.205
88b	737582.704	599422.959
87b	737896.775	599369.191
86b	738076.008	599278.580
85b	738344.133	599025.682
84b	738487.303	598681.391
83b	738473.636	598251.838
69	73214.115	598728.783
72	733599.937	596983.365
73	735106.673	597487.135
74	735801.764	597528.162
75	736361.229	597416.685
67	731022.018	596202.665
68	731873.857	596665.924
68x	731928.455	596524.884
67b	731067.293	596056.555
66b	730656.096	596014.098
65b	730221.437	596134.888
64b	729823.820	596375.442
63b	729177.922	596552.109
62	728435.319	596945.066
61b	727880.299	596935.522
60b	727422.499	596876.690
59d	725121.453	596320.874
59b	725014.969	596268.648
58b	724565.994	595921.367
57b	724223.168	595565.761
42	715218.587	591886.532
43	715782.428	592273.957
44	716157.003	592402.187
47	716654.549	592750.987
51	720551.577	592503.624
52	721191.290	592283.660
55	723303.636	593146.827
56	723813.197	593054.081
57	724095.927	593549.880
58	724465.520	596033.250

PASSAIC RIVER CHANNEL COORDINATES NEW JERSEY 2900 (NAD83)		
POINTS	NORTHING	EASTING
60	727395.251	597024.409
61	727869.415	597085.344
62	728471.344	597095.716
63	728233.453	596892.417
64	728581.564	596514.596
65	730281.446	596273.882
66	730668.917	596166.207
59c	724935.611	596397.910
59a	725070.771	596462.932
56b	723984.955	595004.185
51a	720606.352	592071.417
50b	719683.076	592086.645
49b	719065.702	591988.471
45b	718504.004	592223.076
44b	716175.921	592250.151
43b	715851.792	592139.141
42b	715320.018	591758.943
52b	721202.501	592133.250
77w	736931.419	597171.325
78w	737239.883	597278.578
79w	737955.155	597405.842
80w	738104.726	597468.383
81w	738233.502	597561.686
82w	738337.880	597681.911
83w	738412.497	597822.555
75e	736678.390	597315.184
71e	736897.061	597318.222
78e	737201.813	597425.773
79e	737915.317	597550.598
80e	738030.368	597599.438
81e	738131.463	597672.938
82e	738213.405	597767.320
83e	738271.983	597877.732
70a	732614.977	596800.940
69a	732324.898	596776.601
A9	718742.251	592015.159
45a	718533.276	592371.158
A4	717654.646	592014.364
A3	718099.679	591937.994
A2	718370.096	591928.682
43a	718024.259	592133.752
B1	718657.424	591816.776
B2	718377.782	591778.341
72b	718084.340	591788.446
69c	732349.189	596628.125
72a	733566.052	596972.032
72b	737682.536	597275.728
52c	721966.736	592425.070
53a	722834.578	592660.037
54a	723115.369	592852.724
55c	723441.918	593084.648
54c	723225.300	592746.258
53c	722898.404	592521.931
52d	721999.847	592278.647

MULTIBEAM HYDROGRAPHIC SURVEY OF
PASSAIC RIVER

RIVER MILE 0.0 TO 14.3

Drawing Date: 27 JULY 2010
Drawn By: J. Drake
Checked By: E. DeAngelo
Drawing Name: PR2010_SHEET01.DWG
Drawing Scale: 1" = 1,000'
Sheet Number: 1 OF 17

CONDITION SURVEY
Survey Date: 9 JUNE 2010 - 23 JUNE 2010
Horizontal Projection: U.S. State Plane, NAD 83
Zone: New Jersey - 2900
Vertical Reference: NGVD29
Survey Units: U.S. Survey Feet

NOTES:
1. THE INFORMATION DEPICTED ON THIS MAP REPRESENTS THE RESULTS OF SURVEYS MADE ON THE DATES SHOWN AND CAN ONLY BE CONSIDERED AS INDICATING THE GENERAL CONDITION EXISTING AT THAT TIME.
2. THE DIGITAL ORTHOPHOTOGRAPHY SHOWN WAS PUBLISHED IN 2007-2008 BY THE NEW JERSEY OFFICE OF INFORMATION TECHNOLOGY.

GAHAGAN & BRYANT ASSOCIATES, INC.
5803 KENNETT PIKE, SUITE D
CENTREVILLE SQUARE
WILMINGTON, DELAWARE 19807-1195
TEL. 302.652.4948 FAX. 302.655.9218
WILMINGTON@GBA-INC.COM





MULTIBEAM HYDROGRAPHIC SURVEY OF
PASSAIC RIVER

RIVER MILE 0.0 TO 0.5

Drawing Date:	27 JULY 2010
Drawn By:	J. Drake
Checked By:	E. DeAngelo
Drawing Name:	PR2010_SHEET02.DWG
Drawing Scale:	1" = 200'
Sheet Number:	2 OF 17

CONDITION SURVEY	
Survey Date:	9 JUNE 2010 - 23 JUNE 2010
Horizontal Projection:	U.S. State Plane, NAD 83
Zone:	New Jersey - 2900
Vertical Reference:	NGVD29
Survey Units:	U.S. Survey Feet

- NOTES:
1. THE INFORMATION DEPICTED ON THIS MAP REPRESENTS THE RESULTS OF SURVEYS MADE ON THE DATES SHOWN AND CAN ONLY BE CONSIDERED AS INDICATING THE GENERAL CONDITION EXISTING AT THAT TIME.
 2. THE DIGITAL ORTHOPHOTOGRAPHY SHOWN WAS PUBLISHED IN 2007-2008 BY THE NEW JERSEY OFFICE OF INFORMATION TECHNOLOGY.

GAHAGAN & BRYANT ASSOCIATES, INC.
5803 KENNETT PIKE, SUITE D
CENTREVILLE SQUARE
WILMINGTON, DELAWARE 19807-1195
TEL. 302.652.4948 FAX. 302.655.9218
WILMINGTONDE@GBA-INC.COM





MULTIBEAM HYDROGRAPHIC SURVEY OF
PASSAIC RIVER

RIVER MILE 0.5 TO 1.7

Drawing Date:	27 JUNE 2010
Drawn By:	J. Drake
Checked By:	E. DeAngelo
Drawing Name:	PR2010_SHEET03.DWG
Drawing Scale:	1" = 200'
Sheet Number:	3 OF 17

CONDITION SURVEY	
Survey Date:	9 JUNE 2010 - 23 JUNE 2010
Horizontal Projection:	U.S. State Plane, NAD 83
Zone:	New Jersey - 2900
Vertical Reference:	NGVD29
Survey Units:	U.S. Survey Feet

- NOTES:
1. THE INFORMATION DEPICTED ON THIS MAP REPRESENTS THE RESULTS OF SURVEYS MADE ON THE DATES SHOWN AND CAN ONLY BE CONSIDERED AS INDICATING THE GENERAL CONDITION EXISTING AT THAT TIME.
 2. THE DIGITAL ORTHOPHOTOGRAPHY SHOWN WAS PUBLISHED IN 2007-2008 BY THE NEW JERSEY OFFICE OF INFORMATION TECHNOLOGY.

GAHAGAN & BRYANT ASSOCIATES, INC.
5803 KENNETT PIKE, SUITE D
CENTREVILLE SQUARE
WILMINGTON, DELAWARE 19807-1195
TEL. 302.652.4948 FAX. 302.655.9218
WILMINGTONDE@GBA-INC.COM

GBA
ENGINEERS ★ SURVEYORS



MULTIBEAM HYDROGRAPHIC SURVEY OF PASSAIC RIVER	Drawing Date:	27 JUNE 2010	CONDITION SURVEY	NOTES: 1. THE INFORMATION DEPICTED ON THIS MAP REPRESENTS THE RESULTS OF SURVEYS MADE ON THE DATES SHOWN AND CAN ONLY BE CONSIDERED AS INDICATING THE GENERAL CONDITION EXISTING AT THAT TIME. 2. THE DIGITAL ORTHOPHOTOGRAPHY SHOWN WAS PUBLISHED IN 2007-2008 BY THE NEW JERSEY OFFICE OF INFORMATION TECHNOLOGY.	GAHAGAN & BRYANT ASSOCIATES, INC. 5803 KENNETT PIKE, SUITE D CENTREVILLE SQUARE WILMINGTON, DELAWARE 19807-1195 TEL. 302.652.4948 FAX. 302.655.9218 WILMINGTONDE@GBA-INC.COM	
	Drawn By:	J. Drake				
RIVER MILE 1.7 TO 3.1	Checked By:	E. DeAngelo	Horizontal Projection:	U.S. State Plane, NAD 83		
	Drawing Name:	PR2010_SHEET04.DWG	Zone:	New Jersey - 2900		
	Drawing Scale:	1" = 200'	Vertical Reference:	NGVD29		
	Sheet Number:	4 OF 17	Survey Units:	U.S. Survey Feet		



MULTIBEAM HYDROGRAPHIC SURVEY OF
PASSAIC RIVER

RIVER MILE 3.1 TO 4.4

Drawing Date:	27 JUNE 2010
Drawn By:	J. Drake
Checked By:	E. DeAngelo
Drawing Name:	PR2010_SHEET05.DWG
Drawing Scale:	1" = 200'
Sheet Number:	5 OF 17

CONDITION SURVEY	
Survey Date:	9 JUNE 2010 - 23 JUNE 2010
Horizontal Projection:	U.S. State Plane, NAD 83
Zone:	New Jersey - 2900
Vertical Reference:	NGVD29
Survey Units:	U.S. Survey Feet

- NOTES:
1. THE INFORMATION DEPICTED ON THIS MAP REPRESENTS THE RESULTS OF SURVEYS MADE ON THE DATES SHOWN AND CAN ONLY BE CONSIDERED AS INDICATING THE GENERAL CONDITION EXISTING AT THAT TIME.
 2. THE DIGITAL ORTHOPHOTOGRAPHY SHOWN WAS PUBLISHED IN 2007-2008 BY THE NEW JERSEY OFFICE OF INFORMATION TECHNOLOGY.

GAHAGAN & BRYANT ASSOCIATES, INC.
5803 KENNETT PIKE, SUITE D
CENTREVILLE SQUARE
WILMINGTON, DELAWARE 19807-1195
TEL. 302.652.4948 FAX. 302.655.9218
WILMINGTON@GBA-INC.COM





MULTIBEAM HYDROGRAPHIC SURVEY OF PASSAIC RIVER		RIVER MILE 4.4 TO 5.6	
Drawing Date:	27 JUNE 2010	CONDITION SURVEY	
Drawn By:	J. Drake	Survey Date:	9 JUNE 2010 - 23 JUNE 2010
Checked By:	E. DeAngelo	Horizontal Projection:	U.S. State Plane, NAD 83
Drawing Name:	PR2010_SHEET06.DWG	Zone:	New Jersey - 2900
Drawing Scale:	1" = 200'	Vertical Reference:	NGVD29
Sheet Number:	6 OF 17	Survey Units:	U.S. Survey Feet
		NOTES:	
		1. THE INFORMATION DEPICTED ON THIS MAP REPRESENTS THE RESULTS OF SURVEYS MADE ON THE DATES SHOWN AND CAN ONLY BE CONSIDERED AS INDICATING THE GENERAL CONDITION EXISTING AT THAT TIME.	
		2. THE DIGITAL ORTHOPHOTOGRAPHY SHOWN WAS PUBLISHED IN 2007-2008 BY THE NEW JERSEY OFFICE OF INFORMATION TECHNOLOGY.	
		GAHAGAN & BRYANT ASSOCIATES, INC. 5803 KENNETT PIKE, SUITE D CENTREVILLE SQUARE WILMINGTON, DELAWARE 19807-1195 TEL. 302.652.4948 FAX. 302.655.9218 WILMINGTONDE@GBA-INC.COM	
		GBA ENGINEERS ★ SURVEYORS	



MULTIBEAM HYDROGRAPHIC SURVEY OF
PASSAIC RIVER

RIVER MILE 5.6 TO 6.9

Drawing Date:	27 JUNE 2010
Drawn By:	J. Drake
Checked By:	E. DeAngelo
Drawing Name:	PR2010_SHEET07.DWG
Drawing Scale:	1" = 200'
Sheet Number:	7 OF 17

CONDITION SURVEY	
Survey Date:	9 JUNE 2010 - 23 JUNE 2010
Horizontal Projection:	U.S. State Plane, NAD 83
Zone:	New Jersey - 2900
Vertical Reference:	NGVD29
Survey Units:	U.S. Survey Feet

- NOTES:
1. THE INFORMATION DEPICTED ON THIS MAP REPRESENTS THE RESULTS OF SURVEYS MADE ON THE DATES SHOWN AND CAN ONLY BE CONSIDERED AS INDICATING THE GENERAL CONDITION EXISTING AT THAT TIME.
 2. THE DIGITAL ORTHOPHOTOGRAPHY SHOWN WAS PUBLISHED IN 2007-208 BY THE NEW JERSEY OFFICE OF INFORMATION TECHNOLOGY.

GAHAGAN & BRYANT ASSOCIATES, INC.
5803 KENNETT PIKE, SUITE D
CENTREVILLE SQUARE
WILMINGTON, DELAWARE 19807-1195
TEL. 302.652.4948 FAX. 302.655.9218
WILMINGTONDE@GBA-INC.COM






MULTIBEAM HYDROGRAPHIC SURVEY OF PASSAIC RIVER RIVER MILE 6.9 TO 8.2	<table border="1"><tr><td>Drawing Date:</td><td>27 JULY 2010</td></tr><tr><td>Drawn By:</td><td>J. Drake</td></tr><tr><td>Checked By:</td><td>E. DeAngelo</td></tr><tr><td>Drawing Name:</td><td>PR2010_SHEET08.DWG</td></tr><tr><td>Drawing Scale:</td><td>1" = 200'</td></tr><tr><td>Sheet Number:</td><td>8 OF 17</td></tr></table>	Drawing Date:	27 JULY 2010	Drawn By:	J. Drake	Checked By:	E. DeAngelo	Drawing Name:	PR2010_SHEET08.DWG	Drawing Scale:	1" = 200'	Sheet Number:	8 OF 17	<table border="1"><tr><td colspan="2">CONDITION SURVEY</td></tr><tr><td>Survey Date:</td><td>9 JUNE 2010 - 23 JUNE 2010</td></tr><tr><td>Horizontal Projection:</td><td>U.S. State Plane, NAD 83</td></tr><tr><td>Zone:</td><td>New Jersey - 2900</td></tr><tr><td>Vertical Reference:</td><td>NGVD29</td></tr><tr><td>Survey Units:</td><td>U.S. Survey Feet</td></tr></table>	CONDITION SURVEY		Survey Date:	9 JUNE 2010 - 23 JUNE 2010	Horizontal Projection:	U.S. State Plane, NAD 83	Zone:	New Jersey - 2900	Vertical Reference:	NGVD29	Survey Units:	U.S. Survey Feet	<p>NOTES:</p> <p>1. THE INFORMATION DEPICTED ON THIS MAP REPRESENTS THE RESULTS OF SURVEYS MADE ON THE DATES SHOWN AND CAN ONLY BE CONSIDERED AS INDICATING THE GENERAL CONDITION EXISTING AT THAT TIME.</p> <p>2. THE DIGITAL ORTHOPHOTOGRAPHY SHOWN WAS PUBLISHED IN 2007-2008 BY THE NEW JERSEY OFFICE OF INFORMATION TECHNOLOGY.</p>	<p>GAHAGAN & BRYANT ASSOCIATES, INC. 5803 KENNETT PIKE, SUITE D CENTREVILLE SQUARE WILMINGTON, DELAWARE 19807-1195 TEL. 302.652.4948 FAX. 302.655.9218 WILMINGTONDE@GBA-INC.COM</p> <p>GBA ENGINEERS ★ SURVEYORS</p>
	Drawing Date:	27 JULY 2010																										
Drawn By:	J. Drake																											
Checked By:	E. DeAngelo																											
Drawing Name:	PR2010_SHEET08.DWG																											
Drawing Scale:	1" = 200'																											
Sheet Number:	8 OF 17																											
CONDITION SURVEY																												
Survey Date:	9 JUNE 2010 - 23 JUNE 2010																											
Horizontal Projection:	U.S. State Plane, NAD 83																											
Zone:	New Jersey - 2900																											
Vertical Reference:	NGVD29																											
Survey Units:	U.S. Survey Feet																											



MULTIBEAM HYDROGRAPHIC SURVEY OF PASSAIC RIVER	Drawing Date:	27 JULY 2010	CONDITION SURVEY	NOTES: 1. THE INFORMATION DEPICTED ON THIS MAP REPRESENTS THE RESULTS OF SURVEYS MADE ON THE DATES SHOWN AND CAN ONLY BE CONSIDERED AS INDICATING THE GENERAL CONDITION EXISTING AT THAT TIME. 2. THE DIGITAL ORTHOPHOTOGRAPHY SHOWN WAS PUBLISHED IN 2007-2008 BY THE NEW JERSEY OFFICE OF INFORMATION TECHNOLOGY.	GAHAGAN & BRYANT ASSOCIATES, INC. 5803 KENNETT PIKE, SUITE D CENTREVILLE SQUARE WILMINGTON, DELAWARE 19807-1195 TEL. 302.652.4948 FAX. 302.655.9218 WILMINGTONDE@GBA-INC.COM	
	Drawn By:	J. Drake				
RIVER MILE 8.2 TO 9.5	Checked By:	E. DeAngelo	Horizontal Projection:	U.S. State Plane, NAD 83		
	Drawing Name:	PR2010_SHEET09.DWG	Zone:	New Jersey - 2900		
	Drawing Scale:	1" = 200'	Vertical Reference:	NGVD29		
	Sheet Number:	9 OF 17	Survey Units:	U.S. Survey Feet		



MULTIBEAM HYDROGRAPHIC SURVEY OF PASSAIC RIVER	Drawing Date: 27 JULY 2010	CONDITION SURVEY	NOTES: 1. THE INFORMATION DEPICTED ON THIS MAP REPRESENTS THE RESULTS OF SURVEYS MADE ON THE DATES SHOWN AND CAN ONLY BE CONSIDERED AS INDICATING THE GENERAL CONDITION EXISTING AT THAT TIME. 2. THE DIGITAL ORTHOPHOTOGRAPHY SHOWN WAS PUBLISHED IN 2007-2008 BY THE NEW JERSEY OFFICE OF INFORMATION TECHNOLOGY.	<div>GAHAGAN & BRYANT ASSOCIATES, INC. 5803 KENNETT PIKE, SUITE D CENTREVILLE SQUARE WILMINGTON, DELAWARE 19807-1195 TEL. 302.652.4948 FAX. 302.655.9218 WILMINGTONDE@GBA-INC.COM</div> <div> ENGINEERS ★ SURVEYORS</div>
	Drawn By: J. Drake	Survey Date: 6 JUNE 2010 - 23 JUNE 2010		
Checked By: E. DeAngelo	Horizontal Projection: U.S. State Plane, NAD 83			
Drawing Name: PR2010_SHEET10.DWG	Zone: New Jersey - 2900			
Drawing Scale: 1" = 200'	Vertical Reference: NGVD29			
Sheet Number: 10 OF 17	Survey Units: U.S. Survey Feet			



MULTIBEAM HYDROGRAPHIC SURVEY OF
PASSAIC RIVER

RIVER MILE 10.6 TO 11.4

Drawing Date:	27 JULY 2010
Drawn By:	J. Drake
Checked By:	E. DeAngelo
Drawing Name:	PR2010_SHEET11.DWG
Drawing Scale:	1" = 200'
Sheet Number:	11 OF 17

CONDITION SURVEY	
Survey Date:	6 JUNE 2010 - 23 JUNE 2010
Horizontal Projection:	U.S. State Plane, NAD 83
Zone:	New Jersey - 2900
Vertical Reference:	NGVD29
Survey Units:	U.S. Survey Feet

NOTES:

1. THE INFORMATION DEPICTED ON THIS MAP REPRESENTS THE RESULTS OF SURVEYS MADE ON THE DATES SHOWN AND CAN ONLY BE CONSIDERED AS INDICATING THE GENERAL CONDITION EXISTING AT THAT TIME.
2. THE DIGITAL ORTHOPHOTOGRAPHY SHOWN WAS PUBLISHED IN 2007-2008 BY THE NEW JERSEY OFFICE OF INFORMATION TECHNOLOGY.

GAHAGAN & BRYANT ASSOCIATES, INC.
5803 KENNETT PIKE, SUITE D
CENTREVILLE SQUARE
WILMINGTON, DELAWARE 19807-1195
TEL. 302.652.4948 FAX. 302.655.9218
WILMINGTONDE@GBA-INC.COM



MULTIBEAM HYDROGRAPHIC SURVEY OF
PASSAIC RIVER

RIVER MILE 11.4 TO 12.7

Drawing Date:	27 JULY 2010
Drawn By:	J. Drake
Checked By:	E. DeAngelo
Drawing Name:	PR2010_SHEET12.DWG
Drawing Scale:	1" = 200'
Sheet Number:	12 OF 17

CONDITION SURVEY	
Survey Date:	6 JUNE 2010 - 23 JUNE 2010
Horizontal Projection:	U.S. State Plane, NAD 83
Zone:	New Jersey - 2900
Vertical Reference:	NGVD29
Survey Units:	U.S. Survey Feet

- NOTES:
1. THE INFORMATION DEPICTED ON THIS MAP REPRESENTS THE RESULTS OF SURVEYS MADE ON THE DATES SHOWN AND CAN ONLY BE CONSIDERED AS INDICATING THE GENERAL CONDITION EXISTING AT THAT TIME.
 2. THE DIGITAL ORTHOPHOTOGRAPHY SHOWN WAS PUBLISHED IN 2007-2008 BY THE NEW JERSEY OFFICE OF INFORMATION TECHNOLOGY.

GAHAGAN & BRYANT ASSOCIATES, INC.
5803 KENNETT PIKE, SUITE D
CENTREVILLE SQUARE
WILMINGTON, DELAWARE 19807-1195
TEL. 302.652.4948 FAX. 302.655.9218
WILMINGTONDE@GBA-INC.COM





MULTIBEAM HYDROGRAPHIC SURVEY OF
PASSAIC RIVER

RIVER MILE 12.7 TO 14.0

Drawing Date:	27 JULY 2010
Drawn By:	J. Drake
Checked By:	E. DeAngelo
Drawing Name:	PR2010_SHEET13.DWG
Drawing Scale:	1" = 200'
Sheet Number:	13 OF 17

CONDITION SURVEY	
Survey Date:	9 JUNE 2010 - 23 JUNE 2010
Horizontal Projection:	U.S. State Plane, NAD 83
Zone:	New Jersey - 2900
Vertical Reference:	NGVD29
Survey Units:	U.S. Survey Feet

NOTES:

1. THE INFORMATION DEPICTED ON THIS MAP REPRESENTS THE RESULTS OF SURVEYS MADE ON THE DATES SHOWN AND CAN ONLY BE CONSIDERED AS INDICATING THE GENERAL CONDITION EXISTING AT THAT TIME.

2. THE DIGITAL ORTHOPHOTOGRAPHY SHOWN WAS PUBLISHED IN 2007-2008 BY THE NEW JERSEY OFFICE OF INFORMATION TECHNOLOGY.

GAHAGAN & BRYANT ASSOCIATES, INC.
5803 KENNETT PIKE, SUITE D
CENTREVILLE SQUARE
WILMINGTON, DELAWARE 19807-1195
TEL. 302.652.4948 FAX. 302.655.9218
WILMINGTONDE@GBA-INC.COM

ENGINEERS ★ SURVEYORS



CONTINUED ON SHEET 13

MULTIBEAM HYDROGRAPHIC SURVEY OF
PASSAIC RIVER

RIVER MILE 14.0 TO 14.3

Drawing Date:	27 JULY 2010
Drawn By:	J. Drake
Checked By:	E. DeAngelo
Drawing Name:	PR2010_SHEET14.DWG
Drawing Scale:	1" = 200'
Sheet Number:	14 OF 17

CONDITION SURVEY	
Survey Date:	9 JUNE 2010 - 23 JUNE 2010
Horizontal Projection:	U.S. State Plane, NAD 83
Zone:	New Jersey - 2900
Vertical Reference:	NGVD29
Survey Units:	U.S. Survey Feet

- NOTES:
1. THE INFORMATION DEPICTED ON THIS MAP REPRESENTS THE RESULTS OF SURVEYS MADE ON THE DATES SHOWN AND CAN ONLY BE CONSIDERED AS INDICATING THE GENERAL CONDITION EXISTING AT THAT TIME.
 2. THE DIGITAL ORTHOPHOTOGRAPHY SHOWN WAS PUBLISHED IN 2007-2008 BY THE NEW JERSEY OFFICE OF INFORMATION TECHNOLOGY.

GAHAGAN & BRYANT ASSOCIATES, INC.
5803 KENNETT PIKE, SUITE D
CENTREVILLE SQUARE
WILMINGTON, DELAWARE 19807-1195
TEL. 302.652.4948 FAX. 302.655.9218
WILMINGTONDE@GBA-INC.COM



DEBRIS TABLE OF COORDINATES		
NUMBER	EASTING	NORTHING
1	598,308.20	692,481.70
2	598,393.50	694,017.00
3	598,276.20	694,316.70
4	598,318.10	694,409.30
5	597,848.90	694,972.90
6	595,975.76	695,805.16
7	595,926.62	695,788.98
8	594,921.56	695,501.83
9	594,896.92	695,505.69
10	590,735.84	693,158.74
11	590,596.25	693,036.69
12	590,233.95	692,548.61
13	588,668.85	692,221.05
14	587,560.00	692,190.10
15	587,006.80	692,262.60
16	587,008.40	692,262.50
17	587,006.50	692,262.60
18	586,966.60	692,363.80
19	586,897.90	692,306.40
20	586,901.30	692,394.40
21	586,867.50	692,333.50
22	586,789.30	692,347.50
23	586,708.60	692,374.90
24	586,580.10	692,446.30
25	586,520.60	692,663.80
26	586,280.30	692,663.30
27	586,119.30	692,735.20
28	586,082.00	692,826.60
29	586,007.00	692,829.90
30	585,954.90	692,509.70
31	585,889.60	692,994.90
32	585,631.40	693,333.90
33	585,402.80	693,817.30
34	585,241.50	694,299.90
35	585,386.60	694,615.40
36	585,394.10	694,982.00
37	584,718.73	697,216.64
38	584,764.56	697,508.98
39	584,904.36	698,225.07
40	584,786.64	698,985.53
41	584,804.79	699,109.29
42	584,829.23	699,162.44
43	584,892.75	699,822.47
44	584,885.43	699,860.14
45	584,897.80	699,912.83
46	584,970.27	700,101.77
47	584,920.90	700,246.03
48	584,938.97	700,417.58
49	584,925.49	700,474.38
50	585,510.17	702,265.32
51	586,777.88	703,727.68
52	587,033.33	704,624.79
53	587,133.16	704,756.32
54	587,104.65	705,313.28
55	587,103.01	705,383.55
56	588,805.93	707,708.65
57	589,073.81	708,082.99
58	589,605.17	709,306.44
59	589,422.00	709,333.11
60	589,474.82	709,674.78
61	589,404.38	709,696.57
62	589,658.52	711,448.40
63	590,046.89	712,028.51
64	590,093.23	712,563.66
65	590,462.70	712,899.60
66	590,516.80	712,991.40
* HORIZONTAL COORDINATES ARE REFERENCED TO U.S. STATE PLANE NAD 83, ZONE NEW JERSEY – 2900 IN SURVEY FEET.		
* ALL INFORMATION SHOWN ON THIS TABLE SHALL NOT BE USED FOR CONSTRUCTION PURPOSES.		
* THE DEBRIS LISTED ARE SUBJECTIVE INTERPRETATIONS OF ANOMALIES OBSERVED IN THE MULTI-BEAM DATA AT THE TIME OF THE SURVEY.		

DEBRIS TABLE OF COORDINATES		
NUMBER	EASTING	NORTHING
67	590,640.30	713,155.20
68	590,764.30	713,382.80
69	590,781.10	713,388.50
70	590,825.10	713,522.20
71	591,105.10	713,772.70
72	591,108.00	713,830.90
73	591,133.30	713,875.30
74	591,217.30	713,990.70
75	591,079.10	714,066.10
76	591,225.10	714,074.40
77	591,418.80	714,412.60
78	591,443.20	714,532.00
79	591,734.00	714,922.80
80	591,820.70	715,085.60
81	592,211.73	715,650.82
82	592,244.27	719,695.27
83	592,155.76	720,081.00
84	592,226.92	720,379.65
85	592,080.60	720,711.40
86	592,182.01	721,627.42
87	592,237.35	721,840.08
88	592,375.11	722,339.23
89	592,467.67	722,654.29
90	592,575.24	723,045.69
91	592,658.97	723,129.78
92	592,697.82	723,216.39
93	592,727.25	723,226.33
94	594,083.25	723,541.59
95	594,273.43	723,606.49
96	594,331.67	723,631.71
97	594,545.35	723,751.02
98	594,953.05	723,792.08
99	595,259.26	724,141.62
100	596,005.13	724,452.28
101	595,990.59	724,481.32
102	596,249.35	724,748.64
103	596,448.70	725,175.10
104	596,537.90	725,465.40
105	596,560.30	725,483.70
106	596,458.70	725,729.40
107	596,465.60	725,734.90
108	596,563.20	725,713.10
109	596,618.50	725,701.90
110	596,572.60	725,739.50
111	596,794.30	726,439.70
112	596,818.10	726,550.20
113	596,835.60	726,745.00
114	597,104.93	727,987.22
115	596,946.00	728,813.50
116	596,641.60	729,083.90
117	596,500.40	729,489.30
118	596,360.40	729,917.00
119	596,348.70	729,919.40
120	596,343.50	729,933.10
121	596,234.70	731,130.80
122	596,368.40	731,442.40
123	596,503.60	731,595.00
124	596,504.80	731,613.60
125	596,567.20	731,746.90
126	596,653.60	732,278.70
127	596,792.00	732,926.00
128	597,357.03	736,117.51
129	597,277.99	737,271.71
130	597,286.95	737,399.86
131	597,357.95	737,808.98
132	597,409.03	737,910.56
* HORIZONTAL COORDINATES ARE REFERENCED TO U.S. STATE PLANE NAD 83, ZONE NEW JERSEY – 2900 IN SURVEY FEET.		
* ALL INFORMATION SHOWN ON THIS TABLE SHALL NOT BE USED FOR CONSTRUCTION PURPOSES.		
* THE DEBRIS LISTED ARE SUBJECTIVE INTERPRETATIONS OF ANOMALIES OBSERVED IN THE MULTI-BEAM DATA AT THE TIME OF THE SURVEY.		

MULTIBEAM HYDROGRAPHIC SURVEY OF
PASSAIC RIVER

RIVER MILE 0.0 TO 14.3

Drawing Date:	27 JULY 2010
Drawn By:	J. Drake
Checked By:	E. DeAngelo
Drawing Name:	PR2010_SHEET17.DWG
Drawing Scale:	AS SHOWN
Sheet Number:	17 of 17

CONDITION SURVEY	
Survey Date:	9 JUNE 2010 – 23 JUNE 2010
Horizontal Projection:	U.S. State Plane, NAD 83
Zone:	New Jersey – 2900
Vertical Reference:	NGVD29
Survey Units:	U.S. Survey Feet

NOTES:


1. THE INFORMATION DEPICTED ON THIS MAP REPRESENTS THE RESULTS OF SURVEYS MADE ON THE DATES SHOWN AND CAN ONLY BE CONSIDERED AS INDICATING THE GENERAL CONDITION EXISTING AT THAT TIME.


GAHAGAN & BRYANT ASSOCIATES, INC.
5803 KENNETT PIKE, SUITE D
CENTREVILLE SQUARE
WILMINGTON, DELAWARE 19807-1195
TEL. 302.652.4948 FAX. 302.655.9218
WILMINGTONDE@GBA-INC.COM



APPENDIX 3

Singlebeam Cross-Sections





MULTIBEAM HYDROGRAPHIC SURVEY OF PASSAIC RIVER	Drawing Date: 27 JULY 2010	CONDITION SURVEY	NOTES: 1. THE INFORMATION DEPICTED ON THIS MAP REPRESENTS THE RESULTS OF SURVEYS MADE ON THE DATES SHOWN AND CAN ONLY BE CONSIDERED AS INDICATING THE GENERAL CONDITION EXISTING AT THAT TIME.	GAHAGAN & BRYANT ASSOCIATES, INC. 5803 KENNETT PIKE, SUITE D CENTREVILLE SQUARE WILMINGTON, DELAWARE 19807-1195 TEL. 302.652.4948 FAX. 302.655.9218 WILMINGTONDE@GBA-INC.COM	
	Drawn By: J. Drake				
RIVER MILE 0.0 TO 14.3	Checked By: E. DeAngelo	Horizontal Projection: U.S. State Plane, NAD 83			
	Drawing Name: PR2010_SHEET16.DWG	Zone: New Jersey - 2900			
	Drawing Scale: AS SHOWN	Vertical Reference: NGVD29			
	Sheet Number: 16 of 17	Survey Units: U.S. Survey Feet			

APPENDIX 4

Copy of Field Notes

GBA MULTIBEAM SURVEY LOG

Date 6/8/2010
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory Passaic MB

Echo Sounder Reson 8101

Matrix/LNW File Roll 2010

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) _____

General Remarks Multibeam Patch Test

People 5

HORZ/VERT CHECKIN
Time RTK Tide Tide Board

S.O.S./Draft 4546 / 3.4'

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
07:50		Sound velocity Gas + @ Port Elizabeth			
		2010 0608-SUR. Vel		Ave 2 4546 F/5	
		Roll Test @ Performance Grid Area			Using key stone
	1	001-0758	180°		RESON Setting
		001-0800	0°		Rings 20 Hz
	2	002-0802	180°		Tx Power = 4
		002-0804	RTK Prop		Auto Gain = 4
		002-0805	0°		Gain mode = TVG
	3	003-0810	180°	offline	Pulse = 75 us
		003-0812	180°		Spread = 60
		003-0814	0°		Adapt = 30
	4	004-0816	180°		
		004-0818	0°		
	5	005-0817	180°	Do not use RTK Prop	
		005-0824	0°	Do not use	
		005-08	180°		
		Switch To Leica			
		005-0831	180°		
		005-0833	0°		

SEE REVERSE OF PAGE
FOR PROCESSING RESULTS

Prepared by: ECV

Page 1 of 7

ROLL TEST
STARTING VALUE $\Rightarrow -2.45$

LINE #	VALUE
1	$\Rightarrow -2.50$
2	$\Rightarrow -2.50$
3	$\Rightarrow -2.45$
4	$\Rightarrow -2.45$
5	$\Rightarrow -2.50$
AVE	$\Rightarrow -2.48$

PITCH TEST
STARTING VALUE $\Rightarrow +0.80$

LINE	VALUE
PY2-1 B -1C	$\Rightarrow +0.60$ (FLAT)
-2 -2A	$\Rightarrow +1.05$ "
-3 -3A	$\Rightarrow +0.70$
-4 -4A	$\Rightarrow +0.65$
-5 -5A	$\Rightarrow +0.50$
AVE	$\Rightarrow +0.70$

START VALUE $\Rightarrow -2.00$

LINES	VALUE
PY2-1 B	$\Rightarrow -2.50$
PY2-2A	
PY2-2 -3	$\Rightarrow -3.00$
-2A	$\Rightarrow -2.50$
-3A	
-3	$\Rightarrow -2.00$
-4	
-3A	$\Rightarrow -2.00$
-4A	
-4	$\Rightarrow -2.00$
-5	
-4A	$\Rightarrow -2.00$
-5A	
AVE	$\Rightarrow -2.30$

FLAT

3
5
3
16.5
27

LATENCY TEST
START VALUE $\Rightarrow \emptyset$

PY2-5	$\Rightarrow -0.15$
PY2-5B	
PY2-3A -3B	$\Rightarrow +0.05$
PY2-1D PY2-1C	$\Rightarrow +0.00$
AVE	$\Rightarrow -0.03$

USE \emptyset

GBA
MULTIBEAM SURVEY LOG

Date 6/8/2010
Vessel Name Sea Fix

Project ID #	631-10A
Description	Passaic River Multibeam

Raw Data Directory Passaic Patch MR

Echo Sounder Reson 8101

Matrix/LNW File P.42.Lnw

Positioning POSMV 320 w/ Leica RTK

**Average Boat
Speed (kts)**

General Remarks MR Patch TEST

People

HORZ/VERT CHECKIN
 Time RTK Tide Tide Board

S.O.S./Draft

Slope Lines Pitch, Yaw, Roll

[illegible]

GBA MULTIBEAM SURVEY LOG

Date 6/8/2010
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory _____

Echo Sounder Reson 8101

Matrix/LNW File Performance.LNW.MTX

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) _____

General Remarks Performance Test

People 25

HORZ/VERT CHECKIN
Time RTK Tide Tide Board

S.O.S./Draft 13.4

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
<u>Performance Grid multibeam</u>					
<u>10:37</u>	<u>1</u>	<u>001-1037</u>	<u>0°</u>		
<u>10:41</u>	<u>2</u>	<u>002-1041</u>	<u>180°</u>		
<u>10:43</u>	<u>3</u>	<u>003-1043</u>	<u>0°</u>		
<u>10:47</u>	<u>4</u>	<u>004-1047</u>	<u>180°</u>		
<u>10:49</u>	<u>5</u>	<u>005-1048</u>	<u>0°</u>		
<u>10:51</u>	<u>8</u>	<u>008-1051</u>	<u>90°</u>		
<u>10:52</u>	<u>9</u>	<u>009-1052</u>	<u>270°</u>		
<u>10:53</u>	<u>10</u>	<u>010-1053</u>	<u>90°</u>		
<u>10:54</u>	<u>11</u>	<u>011-1054</u>	<u>270°</u>		
<u>10:55</u>	<u>12</u>	<u>012-1055</u>	<u>90°</u>		
<u>For Beam Angle Test</u>					
<u>10:57</u>	<u>10</u>	<u>010-1057</u>	<u>270°</u>		
<u>10:59</u>	<u>03</u>	<u>003-1059</u>	<u>0°</u>		
<u>Single-Beam</u>					
<u>11:02</u>	<u>Bar check</u>		<u>5', 45', 30', 15', 5'</u>		
	<u>005-1115</u>		<u>000105</u>		
	<u>005-1117</u>		<u>008-1122</u>		
	<u>003-1119</u>		<u>010-1123</u>		
	<u>001-1120</u>		<u>012-1124</u>		

Prepared by: SCD

Page 3 of 7

MULTIBEAM SURVEY LOG

Date 6/8/10
Vessel Name Sea Fix

Project ID #	631-10A
Description	Passaic River Multibeam

Raw Data Directory Passaic-Patch SP

Echo Sounder **Reson 8101**

Matrix/LNW File ACE QC - LNW

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) 5

General
Remarks USACE QC Aler

HORZ/VERT CHECKIN

Time	RTK Tide	Tide Board
------	----------	------------

People 5

S.O.S./Draft 11

Single Beam

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
Bar check <u>8', 45', 30', 15'</u>					
Sound velocity <u>dec 70 wind & currents 4750</u>					
1251	ACE 11	ACE 11 RAW	35°		
1256	ACE 3	ACE 3 RAW	215°		offline dont use
1257	ACE 5	ACE 5 RAW	35°		RTK Antenna Hgt adjustment
1259	ACE 7	ACE 7 RAW	215°		cal. brate to USACE Tide
1300	ACE 9	ACE 9 RAW	35°		
1304	ACE 18	ACE 18 RAW	305°		
1306	ACE 16	ACE 16 RAW	125°		
1307	ACE 14	ACE 14 RAW	305°		
1308	ACE 12	ACE 12 RAW	125°		

Prepared by: FCP

Page 4 of 7

Date 6/8/10
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory Passaic Path m3

Echo Sounder Reson 8101

Matrix/LNW File ACE QC LNW & MTY

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) 5

General Remarks ACE QC

People 5

HORZ/VERT CHECKIN

Time RTK Tide Tide Board

S.O.S./Draft 4927/3.4

Mult. Beam

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
1324	ACE9	ACE9	215°		
1326	ACE8	ACE8	350		
1327	ACE7	ACE7.RAW	215°		
1329	ACE6	ACE6.RAW	350		
1330	ACE5	ACE5.RAW	215°		
1331	ACE4	ACE4.RAW	350		Lost RTK
1334	ACE4	ACE4A.RAW	215°		
1335	ACE3	ACE3.RAW	350		
1337	ACE2	ACE2.RAW	215°		
1338	ACE1	ACE1.RAW	350		
1340	ACE18	ACE18.RAW	125°		
1341	ACE17	ACE17.RAW	305°		point use lost RTK
1342	ACE17	ACE17A.RAW	125°		
1344	ACE16	ACE16.RAW	305°		
1346	ACE15	ACE15.RAW	125°		
1347	ACE14	ACE14.RAW	305°		142A point use Traffic
1349	ACE14	ACE14B.RAW	305°		
1351	ACE13	ACE13.RAW	125°		lost RTK
1352	ACE13	ACE13A	125°		
1353	ACE12	ACE12	305°		
1354	ACE11	ACE11	125°		

Prepared by: ECD

Page 5 of 7

GBA MULTIBEAM SURVEY LOG

Date 6/8/2010
Vessel Name Sea Fix

Project ID #	631-10A
Description	Passaic River Multibeam

Raw Data Directory

Echo Sounder _____ **Reson 8101**

Matrix/LNW File Performance

Positioning POSMV 320 w/ Leica RTK

**Average Boat
Speed (kts)**

General Remarks

People

HORZ/VERT CHECKIN

Time	RTK Tide
------	----------

Tide Board

S.O.S./Draft _____

corrected Antenna Leica Performance

[illegible]

Prepared by: ECD

Page 9 of 7

GBA MULTIBEAM SURVEY LOG

Date 6/9/10
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory Passaic - 2010 MB

Echo Sounder Reson 8101

Matrix/LNW File A01

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) 5

General Remarks Weather Rainy
HORZ/VERT CHECKIN

People 5

Time RTK Tide Tide Board Ant 115ft

S.O.S./Draft 4953 / 3.4'

13:35 -0.85 -0.80 7.3ft

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
	-0.15'	Delta Applied To Rover Ant to Account for Leica system Reference station Antenna			
		Reson Settings			
		Range 80m			
		max Rate 20 p/s			
		Tx Power 4			
		Tx Pulse 75			
		Rx Gain			
		Gain mode = TVG			
		Autogain = 4			
		Spread = 60 Log DB			
1359	Absorb = 30				
1359	A01-30	A01-30	341	1.1	RNG 35m
1406	A01-44	A01-44	161	1.4	Shadowed
1413	A01-45	A01-45	341	1.1	
1422	A01-39	A01-39	341	1.1	end @ Barges
1424	A01-39	A01-39A	141	1.1	
1429	A01-34	A01-34	341	1.2	
1438	A01-33	A01-33	141		shoreline Lost RTK

Prepared by: ECN

Page 1 of 4

GBA MULTIBEAM SURVEY LOG

Date 6/9/10
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory Passaic 2010 MB

Echo Sounder Reson 8101

Matrix/LNW File A01

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) 4.75

General Remarks

People 5

HORZ/VERT CHECKIN

Time RTK Tide Tide Board

S.O.S./Draft 13.4

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
14:41	A01-33	A01-33A	341	1.1	
14:47	A01-41	A01-41	141	1.1	GAP Filling
14:52	A01-54	A01-54	341	1.1	
14:57	A01-55	A01-55	141	1.1	
	A01-62	A01-61			
15:09	A01-61	A01-61A	341	0.9	
15:15	A01-67	A01-67	141	1.0	
15:23	A01-71	A01-71	341	1.0	
15:35	A01-76	A01-76	141	0.9	
15:36	A01-080	A01-080	341	1.0	
15:41	A01-085	A01-085	141	1.0	
15:47	A01-080	A01-080	341	0.8	
15:52	A01-095	A01-095	141	0.8	
15:58	A01-100	A01-100A	341	0.8	
16:03	A01-105	A01-105	141°	0.8	
16:09	A01-109	A01-109	341°	0.8	
16:15	A01-114	A01-114	141°	0.8	
16:22	A01-119	A01-119	341°	1.1	
16:27	A01-123	A01-123	141°	1.1	
16:34	A01-127	A01-127	341°	1.1	

Prepared by: ECO

Page 2 of 4

GBA MULTIBEAM SURVEY LOG

Date 6/10/07
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory Passaic 2010 MB

Echo Sounder Reson 8101

Matrix/LNW File A02

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) _____

General Remarks _____

People _____

HORZ/VERT CHECKIN

S.O.S./Draft 4938 / 3.4

Time	RTK Tide	Tide Board	
<u>09:10</u>	<u>2.44</u>	<u>2.50</u>	<u>Ant 7.3'</u>

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
<u>07:22</u>		<u>Position check @ Dock</u>	<u>57</u>	<u>9042.5</u>	<u>660 438.7</u>
<u>09:20</u>		<u>SV Cast @ A02</u>	<u>=</u>	<u>4938.6</u>	
		<u>Reson Settings</u>			
		<u>Rng 35</u>			
		<u>TX Power 9</u>			
		<u>Pulse 75 us</u>			
		<u>Ping 20 p/s</u>			
		<u>Gain MOD TVG</u>			
		<u>Autogain 4</u>			
<u>9:27</u>	<u>A02-54</u>	<u>A02-54</u>	<u>357</u>	<u>1.3</u>	
<u>9:30</u>	<u>A02-49</u>	<u>A02-49</u>	<u>177</u>	<u>1.4</u>	
<u>9:34</u>	<u>A02-45</u>	<u>A02-45</u>	<u>357</u>	<u>1.4</u>	
<u>9:37</u>	<u>A02-41</u>	<u>A02-41</u>	<u>177</u>	<u>1.4</u>	
<u>9:44</u>	<u>A01-35</u>	<u>A01-35</u>	<u>341</u>	<u>1.3</u>	<u>Barge Fill in</u>
<u>9:47</u>	<u>A01-31</u>	<u>A01-31</u>	<u>341</u>	<u>1.3</u>	<u>Barge Fill in @ Bulkhead</u>
<u>9:49</u>	<u>A02-58</u>	<u>A02-58</u>	<u>357</u>	<u>1.3</u>	
<u>9:54</u>	<u>A02-37</u>	<u>A02-37</u>	<u>177</u>	<u>1.3</u>	
<u>9:58</u>	<u>A02-33</u>	<u>A02-33</u>	<u>357</u>	<u>1.3</u>	
<u>10:01</u>	<u>A02-61</u>	<u>A02-61</u>	<u>177</u>	<u>1.3</u>	

Prepared by: SCD

Page 1 of 9

GBA MULTIBEAM SURVEY LOG

Date 9/10/2010
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory Passaic 2010 MB

Echo Sounder Reson 8101

Matrix/LNW File A02 & A03

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) A

General Remarks

People

HORZ/VERT CHECKIN

Time RTK Tide Tide Board

S.O.S./Draft

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
10:06	A02-66	A02-66	177 357	1.2	
10:10	A02-71	A02-71	357 177	1.3	Do NOT USE dropped RTK
10:13	A02-71	A02-71A	177 357	1.2	
10:17	A02-76	A02-76	857	1.2	Ended & Circled RTK drop
10:26	A02-76	A02-76A	357	1.2	
10:24	A02-81	A02-81	177	1.2	
10:28	A02-86	A02-86	357	1.1	
10:33	A02-91	A02-91	177	1.0	
10:36	A02-95	A02-95	357	1.0	
10:42	A02-97	A02-97	177	1.0	
10:49	A02-103	A02-103	357	1.0	
10:50	A02-106	A02-106	177	1.0	
10:55	A02-105	A02-105	357	1.0	
		SV Cast	A03		
11:10	A03-65	A03-65	10°		Lost RTK point USE
11:12	A03-65	A03-65A	10°	1.0	
11:18	A03-61	A03-61	170°	1.0	11:20 Dropped RTK circle
11:22	A03-61	A03-61A	190	1.1	
11:24	A03-57	A03-57	10°	1.1	
11:30	A03-53	A03-53	190°	1.1	

Prepared by: ECN

Page 2 of 9

GBA MULTIBEAM SURVEY LOG

Date 6/10/2010
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory Passaic 2010 MB

Echo Sounder Reson 8101

Matrix/LNW File A03

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) 5 kts

General Remarks

People 5

HORZ/VERT CHECKIN

Time RTK Tide Tide Board

S.O.S./Draft 4931 / 3.4

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
11:34	A03-049	A03-049	10°	1.1	
11:40	A03-045	A03-045	190°	1.1	
11:45	A03-041	A03-041	10°	1.1	
11:50	A03-037	A03-037	190°	1.5	
11:55	A03-33	A03-033	10°	1.5	
12:00	A03-29	A03-029	190°	1.5	FILL
12:03	A03-69	A03-069	10°	1.5	
12:09	A03-73	A03-073	190°	1.6	LOST RTK @ END OF LINE
12:12	A03-73	A03-073A	190°	1.1	RE-RUN P/O LAST LINE
12:15	A03-77	A03-077	10°	1.4	
12:20	A03-81	A03-081	190°	1.1	LOST RTK @ EOL - REDO
12:23	A03-81	A03-081A	190°	1.3	" " " "
12:26	"	A03-081B	190°	1.3	" " " "
12:30	"	A03-081C	10°	1.2	" " " COMPLETED
12:45	A03-84	A03-084	190°	1.2	LOST RTK @ EOL - REDO } CONTINUE
12:49	"	A03-084A	10°	1.2	" " " " }
12:55	A03-89	A03-089	190°	1.2	" " "
13:02	A03-89	A03-089A	10°	1.2	
13:07	A03-93	A03-093	190°	1.2	
13:11	A03-97	A03-097	10°	1.1	

Prepared by: _____

Page 3 of 9

GBA MULTIBEAM SURVEY LOG

Date 6/10/2010
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory PASSAIC 2010 MB

Echo Sounder Reson 8101

Matrix/LNW File A03

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) 5 KTS

General Remarks

People 5

HORZ/VERT CHECKIN

S.O.S./Draft 4931/3.4 m

Time RTK Tide

Tide Board

14:11 -0.70

-0.65

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
13:15	A03-101	A03-101_RAW	190°	1.2	
13:19	A03-105	A03-105	10	1.0	LOST RTK
13:23	"	A03-105A	10°	0.9	RE-RUN 5 LOST RTK
13:25	"	A03-105B	100	0.9	" "
13:28	"	A03-105C	100	0.9	" "
13:31	A03-108	A03-108	190°	1.0	
13:36	A03-111	A03-111	10°	0.9	LOST RTK
13:39	A03 "	A03-111A	10°	1.1	
13:44	A03-113	A03-113	190°	1.1	
13:49	A03-115	A03-115	10°	1.1	
13:55	A03-118	A03-118	190°	1.1	
14:00	A03-121	A03-121	10°	1.1	
14:11		MID-DAY TIDE CHECK			
14:15		5v Cast A04 4922 FT			
14:21	A04-77	A04-77	17°	1.2	Dropped RTK circled
14:24	A04-77	A04-77A	17°	1.2	Dropped RTK circled
14:27	A04-77	A04-77B	17°	1.2	
14:32	A04-77	A04-77	17°	1.1	
14:36	A04-71	A04-71	17°	1.1	Dropped RTK circled

Prepared by: PLS & ECD

Page 4 of 9

GBA MULTIBEAM SURVEY LOG

Date 6/10/2010
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory Passaic 2010 m.b.

Echo Sounder Reson 8101

Matrix/LNW File A04

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) _____

General Remarks _____

People 5

HORZ/VERT CHECKIN _____

Time RTK Tide Tide Board

S.O.S./Draft 4922 / 3.4

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
14:38	A04-71	A04-71A	17°	1.1	
14:43	A04-68	A04-68	17°	1.2	
14:48	A04-65	A04-65	17°	1.1	14:49 Drapped & Circled
14:50	A04-65	A04-65A	17°	1.1	
14:54	A04-62	A04-62	17°	1.1	
15:00	A04-59	A04-59	17°	1.1	
15:02	A04-56	A04-56	17°	1.1	
15:06	A04-53	A04-53	17°	1.0	
15:10	A04-50	A04-50	17°	1.0	
15:15	A04-80	A04-80	17°	1.0	
15:19	A04-83	A04-83	17°	0.9	
15:24	A04-86	A04-86	17°	1.5	
15:28	A04-89	A04-89	17°	1.0	
15:34	A04-92	A04-92	17°	1.0	15:35 Drapped RTK & Circled
15:36	A04-92	A04-92A	17°	1.0	
15:40	A04-059	A04-059	17°	0.8	
15:44	A04-054	A04-054	17°	0.8	
15:46	A04-051	A04-051	17°	0.8	
15:55	A04-048	A04-048	17°	0.8	
15:52	A04-45	A04-045			

Prepared by: ECB

Page 5 of 9

GBA MULTIBEAM SURVEY LOG

Date 6/10/10
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory A04

Echo Sounder Reson 8101

Matrix/LNW File _____

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) _____

General Remarks _____

People 5

HORZ/VERT CHECKIN

S.O.S./Draft 4922 / 3.9

Time RTK Tide Tide Board

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
15:55	A04-043	A04-043	17°		
15:58	A04-040	A04-040	197°		
16:02	A04-095	A04-095	17°		
16:09	A04-098	A04-098	17°	1.1	
16:13	A04-101	A04-101	197	1.1	
16:19	A04-105	A04-105	17	1.1	Loss RTK
16:24	"	A04-105A	17	1.2	
16:24	A04-109	A04-109	197	1.1	
16:30	A04-113	A04-113	17	1.1	
16:32	A04-118	A04-118	197	1.2	
16:40	A04-123	A04-123	17	1.3	
16:44	A04-126	A04-126	197	1.2	
16:50	A04-130	A04-130	17	1.0	
16:55	A04-134	A04-134	197	1.3	
17:01	A04-138	A04-138	17	1.1	
17:07	A04-142	A04-142	197	1.4	
17:14	A04-146	A04-146	17	1.4	
17:19	A04-150	A04-150	197	1.3	
17:26	A04-154	A04-154	17	1.1	
17:32	A04-158	A04-158	197	1.4	

Prepared by: _____

Page 6 of 9

GBA MULTIBEAM SURVEY LOG

Date 6/20/10
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory Passaic 2010 SB

Echo Sounder Reson 8101

Matrix/LNW File A01, A02, A03, A04

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) _____

General Remarks _____

People _____

HORZ/VERT CHECKIN

Time RTK Tide Tide Board

S.O.S./Draft 4942 / 1.1

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
18:20		Bar check	5', 35', 15', 5'		
A01	Longitudinals				
18:32	A01-051	A01-051	341	1.4	Cnd @ Barge
18:38	A01-125	A01-125	161	1.4	
	A02	Crosslines			A02-CROSS, LNW
18:45	4	004-1845	268°	1.0	
18:48	3	003-1848	268°	1.0	
18:50	2	002-1850	268°	1.0	
18:52	1	001-1852	268°	1.0	
18:54	A02-049	A02-049	177°	1.0	Longitudinals Lost RTK
18:57	A02-049	A02-049	177°	1.0	
19:02	A02-076	A02-076	357°	1.0	
19:05	A02-100	A02-100	177	1.0	
	A03	Crosslines			=> From 2007 Single Beam Lines File
19:11	0006	0006.RAW	268	1.0	
19:14	0011	0011.RAW	268°	1.0	
19:16	0016	0016.RAW	268°	1.0	
19:19	A03-057	A03-057.RAW	189°	1.0	Longitudinal
19:22	A03-077	A03-077.RAW	170°	1.1	
19:26	A03-107	A03-107	189°		

Prepared by: ECO

Page 8 of 9

GBA MULTIBEAM SURVEY LOG

Date 6/11/10
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory Passaic 2010 MB

Echo Sounder Reson 8101

Matrix/LNW File A02

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) _____

General Remarks Shallow Edges

People 4

HORZ/VERT CHECKIN
Time RTK Tide Tide Board

S.O.S./Draft 4940

08:00 3.33 3.40 Ant Hgt 7.3'

08:15 = SV Cast @ A02

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
07:04		Position check @ Dock			578042.3, 660438.6
08:22	A02-106		177		RESON Settings
08:31	A02-114		177		RNG = 20 m
08:35	A02-118		357		TX POW = 4
08:39	A02-122		177		Auto Gain = 4
08:43	A02-121		357		
08:47	A02-125		177		
08:53	A02-128		357		1/2 LINE
08:57	A02-131		177		"
09:00	A02-134		357		"
09:04	A02-137		177		"
09:07	A02-139		357		"
09:12	A02-142		177		"
09:15	145		357		"
09:16	A02-148		177		NOT NEEDED
09:17	A02-148	A RAW	357		IN FILE
09:20	A02-151		357		"
09:21	A02-133		357		"
09:24	A02-127		177		1/2 LINES
09:29	A02-130		357		LOG RTK

Prepared by: PL 65 ECP

Page 1 of 8

GBA MULTIBEAM SURVEY LOG

Date 6/11/2010
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory PASSAIC RIVER MB

Echo Sounder Reson 8101

Matrix/LNW File A02/A03

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) 5

General Remarks

People 4

HORZ/VERT CHECKIN

Time RTK Tide Tide Board

S.O.S./Draft 4940/3.4 MB

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
0932	A02-130	A.RAW	177		
0936	A02-133	A.RAW	177		
0938	A02-136		177		
0940	A02-138		357		
0942	A02-140		177		
0945	A02-143		357		
CHANGE LINE FILE TO A03. LNW					
0946	A02-121		10		
0951	A03-125		190		
0955	A03-129		10		
1000	A03-132		190		
1003	A03-135		10		PARTIAL
1007	A03-138	A.RAW	10		
1012	A03-136		190		LOSS RTK
1015	A03-136	A.RAW	10		
1021	A03-138		190		
1024	A03-140		10		
1030	A03-142		190		
1034	A03-144		10		

Prepared by: _____

Page 2 of 8

GBA MULTIBEAM SURVEY LOG

Date 6/11/2010
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory Passaic River MB
Matrix/LNW File A03/A05

Echo Sounder Reson 8101
Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) 5

General Remarks HORZ/VERT CHECKIN

People 4

Time RTK Tide Tide Board

S.O.S./Draft 4240/3.4

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
1039	A03-144	A.RAW	10		
1044	A03-147		1070		
1048	A03-145		10		FILL IN
1055	A03-123		190		LOST RTK
1058	A03-123	A.RAW	10		FILL
	CHANGE TO REACH		A05		
1121	A05-90		10		REDO
1123	"	A.RAW	10		RUN UNDER 2 BRIDGES
1130	A05-86		190		- FILL TIDE!
1134	A05-82		10		FOR ENTIRE REACH
1141	A05-78		190		
1143	A05-74		10		
1149	A05-70		190		
1153	A05-67		10		South of Bridge Only
1210	A05-90	B.RAW	190		
1216	A05-94		190		
1224	A05-98		190		
1227	A05-102		190		
1232	A05-106		10		
1238	A05-111		190		

Prepared by: _____

Page 3 of 4

GBA MULTIBEAM SURVEY LOG

Date 6/11/2010
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory Passaic River MB

Echo Sounder Reson 8101

Matrix/LNW File A05-LNW

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) 5

General Remarks

People 4

HORZ/VERT CHECKIN

S.O.S./Draft 49.27/3.4m

Time	RTK Tide	Tide Board
<u>13:34</u>	<u>-0.94</u>	<u>-0.90'</u>

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
<u>1242</u>	<u>A05-115</u>		<u>10</u>		<u>EDIT RTK TIDE</u>
<u>1249</u>	<u>A05-120</u>		<u>190</u>		<u>FOR ENTIRE REACH</u>
<u>1255</u>	<u>A05-119</u>		<u>10</u>		
<u>1258</u>	<u>A05-123</u>		<u>190</u>		
<u>1259</u>	<u>A05-124</u>		<u>10</u>		
<u>1302</u>	<u>A05-128</u>		<u>190</u>		
<u>1308</u>	<u>A05-122</u>		<u>10</u>		<u>File</u>
<u>1306</u>	<u>A05-117</u>		<u>190</u>		<u>File</u>
<u>1309</u>	<u>A05-072</u>		<u>10</u>		
<u>1313</u>	<u>A05-110</u>		<u>190</u>		
<u>1315</u>	<u>A05-118</u>		<u>10</u>		
<u>1319</u>	<u>A05-125</u>		<u>190°</u>		
<u>1321</u>	<u>A05-129</u>		<u>10</u>		
<u>1323</u>	<u>A05-131</u>		<u>190°</u>		
<u>13:34</u>	<u>Tide Board check</u>				

Prepared by: _____

Page 4 of 8

GBA MULTIBEAM SURVEY LOG

Date 6/11/10
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory _____

Echo Sounder Reson 8101

Matrix/LNW File A06

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) 1.1 kts

General Remarks _____

People 4

HORZ/VERT CHECKIN

Time RTK Tide Tide Board

S.O.S./Draft 4.28 / 3.4

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
13:44	A06-083	A06-083	175°	1.1	
13:47	A06-087	A06-087	355°	1.1	
13:49	A06-091	A06-091	175	1.1	
13:50	A06-095	A06-095	355°	1.1	
13:53	A06-101	A06-101	175°	1.1	
13:56	A06-105	A06-105	355°	1.1	next to barge
13:58	A06-109	A06-109	175	1.1	Debris Field East shore
14:02	A06-113	A06-113	355	1.1	STRD Beam @ 80°
14:07	A06-079	A06-079	175	1.1	
14:09	A06-075	A06-075	355°	1.1	
14:12	A06-072	A06-072	175°	1.1	
14:14	A06-069	A06-069	355°	1.1	
14:17	A06-066	A06-066	175°	1.1	
14:19	A06-063	A06-063	335	1.1	
14:21	A06-064	A06-064	175	1.1	
14	A06-061	A06-061	335	1.1	
	A06-068	A06-068	175	1.1	F. 11 SA
14:29	A06-065	A06-065			F. 11 SA

Prepared by: ECO

Page 5 of 8

GBA MULTIBEAM SURVEY LOG

Date 6/11/10
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory Passaic 2010 MB

Echo Sounder Reson 8101

Matrix/LNW File A07

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) _____

General Remarks _____

People 4

HORZ/VERT CHECKIN
Time _____ RTK Tide _____ Tide Board _____

S.O.S./Draft 4909 / 3.4

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
14:34	A07-089	A07-089	332°	1.1	
14:37	A07-086	A07-086	152°	1.1	
14:40	A07-083	A07-083	332°	1.1	
14:42	A07-080	A07-080	152°	1.1	
14:45	A07-087	A07-087	332°	1.1	
14:48	A07-085	A07-085	152°	1.1	14:49 cited dropped RTK
14:50	A07-085	A07-085A	152°	1.1	
14:52	A07-082	A07-082	332°	1.1	
14:55	A07-079	A07-079	152°	1.1	
15:00	A07-102	A07-102	332°	1.1	
15:00	A07-105	A07-105	152°	1.1	
15:05	A07-110	A07-110	332°	1.1	
15:08	A07-113	A07-113	152°	1.1	
15:11	A07-116	A07-116	332°	1.0	
15:14	A07-119	A07-119	152°	1.1	
15:17	A07-122	A07-122	332°	1.1	
15:20	A07-125	A07-125	152°	1.1	
15:24	A07-128	A07-128	332°		open up starboard beams
15:30	End	SV Check			

Prepared by: SCD

Page 6 of 8

GBA MULTIBEAM SURVEY LOG

Date 6/11/2010
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory Passaic 2010 SB

Echo Sounder Reson 8101

Matrix/LNW File Passaic 2007 SB

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) _____

General Remarks 18:07 Position check

People _____

HORZ/VERT CHECKIN
Time RTK Tide Tide Board

S.O.S./Draft _____

17:35 2.95 2.95

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
		Longitudinal Lines for A05 - A07			
16:28	A05-071	A05-071			center channel
16:35	A05-086	A05-086			Lost RTK under Bridges
	A05-088	A05-086			South shore Longitudinal
16:44	A05-081				North shore Longitudinal
		A03 Cross Lines			
16:57	0016	0016	268°		
16:	0011	0011	268°		Do not use
17:00		0011A	268°		
17:03	0006	006	268°		
	A02	Cross Lines			
	001-	001			Do not use
		001-1706	268°		
	2	002-1710	268°		
	3	003-1713	268°		
	4	004-1715	268°		
17:18	A02-116				Long Line East shore A22 A3
17:26	End Bar check				20', 15', 10' @ A05

Prepared by: ECO

Page 8 of 9

GBA MULTIBEAM SURVEY LOG

Date 6/12/12
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory Passaic 2010 MB

Echo Sounder Reson 8101

Matrix/LNW File A05

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) 4 KTS

General Remarks

People 3

HORZ/VERT CHECKIN

S.O.S./Draft 9943 / 3.4

Time	RTK Tide	Tide Board	Ant Hgt
<u>8:48</u>	<u>3.60</u>	<u>3.65'</u>	<u>2.3'</u>

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
<u>8:5</u>		<u>Position check @ DOCK</u>			<u>579042.3 660432.6</u>
<u>08:49</u>		<u>Tide check @</u>			<u>Tide Board @ Port</u>
<u>08:52</u>		<u>SU Cast @ A05</u>			
		<u>RESON settings</u>			
		<u>Range 20m</u>			
		<u>TX Power 4</u>			
		<u>TX Pulse 63 us</u>			
		<u>Gain MODE TVG</u>			
		<u>Autogain 4</u>			
		<u>A05 - Shallow</u>	<u>side</u>	<u>East</u>	
<u>0901</u>	<u>A05-125</u>		<u>10°</u>	<u>1.3</u>	
<u>0903</u>	<u>A05-128</u>		<u>190°</u>	<u>1.3</u>	
<u>0906</u>	<u>A05-131</u>		<u>10°</u>	<u>1.3</u>	
<u>0908</u>	<u>A05-133</u>		<u>190°</u>	<u>1.3</u>	
<u>0910</u>	<u>A05-135</u>		<u>10°</u>	<u>1.3</u>	
<u>0912</u>	<u>A05-137</u>		<u>190°</u>	<u>1.3</u>	
<u>09:15</u>	<u>A05-139</u>		<u>190°</u>	<u>1.3</u>	
<u>9:17</u>	<u>A05-141</u>		<u>10°</u>	<u>1.3</u>	
<u>9:17</u>	<u>A05-142 A</u>		<u>190</u>	<u>1.3</u>	

Prepared by: ECO

Page 1 of 8

GBA MULTIBEAM SURVEY LOG

Date 6/12/10
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory Passaic 2010mB

Echo Sounder Reson 8101

Matrix/LNW File A05

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) 4 kts

General Remarks

People 3

HORZ/VERT CHECKIN

Time RTK Tide Tide Board

S.O.S./Draft 4743/3.9

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
9:24	A05-052		10°	1.3	
9:27	A05-055		190	1.4	
9:29	A05-053		10°	1.4	
9:31	A05-81		190	1.4	
9:33	A05-49		10°	1.4	
9:36	A05-47		190°	1.3	
9:38	A05-45		10°	1.3	
9:40	A05-43		190	1.3	
9:42	A05-68		10°	1.4	
9:48	A05-61		190°	2.4	
9:52	A05-65		10°	1.5	
9:55	A05-58		190°	2.5	
9:58	A05-56		10°	1.2	
10:02	A05-54		190°	1.3	
10:06	A05-132		10°	1.3	
10:09	A05-134		190°	1.5	
10:13	A05-136		10°	1.9	open Port Beam 60° - Bulkhead
10:16	A05-138				open STBD 75° Bulkhead

Prepared by: ECD

Page 2 of 8

GBA MULTIBEAM SURVEY LOG

Date 6/12/10
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory Passaic 2010 MB

Echo Sounder Reson 8101

Matrix/LNW File A06/A07

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) _____

General Remarks 10:20 SV East A06

People 3

HORZ/VERT CHECKIN
Time RTK Tide Tide Board

S.O.S./Draft 4

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
10:24	A06-56		355	1.0	
10:27	A06-54		175	1.0	
10:29	A06-52		355		
10:30	A06-50		175		
10:32	A06-51		355		
10:37	A06-119		355		
10:39	A06-50	A.RAW	175		
10:40	A06-52	A.RAW	175		
Switch		Reach	50	A07	
10:43	A07-080		332		
10:46	A07-077		152		
10:49	A07-75		332		
10:51	A07-73		152		
10:54	A07-71		332		
10:57	A07-69		152		
10:59	A07-67		332		
11:02	A07-65		152		
11:04	A07-63		332		
11:06	A07-61		152		NAV HAZ OPEN PORT X

Prepared by: _____

Page 3 of 8

GBA MULTIBEAM SURVEY LOG

Date 6/12/2010
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory Passaic River MB

Echo Sounder Reson 8101

Matrix/LNW File A08

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) 5

General Remarks

People 3

HORZ/VERT CHECKIN

S.O.S./Draft 4043/3.4 m

Time RTK Tide Tide Board

1114 1.93 1.9'

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
11:22	A08-122		296		EDIT RTK TIDE FOR
11:30	A08-119		116		ENTIRE REACH A08
11:33	A08-116		296		BRIDGE INTERFERENCE
11:38	A08-113		116		
11:42	A08-110		296		
11:46	A08-107		116		
11:51	A08-125		296		
11:55	A08-129		116		
11:58	A08-133		296		
12:02	A08-137		116		
12:05	A08-141		296		
12:10	A08-145		116		
12:13	A08-149		296		
12:16	A08-153		116		
12:20	A08-157		296		
12:25	A08-160		116		
12:28	A08-165		296		DOWNSTREAM OF RR BRIDGE
12:30	A08-168		116		
12:31	A08-172		296		
12:33	A08-175		116		

Prepared by: _____

Page 4 of 8

GBA MULTIBEAM SURVEY LOG

Date 6/12/2010
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory Passaic River MB

Echo Sounder Reson 8101

Matrix/LNW File AOB/ B01

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) 5

General Remarks 12:49 SV Cast B01

People 3

HORZ/VERT CHECKIN

Time RTK Tide Tide Board

S.O.S./Draft 49.43/3.4m

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
12:36	AOB - 164		296		
12:39	AOB - 167		116		
12:41	AOB - 170		296		
12:44	AOB - 173		116		
12:46	AOB - 176		296		
12:49	SV Cast	B01			
12:54	B01 - 122		279°	1.2	
12:57	B01 - 126		90°	1.2	
13:00	B01 - 129		90°	1.1	
13:02	B01 - 129A		270°	1.1	
13:05	B01 - 132		90°	1.0	
13:09	B01 - 138		270°	1.0	
13:11	B01 - 141		90°	1.3	
13:14	B01 - 145		270°	0.9	
13:16	B01 - 149		90°	1.2	
13:18	B01 - 152		270°	1.2	
13:21	B01 - 155		90°	1.2	
13:25	B01 - 158		270°	0.9	
13:27	B01 - 119		90°	1.2	
13:30	B01 - 115		270°	1.2	

Prepared by: ECD

Page 5 of 8

GBA MULTIBEAM SURVEY LOG

Date 6/12/10
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory P559ic 2010 SB

Echo Sounder Reson 8101

Matrix/LNW File _____

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) _____

General Remarks Single Beam Check Lines
HORZ/VERT CHECKIN

People 3

Time RTK Tide Tide Board

S.O.S./Draft 4854/1.1

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
	109		359		
14:27	109	0109A	359°	1.1	
1428	109	0109B	179°	1.1	
14:33	109	0109	184°	1.2	
14:34	109	0109A	4°	1.2	
1443	101	0101	183°	1.1	
1444		0101A	7°	1.1	
1452	91	0091	203°	1.1	
1453		0091A	27°	1.1	
1456	87	0087	219°	1.8	
1457	87	0087A	39°	1.8	
1459	82	0082	242°	1.7	
1501		0082A	62°		
1503	78	0078	255°		
1504		0078A	79°	0.9	
1506	69	0069	275°		
1507		0069A	295°	1.0	
1511	63	0063	275°	1.0	
1512		0063	95°	1.2	

Prepared by: SCD

Page 7 of 9

GBA MULTIBEAM SURVEY LOG

Date 6/13/10
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory Passaic2010.mdb

Echo Sounder Reson 8101

Matrix/LNW File A08

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) 5

General Remarks 07:01 position checked @ dock

People 3

HORZ/VERT CHECKIN
Time RTK Tide Tide Board

S.O.S./Draft 4041 / 3.4m

07:29 2.35 2.40

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
<u>07:32</u>	<u>SV Cast @</u>	<u>A08</u>			
	<u>RESON settings</u>		<u>RNG: 20m</u>		
			<u>max Rate 20 p/s</u>		
			<u>Tx Power 4</u>		
			<u>Pulse: 63 us</u>		
			<u>Gain Mod2: TUG</u>		
			<u>AutoGain: 4</u>		
<u>0742</u>	<u>A08-17A</u>		<u>296</u>	<u>0.9</u>	
<u>0745</u>	<u>A08-17B</u>		<u>116</u>	<u>0.9</u>	
<u>0747</u>	<u>A08-17B</u>		<u>296</u>	<u>1.4</u>	<u>HAZARDS</u>
<u>0751</u>	<u>A08-110</u>		<u>116</u>	<u>1.6</u>	
<u>0753</u>	<u>A08-108</u>		<u>296</u>	<u>1.5</u>	
<u>0755</u>	<u>A08-106</u>		<u>116</u>	<u>1.5</u>	
<u>0757</u>	<u>A08-104</u>		<u>296</u>	<u>1.5</u>	
<u>0759</u>	<u>A08-102</u>		<u>116</u>	<u>1.5</u>	<u>-6 ELEV</u>
<u>0807</u>	<u>A08-107</u>		<u>116</u>	<u>1.4</u>	<u>CHECK RTK TIDE</u>
<u>0810</u>	<u>A08-105</u>		<u>296</u>	<u>1.5</u>	<u>BRIDGE X-ING</u>
<u>0813</u>	<u>A08-103</u>		<u>116</u>	<u>1.4</u>	
<u>0816</u>	<u>A08-101</u>		<u>296</u>	<u>1.5</u>	

Prepared by: PAG/ELW

Page 1 of 7

GBA MULTIBEAM SURVEY LOG

Date 6/13/2010
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory PASSAIC RIVER MB

Echo Sounder Reson 8101

Matrix/LNW File 1.08/B01

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) 5

General Remarks

People 3

HORZ/VERT CHECKIN

S.O.S./Draft 4.41/3.4 MB

Time RTK Tide Tide Board

0859 3.85 3.85

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
0818	A08-099		296	1.5	BRIDGE X-ING
0820	A08-097		216	1.4	CHECK RTK
0823	A08-095		296	1.4	EDIT TIME -
0825	A08-093		116		"
0830	A08-163		116	2.6	BRIDGE
0832	A08-165		296	1.6	"
0838	A08-167		296	1.6	
0839	A08-169		116	1.7	
0847	A08-171		296	1.7	
	CHANGE REACH	TO	B01		
0847	B01-158		270	1.7	SU CAST @ 0940
0944	B01-160		90	1.1	STOP FOR BOAT REPAIR
0947	B01-162		270	1.4	OPEN STBD & CUTOFF
0955	B01-164		270		VOID -
0951	B01-094		90	1.1	
0955	B01-092		270	1.1	
0957	B01-090		90	1.1	
1000	B01-085		270	1.1	
1002	B01-083		90	1.2	
1004	B01-081		270	1.6	

Prepared by: _____

Page 2 of 7

GBA MULTIBEAM SURVEY LOG

Date 6/13/2010
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory PASSAIC RIVER MB

Echo Sounder Reson 8101

Matrix/LNW File B01/B02

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) 5

General Remarks _____

People 3

HORZ/VERT CHECKIN
Time RTK Tide Tide Board

S.O.S./Draft 4044/3.4mb

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
1009	B01-079		90	1.1	
1012	B01-077		270	1.2	OPEN PORT & CUTOFF TO 58°
1016	B01-087		270	1.2	FILL
	SWITCH REACH	TO	B02		
1022	B02-070		264	1.0	
1027	B02-067		84	1.0	
1031	B02-064		264	1.0	
1036	B02-061		84	1.0	
1041	B02-058		264	1.0	
1046	B02-055		84	1.0	SUNKEN BARGE ON LINE
1050	B02-055		264	1.0	" " " " FILL
1057	B02-127		84	1.0	
1101	B02-131		264	1.0	
1106	B02-134		84	1.0	OPEN PORT CUTOFF &
1111	B02-139		264	1.0	OPEN STBD CUTOFF &
1118	B02-142		84	1.0	" PORT " "
	SV CAST	B02	@	11:25	
1130	B02-078		84	1.1	
1134	B02-077		264	1.1	
1138	B02-080		84	1.1	

Prepared by: PAS / ECD

Page 3 of 7

GBA MULTIBEAM SURVEY LOG

Date 6/13/2010
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory PASSAIC RIVER MB

Echo Sounder Reson 8101

Matrix/LNW File B02/B03

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) 5

General Remarks

People 3

HORZ/VERT CHECKIN

Time RTK Tide Tide Board

S.O.S./Draft 40XAG/3.4MB

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
1144	B02-088		264	1.4	
1150	B02-087		84	1.4	
1154	B02-090		264	1.6	
1159	B02-091		84	1.7	
1203	B02-097		264	1.4	
1209	B02-101		84	1.1	
1212	B02-107		264	1.3	NOTE B02-072 INFILE
1218	B02-110		84	1.3	+ B02-07
1222	B02-114		264	1.2	
1227	B02-119		84	1.2	
1231	B02-122		264	1.2	
1237	B02-125		84	1.2	FILE
	BEGUN	NEW REACH	B03		
1255	B03-114		249	1.1	
1300	B03-118		69	1.2	
1303	B03-122		249	1.2	
1307	B03-126		69	1.1	
1311	B03-130		249	1.1	
1316	B03-110		69	1.0	
1319	B03-106		249	1.0	

Prepared by: _____

Page 4 of 7

GBA MULTIBEAM SURVEY LOG

Date 6/13/2010
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory Passaic 2010SB

Echo Sounder Reson 8101

Matrix/LNW File Passaic Single Beam

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) _____

General Remarks Barcheck @ 14:15

People _____

HORZ/VERT CHECKIN

Time _____ RTK Tide _____ Tide Board _____

S.O.S./Draft 4959 / 1.1

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
14:21	148	0148	148	1.1	
14:23		0148A	328	1.1	
14:24	143	0143	162°	1.1	
		0143A	342°	1.1	
14:28	138	0138	165°	1.1	
14:28		0138A	345°	1.1	
14:31	133	0133	171°	1.1	
14:32		0133A	351°	1.1	
14	128	0128	172	1.1	
		0128			
14:35	Leica	Server down			14:44 Back up
14:44	128	0128	172°	1.1	
14:45	128	0128A	352°	1.1	
14:48	123	0123	173	1.1	
14:49		0123A	353	1.1	
14:51	118	0118	173	0.9	
14:52	1	0118A	353		
14:54	113	0113	172		
14:56	113A	0113A	352		

Prepared by: ECD

Page 6 of 7

GBA MULTIBEAM SURVEY LOG

Date 6/13/2010
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory Passaic Single Beam Echo Sounder Reson 8101

Matrix/LNW File _____ Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) _____

General Remarks _____

People _____

HORZ/VERT CHECKIN

Time RTK Tide Tide Board

S.O.S./Draft 4.57

16:09 -1.35 -1.30

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
<u>14:58</u>	<u>107</u>	<u>0107</u>			
		<u>0107A</u>			
<u>15:00</u>	<u>109</u>	<u>109</u>			<u>Do not use</u>
<u>15:10</u>	<u>107</u>	<u>107A</u>	<u>179°</u>	<u>1.0</u>	
<u>15:19</u>	<u>109</u>	<u>109B</u>	<u>38°</u>	<u>1.0</u>	
<u>15:21</u>	<u>104</u>	<u>104</u>	<u>184</u>	<u>1.0</u>	
<u>15:23</u>		<u>104A</u>	<u>4°</u>	<u>2.8</u>	
<u>15:25</u>	<u>101</u>	<u>101</u>	<u>197°</u>	<u>1.0</u>	
<u>15:26</u>		<u>101A</u>	<u>7°</u>	<u>1.0</u>	
				<u>B01 → B03</u>	
<u>B01</u>	<u>141</u>	<u>15130</u>	<u>405</u>	<u>+ RTK</u>	<u>North Shore Long Line</u>
<u>15:36</u>	<u>B01</u>	<u>101A</u>			<u>RESUMED North Shore</u>
<u>15:42</u>	<u>B01</u>	<u>136</u>	<u>mid channel</u>	<u>Long</u>	<u>Line B03 → B01</u>
<u>15:49</u>	<u>B01</u>	<u>092</u>	<u>South Channel</u>	<u>Long Line</u>	<u>B01 → B03</u>
<u>16:00</u>		<u>Bar check</u>	<u>15', 10', 5'</u>		
<u>16:34</u>		<u>Position check @ Dock</u>			
		<u>578042.25</u>	<u>600439.61</u>		

Prepared by: ECD

Page 7 of 7

GBA MULTIBEAM SURVEY LOG

Date 6/15/2010
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory Passaic MD

Echo Sounder Reson 8101

Matrix/LNW File B04

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) 5.15

General Remarks 07:00 Position check @ Dock

People 2

HORZ/VERT CHECKIN

Time RTK Tide Tide Board

S.O.S./Draft 4993/3.4

07:33 -0.37 -0.30

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
07:00		Position check @ Dock			578041.98 660438.76
		RESO Settings			
		RNG = 20m			
		max Rate = 20 p/s			
		Tx Power = 4			
		Tx Pulse = 63			
		Gain Mode = TUG			
		Auto Gain = 4			
07:19	B04-060		213	1.4	
07:53	B04-063		33°	1.4	
07:59	B04067		213°	1.4	
08:03	B04-070		33°	1.4	
08:09	B04-073		213°	1.4	
8:12	B04-074		33°	1.4	
8:17	B04-078		213°	1.5	
8:21	B04-071		33°	1.5	
8:25	B04-087		213	1.6	
8:30	B04-088		33°	1.7	
8:34	B04-091		213	1.	
8:37	B04-094		33°		

Prepared by: ECB

Page 1 of 9

GBA MULTIBEAM SURVEY LOG

Date 6/15/10
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory B04

Echo Sounder Reson 8101

Matrix/LNW File _____

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) 5kts

General Remarks _____

People 2

HORZ/VERT CHECKIN

Time RTK Tide Tide Board

S.O.S./Draft 4893 / 3.4

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
8:41	B04-097		213	1.2	
8:44	B04-100		33°	1.2	
8:49	B04-103		213°	1.3	
8:53	B04-057		33°	1.3	
8:59	B04-054		213°	1.3	
9:03	B04-051		33°	1.3	
9:01	B04-048		213°	1.3	
9:12	B04-045		37°	1.3	
9:17	B04-42		213°	1.1	
9:21	B04-039		33°	1.1	
9:27	B04-036		213	1.3	Dropped RTK Restart
9:27	B04-036 A		213°	1.3	open Port Beams 70°
9:34	B04-034		33°	1.1	open STRD 70°
9:39	B04-0038		213	1.1	
9:41	B04-031		33°	1.1	
9:44	B04-097		213°	1.2	
9:49	B04-080		33°	1.2	
9:51	B04-105		213°	1.1	open 5+BD Beams to shoreline
10:00	B04-102		33°	1.2	
10:03	284				698 F11

Prepared by: ECD

Page 2 of 9

GBA MULTIBEAM SURVEY LOG

Date 6/15/10
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory B04/B03

Echo Sounder Reson 8101

Matrix/LNW File _____

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) _____

General Remarks _____

People 2

HORZ/VERT CHECKIN

Time RTK Tide Tide Board

S.O.S./Draft 4934 / 03.4

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
10:05	B04-053	-	Gap Fill		
10:07	B04-049		Gap Fill		
10:08	B04-062		Gap Fill		
10:13		SV Cas +	B03		
		JW146 + 0	B03		
10:19	B03-078		69°	1.1	
10:24	B03-075		249°	1.1	
10:27	B03-072		69°	1.0	
10:31	B03-069		249°	1.0	
10:35	B03-066		69°	1.0	
10:38	B03-063		249°	1.0	
10:42	B03-060				Gap Fills
10:42	B034-				
10:44	B03-058		249°	1.0	
10:46	B03-055		67°		
10:48	B03-052				
10:52	B03-029		249°	1.1	
	B03-128				Port Beams 60°
11:02	B03-133				stbd 70°
11	B03-091				Gap fills

Prepared by: ECO

Page 3 of 9

GBA MULTIBEAM SURVEY LOG

Date 6/15/10
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory B03 + B05

Echo Sounder Reson 8101

Matrix/LNW File _____

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) _____

General Remarks _____

People _____

HORZ/VERT CHECKIN

Time RTK Tide Tide Board

S.O.S./Draft _____

11:20 4.10 4.20

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
<u>11:10</u>	<u>B03-080</u>				<u>Gap Filling</u>
<u>11:12</u>	<u>B03-089</u>				<u>Gap Filling</u>
<u>11:14</u>	<u>B03-131</u>				<u>Gap Filling</u>
<u>11:29</u>	<u>B02-100</u>				<u>Gap Filling @ B02</u>
	<u>18 min</u>	<u>day</u>			<u>TIME - check</u>
	<u>Switch</u>	<u>B05</u>			
<u>11:39</u>	<u>B05-059</u>		<u>232°</u>	<u>1.6</u>	
<u>11:41</u>	<u>B05-062</u>		<u>52°</u>		
<u>11:43</u>	<u>B05-065</u>		<u>232</u>	<u>1.9</u>	
<u>11:44</u>	<u>B06-068</u>		<u>52°</u>		
<u>11:46</u>	<u>B06-071</u>		<u>232°</u>	<u>1.6</u>	
<u>11:48</u>	<u>B06-074</u>		<u>52°</u>	<u>1.0</u>	
<u>11:50</u>	<u>B06-077</u>		<u>232°</u>	<u>1.0</u>	
<u>11:51</u>	<u>B06-080</u>		<u>52°</u>	<u>1.1</u>	
<u>11:53</u>	<u>B06-022</u>		<u>52°</u>	<u>1.4</u>	<u>South shore</u>
<u>11:55</u>	<u>B06-014</u>		<u>232°</u>		<u>op Port 60°</u>
<u>11:58</u>	<u>B06-017</u>		<u>52°</u>	<u>1.3</u>	<u>Starboard 60°</u>

Prepared by: ECB

Page 4 of 7

GBA MULTIBEAM SURVEY LOG

Date 6/15/10
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory BOG

Echo Sounder Reson 8101

Matrix/LNW File _____

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) _____

General Remarks _____

People 2

HORZ/VERT CHECKIN

Time RTK Tide Tide Board

S.O.S./Draft 49.34 / 3.4

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
		<u>Switch To</u>	<u>BOG</u>	<u>Edges</u>	<u>while High Tide</u>
<u>12:02</u>	<u>BOG-106</u>		<u>265°</u>	<u>1.1</u>	
<u>12:06</u>	<u>BOG-109</u>		<u>85°</u>	<u>1.3</u>	
<u>12:10</u>	<u>BOG-112</u>		<u>265°</u>	<u>1.3</u>	
<u>12:14</u>	<u>BOG-115</u>		<u>85°</u>	<u>1.2</u>	
<u>12:18</u>	<u>BOG-118</u>		<u>265</u>	<u>1.2</u>	
<u>12:23</u>	<u>BOG-121</u>		<u>85°</u>	<u>1.2</u>	
<u>12:27</u>	<u>BOG-124</u>		<u>265°</u>	<u>1.2</u>	
<u>12:32</u>	<u>BOG-127</u>		<u>85°</u>	<u>1.2</u>	
<u>12:37</u>	<u>BOG-130</u>		<u>265°</u>	<u>1.2</u>	
<u>12:42</u>	<u>BOG-133</u>		<u>85°</u>	<u>1.2</u>	<u>East end shore</u>
<u>12:45</u>	<u>BOG-136</u>		<u>265</u>		
<u>12:47</u>	<u>BOG-135</u>		<u>85</u>	<u>1.2</u>	
<u>12:49</u>	<u>BOG-138</u>		<u>265°</u>		
<u>12:51</u>	<u>BOG-141</u>		<u>85°</u>		
<u>12:57</u>	<u>BOG-144</u>		<u>265°</u>	<u>1.0</u>	
<u>13:01</u>	<u>BOG-148</u>		<u>85°</u>	<u>1.0</u>	
<u>13:07</u>	<u>BOG-157</u>		<u>265</u>	<u>1.2</u>	
<u>13:13</u>	<u>BOG-160</u>		<u>85°</u>	<u>1.1</u>	<u>off BO Beam 60° pilings</u>
<u>13:19</u>	<u>BOG-151</u>		<u>265°</u>	<u>1.2</u>	<u>port 60° shoreline</u>

Prepared by: LCO

Page 5 of 9

GBA MULTIBEAM SURVEY LOG

Date 6/15/10
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory B06

Echo Sounder Reson 8101

Matrix/LNW File _____

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) 5

General Remarks _____

People 2

HORZ/VERT CHECKIN
Time RTK Tide Tide Board

S.O.S./Draft 4724 / 34

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
13:25	B06-0650		85°	1.2	
13:29	B06-067		265°	1.1	
13:31	B06-59		85°	1.1	
13:32	B06-056		265°	1.1	
13:36	B06-53		85°	1.1	
13:39	SV Cast B06			mi	
	middle sections of B06 & B05				
13:42	B06-072		265°	1.1	
13:46	B06-075		85°	1.1	
13:51	B06-081		265°	1.1	
13:56	B06-083		85°	1.4	
13:59	B06-086		265°	1.1	
14:05	B06-089		85°	1.1	
14:07	B06-092		265°	1.1	
14:14	B06-095		85°	1.1	
14:18	B06-100		265°	1.1	DO NOT USE - RTF DEEP
14:20	B06-101		265°	1.1	
14:26	B06-109		85°	1.3	

Prepared by: ECO

Page 6 of 7

GBA MULTIBEAM SURVEY LOG

Date 0/15/10
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory Passaic SB

Echo Sounder Reson 8101

Matrix/LNW File _____

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) _____

General Remarks _____

People _____

HORZ/VERT CHECKIN
Time RTK Tide Tide Board

S.O.S./Draft 11.1

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
1515		Bar check		@ 5, 15, 10, 5	
1521	0197	0197	358	1.0	
1522		0197A	178°		
1525	0192	0192	358		
1526		0192A	178		
1528	0188	0188	356		
1529		0188A	176		
1531	0183	0183	350		
1532		0183A	170		
1534	0178	0178	340°		
1536		0178A	160°		
1539	0173	0173	328°		
1541		0173A	148		
1543	0168	0168	300°		
1544		0168A	120°		
1546	0163	0163	297°		
1547		0163A	117°		
1549	0158	0158	296°		
1550		0158A	116		

Prepared by: GCW

Page 8 of 9

GBA MULTIBEAM SURVEY LOG

Date 6/15/10
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory Passaic SB

Echo Sounder Reson 8101

Matrix/LNW File _____

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) 5

General Remarks _____

People 2

HORZ/VERT CHECKIN

Time RTK Tide Tide Board

S.O.S./Draft 11

16:54 -1.15 -1.10

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
15:51	0153	0153	314°		
15:53		0153A	139		
15:55	0148	0148	328°		
15:56		0148A	198		
15:58	0143	0143	342°		
15:59		0143A	162°		
16:01	0138	0138	345°		
16:02		0138A	165°		
16:04	0133	0133	351		
16:05		0133A	171		

Long Lines

West/South shoreline 000-1608.RAW B03 → B06

Center line 000-1621.RAW B06 → B03

East/North Toe line 000-1633.RAW

16:46 Backcheck @ Jackson St Bridge B06
15', 10', 5'

16:54 RTK time check

16:19:29 Pos. log check @ dock

Prepared by: ECO

Page 7 of 9

GBA MULTIBEAM SURVEY LOG

Date 6/16/10
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory Passaic 2010 MB

Echo Sounder Reson 8101

Matrix/LNW File B07

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) 5

General Remarks

People 2

HORZ/VERT CHECKIN

S.O.S./Draft 4890 / 3.4

Time RTK Tide Tide Board

7:30 -1.80 -1.75

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
7:05		Position check @ Dock			579091.65, 660437.19
7:35		RTK Tide check @ "PORT"			
07:40		SV Cast @ B07			
		RESON Settings			
		RNG = 20m			
		Max Rate = 20 p/s			
		Tx Pulse = 63 us			
		Tx Power = 4			
		Ant gain = 4			
07:48	B07-031		75°	1.5	Bridge @ End
07:51	B07-028		275°	1.4	Bridge @ Start
07:53	B07-025		75°	1.4	open Beam = STBD side wall!
07:58	B07-022		95°	1.4	open Beams Port STBD Dropped
08:17	B07-022A		95°	1.5	
8:20	B07-033		95°	1.6	Bridge @ End
8:24	B07-036		275	1.2	Bridge @ Start
8:26	B07-037		95°	1.1	End @ Bridge
8:30	B07-040		95°	1.2	
8:31	B07-043		275	1.7	
8:32	B07-047		95°	1.2	under Bridge @ end

Prepared by: ECD

Page 1 of 7

GBA MULTIBEAM SURVEY LOG

Date 6/16/10
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory Passaic 2010 MB

Echo Sounder Reson 8101

Matrix/LNW File BO7

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) _____

General Remarks _____

People 2

HORZ/VERT CHECKIN

Time RTK Tide Tide Board

S.O.S./Draft 4850 / 3.4

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
8:35	BO7-051		275°	1.2	Bridge @ Start
8:37	BO7-054		95°	1.2	Bridge @ End
8:40	BO7-058		275°	1.2	Bridge @ Start
8:42	BO7-061		95°	1.2	
8:48	BO7-064A		95°	1.3	and @ Bridge
8:50	BO7-067		275°	1.3	
8:51	BO7-070		95°	1.3	
8:54	BO7-073		275°		
8:55		SU Cast	BO8		
8:58	BO8-021		275°	1.3	
9:01	BO8-025		115°	1.5	
9:03	BO8-022		275°	1.3	wall construction
9:05	BO8-019		115°	1.3	open STBD 60° - Wall
9:10	BO8-033		275°	1.3	
9:12	BO8-036		115°	1.3	
9:15	BO8-039		275°	1.3	
9:17	BO8-044		115°	1.5	
9:19	BO8-050		275°	1.5	
9:21	BO8-054		115°	1.3	

Prepared by: ECO

Page 2 of 9

GBA MULTIBEAM SURVEY LOG

Date 8/16/10
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory Passaic MB 2010

Echo Sounder Reson 8101

Matrix/LNW File RO8 / BO7

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) _____

General Remarks _____

People 2

HORZ/VERT CHECKIN

Time RTK Tide Tide Board

S.O.S./Draft 4924 / 3.4

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
9:23	BO8-057		295	1.3	
9:25	BO8-060		115°	1.3	
9:27	BO8-063		295	1.3	
9:29	BO8-066		115	1.3	
9:31	BO8-069				
		SW+KH	To BO9		
9:37	BO9-018		317°	1.3	End @ Bridge
9:39	BO9-015		137°	2.6	c.
9:41	BO9-013		317	1.1	wall on Port Side
9:42	BO9-010		137	1.5	
9:44	BO9-008		317°	1.3	Port Beam 70°
9:47	BO9-022		137°	1.3	
9:51	BO9-026		317°	1.3	
9:51	BO9-030		137°	1.2	
9:53	BO9-034		317°	1.2	under Bridge Lost RTK
9:55	BO9-037		137°	1.3	under Bridge Lost RTK
9:57	BO9-044		317°	1.2	under Bridge Lost RTK
10:00	BO9-050		137°	1.2	under Bridge " " "
10:03	BO9-053		317°	1.2	" "
10:05	BO9-057		137	1.3	

Prepared by: ECB

Page 3 of 9

GBA MULTIBEAM SURVEY LOG

Date 8/16/10
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory Passaic 2010 MR

Echo Sounder Reson 8101

Matrix/LNW File B07

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) 5

General Remarks

People 2

HORZ/VERT CHECKIN

Time RTK Tide Tide Board

S.O.S./Draft 4924 / 3.4

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
10:08	B09	060	310°	1.1	
10:10	B09	064	130°	1.2	
10:13	B09	067	310°	1.1	
10:15	B07	070	130°	1.2	
10:18	B07	071			
		B8 Edge			
10:22	B09	001	115°	1.0	
10:25	B08	002	135°	1.0	
		B07 Edge			
10:30	B07	097	95°	1.0	
10:32	B07	072	275°	1.0	
	B07	035	95°	1.0	
		Switch To	CO1		
10:37	SV	Cast			
10:44	CO1	082	155°	1.1	
*	CO1	086	1		DO NOT USE
10:48	CO1	085	155°	1.0	
10:51	CO1	088	1335°	1.2	
10:53	CO1	91	155°		

Prepared by: ECO

Page 4 of 9

GBA MULTIBEAM SURVEY LOG

Date 6/16/10
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory Col

Echo Sounder Reson 8101

Matrix/LNW File _____

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) _____

General Remarks _____

People _____

HORZ/VERT CHECKIN

Time RTK Tide Tide Board

S.O.S./Draft 4913 / 3.4

12:05 4.10 4.10

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
10:57	CO1-026		155°	1.2	lost RTK @ Bridge
11:00	CO1-023		155°		
11:03	CO1-020		335°	1.2	DO NOT USE Lost RTK
11:05	CO1-020 A		155°	1.1	
11:08	CO1 019		335°	1.1	lost RTK Briefly
11:09	CO1 018		155°	1.2	
11:12	CO1 015		335°	1.2	
11:14	CO1 014		155°		
	Switch	CO2	Edges		
11:17	CO2-017		342°	1.2	stop @ Bridge
	CO2-014		162°	1.5 open	steep wall on StBD
					open StBD Beams
11:30	CO2-082		342°	1.4	
11:36	CO2-083		162°		open Port Beam steep slope/wall
11:41	CO2-089		342°		StBD Beam 60°+
11:47	CO2-078		162°	1.6	
11:51	SV Cast	CO2			
12:05	RTK	Tide	Check		@ Port

Prepared by: ECO

Page 5 of 9

GBA MULTIBEAM SURVEY LOG

Date 6/16/10
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory Passaic 2010 MB

Echo Sounder Reson 8101

Matrix/LNW File CO1

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) 4

General Remarks

People 2

HORZ/VERT CHECKIN

Time RTK Tide Tide Board

S.O.S./Draft 4924 / 3.4

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
1	12:14	SV	cast	CO16	
12:23	CO1-062		155°	1.2	
12:27	CO1-079		155°	1.2	
12:30	CO1-076		155°	1.2	
12:33	CO1-071		155°	1.2	
12:37	CO1-068		155°	1.2	
12:40	CO1-065		155°	1.2	
12:43	CO1-062		155°	1.2	
12:45	CO1-056		155°	1.2	
12:49	CO1-053		155°	0.7	
12:52	CO1-049		155°	1.0	
13:04	CO1-044		155°	1.0	
13:09	CO1-038		155°	1.0	
13:11	CO1-034		335°	1.0	
13:13	CO1-030		155°	1.0	
13:15	CO1-27		335°	1.2	

Prepared by: ECN

Page 6 of 9

GBA MULTIBEAM SURVEY LOG

Date 6/16/10
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory Passaic 2010.mB

Echo Sounder Reson 8101

Matrix/LNW File C02

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) 5 kts

General Remarks SU Cast 14:45 Coa B

People 2

HORZ/VERT CHECKIN

Time RTK Tide Tide Board

S.O.S./Draft 4924/3.4

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
13:18	C02-019		342°	1.1	
13:24	C02-022		162°	1.1	
13:25	C02-026		162°	1.1	Do NOT USE
13:28	C02-026A		162°	1.1	
13:32	C02-028		342°	1.1	
13:38	C02-032		162°	1.1	
13:42	C02-036		342°	1.1	
13:48	C02-040		162°	1.1	
13:53	C02-043		342°	1.1	
13:58	C02-040		162°	1.2	
14:02	C02-052		342°	1.2	
14:09	C02-056		162°	1.1	
14:14	C02-060		342°	1.1	
14:19	C02-064		162°	1.3	
14:24	C02-068		342°	1.1	
14:30	C02-072		162°	1.3	
14:32	C02-074		162°	1.1	
14:37	C02-075		342°	1.1	
14:40	C02-053				Gap
14:41	C02-053A				Gap Fill
14:42	C02-023				Gap Fill

Prepared by: ECO

Page 7 of 7

GBA MULTIBEAM SURVEY LOG

Date 6/16/2010
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory Single Beam

Echo Sounder Reson 8101

Matrix/LNW File _____

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) _____

General Remarks _____

People _____

HORZ/VERT CHECKIN

Time RTK Tide Tide Board

S.O.S./Draft 496 / 1.1

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
14:52		Barcheck	5', 10', 5'		
14:56	249	249	75°	1.0	
14:57		249A	255°		
14:59	245	245	72°		
		245A	252°		
15:01	240	240	72°	0.8	
15:02		240A	252		
15:04	235	235	72	1.0	
15:05		235A	252		
15:07	230	230	72°	1.0	
15:08		230A	252°		Dis Regard R File
15:10	225	225	69°	1.6	
15:11		225A	249		
15:13	220	220	64°	1.0	
		220A	244		
15:20	215	215	41°	1.4	
15:21		215	221°	0.9	
15:23	210	210	213°	0.9	
15:25	210	210AC	33	0.7	

Prepared by: ECD

Page 8 of 9

GBA MULTIBEAM SURVEY LOG

Date 6/17/2010
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory P01/Passaic

Echo Sounder Reson 8101

Matrix/LNW File in Newark Bay

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) _____

General Remarks _____

People _____

HORZ/VERT CHECKIN

Time RTK Tide Tide Board

S.O.S./Draft 4996 / 3.4

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
07:02		Position check @ Dock			75092.21, 660439.55
		Mid-Survey Performance Test			
07:20		50 Profile @ Performance			
		Multibeam			
7:27	001 - 0727				Reson 50m
7:28	002 - 0728				Also with 75 m
7:29	003 - 0729				
7:30	004 - 0730				
7:32	005 - 0732				
7:33	006 - 0733				
7:34	009 - 0734				
7:35	010 - 0735				
7:37	011 - 0737				
7:39	012 - 0739				
		Bar check 5', 45', 30', 15', 5'			
		Single Beam Lines			
	001 - 0746			008 - 800	
	002 - 0748			009 - 0759	
	003 - 0750			010 - 0758	
	004 - 0751			011 - 0757	
	005 - 0752 DO NOT USE			012 - 0756	
	006 - 0754				

Prepared by: FLD

Page 1 of 13

GBA MULTIBEAM SURVEY LOG

Date 8/17/10
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory C03

Echo Sounder Reson 8101

Matrix/LNW File _____

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) _____

General Remarks _____

People 3

HORZ/VERT CHECKIN

Time RTK Tide Tide Board

S.O.S./Draft _____

8:15 -1.50 -1.50 Ant 23'

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
8:18		RTK Tide Check @ Port			
	C03	SU Cast			UNDER BRIDGES!
8:38	C03	-025			Under Bridge
8:40	C03	-028			Under Bridge
8:40	C03	-031			Under Bridge
8:41	C03	-034			Under Bridge
8:43	C03	-035			"
8:44	C03	-023			"
8:45	C03	-055	176°		" extended "
8:47	C03	-058	356°		"
8:48	C03	-061	176°		"
8:50	C03	-067	356°		"
8:52	C03	-068	176		"
8:53	C03	-058			"
8:55	C03	-052			"
8:58	C03	-036			"
8:59	C03	-033			"
9:00	C03	-030			"
9:02	C03	-027			"
9:04	C03	-024			"

Prepared by: ECD

Page 2 of 13

GBA MULTIBEAM SURVEY LOG

Date 8/17/10
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory C03

Echo Sounder Reson 8101

Matrix/LNW File _____

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) _____

General Remarks _____

People 3

HORZ/VERT CHECKIN

Time RTK Tide Tide Board

S.O.S./Draft 4890 / 3.4

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
9:06	C03-19		176°	1.3	open air lines
9:08	C03-21		356	1.5	
9:10	C03-24		176°	1.3	
9:12	C03-27		356°	1.5	
9:13	C03-33A		176°	1.5	
9:15	C03-036A		356°	1.3	
9:16	C03-042		176°	1.1	
9:18	C03-046		356°	1.3	
9:20	C03-049		176°	1.5	
9:22	C03-055		356	1.3	
9:23	C03-059		176°	1.5	
9:24	C03-066		356°	1.3	
9:26	C03-069		176°	1.3	
9:28	C03-072		356°	1.3	
9:30	C03-075		176°	1.4	

Prepared by: CD

Page 3 of 13

GBA
MULTIBEAM SURVEY LOG

Project ID #	631-10A
Description	Passaic River Multibeam

Echo Sounder Reson 8101

Positioning POSMV 320 w/ Leica RTK

General Remarks SV Cast COY 9:35

HORZ/VERT CHECKIN		
Time	RTK Tide	Tide Board

Time	RTK Tide	Tide Board
------	----------	------------

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
9:38	C04_064		8°	1.2	
9:41	C04_067		188°		
	C04_070		8°	1.4	
9:48	C04_062		180°	1.2	Do not use
9:49	C04_062A		8°	1.2	
9:51	C04_059		188°	1.2	
9:57	C04_055		8°	1.3	
9:59	C04_055A		8°	1.3	
10:01	C04_052		188°	1.1	
10:04	C04_046		8°	1.6	
10:06	C04_043		188°	1.1	
10:07	C04_040		8°	1.2	
10:09	C04_36		188°	1.2	
10:11	C04_31		8°	1.6	
10:16	C04_27		180°	1.2	
10:16	C04_24				
10:18	C04_21				

Page 4 of 13

GBA MULTIBEAM SURVEY LOG

Date 6/17/10
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory _____

Echo Sounder Reson 8101

Matrix/LNW File COS

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) 5

General Remarks 10:23 SU Cast COS

People 3

HORZ/VERT CHECKIN
Time RTK Tide Tide Board

S.O.S./Draft 4892

Gap under clay st Bridge

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
10:28	COS-058		70	1.0	
10:30	COS-061		187	1.7	
10:32	COS-064		70	1.7	
10:35	COS-55		187	1.7	
10:38	COS-50		70	1.0	
10:43	COS-047		187	1.0	
10:48	COS-044		7	1.0	DIFF C EJO
11:02	COS-044		187	2.0	RUN N-SIDE
11:08	COS-041		7	1.9	
11:12	COS-038		187	1.8	
11:17	COS-035		7	1.8	
11:21	COS-032		187	2.0	
11:27	COS-029		7	2.0	FOLIAGE
11:50	COS-26		187		open S+BD Beams Trees
11:35	COS-23		7	1.4	
11:38	COS-65		187	1.1	TREE
11:41	COS-608		70		NO RTK Dont USE
11:44	COS-684		187		open Port Beams
11:49	COS-45		70		Gap Fill
11:50	COS-		187		Gap Fill

Prepared by: ECO

Page 5 of 13

GBA
MULTIBEAM SURVEY LOG

Project ID #	631-10A
Description	Passaic River Multibeam

Echo Sounder Reson 8101

Positioning POSMV 320 w/ Leica RTK

General Remarks

HORZ/VERT CHECKIN
 Time RTK Tide Tide Board

Time	RTK Tide	Tide Board
------	----------	------------

[illegible]

Page 6 of 13

GBA MULTIBEAM SURVEY LOG

Date 6/17/10
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory _____

Echo Sounder Reson 8101

Matrix/LNW File _____

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) _____

General Remarks 12:45 JV Cas + COG

People _____

HORZ/VERT CHECKIN
Time RTK Tide Tide Board @ 12/4

S.O.S./Draft _____

12:43 3.81 3.76

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
		RTK Tide check "PATH 3"			
12:52	COG-10		196°	2.1	
12:54	COG-07		16	1.8	
12:57	COG-04		196	1.9	BEAMS OPEN STRD
12:59	COG-57		16	1.7	
13:00	COG-60		196	1.6	
13:01	COG-63		16	1.6	
13:02	COG-66		196	1.6	
13:04	COG-69		16	1.9	
13:05	COG-72		196	1.9	
	COG-75		16		
13:10	COG-019		25°	2.0	
13:13	COG-016		205°	2.1	
13:16	COG-013		25°	1.9	OPEN BEAMS PORT
13:22	COG-073		205	2.1	
13:24	COG-076		25	2.2	
13:27	COG-079		205	2.1	
13:31	COG-55		196	2.1	
13:34	COG-52		16	2.3	
13:36	COG-49		196	2.4	

Prepared by: _____

Page 7 of 13

GBA MULTIBEAM SURVEY LOG

Date 6/17/10 Project ID # 631-10A
 Vessel Name Sea Fix Description Passaic River Multibeam

Raw Data Directory _____ Echo Sounder Reson 8101
 Matrix/LNW File _____ Positioning POSMV 320 w/ Leica RTK
 Average Boat Speed (kts) _____ General Remarks _____
 # People _____ HORZ/VERT CHECKIN _____
 S.O.S./Draft _____ Time _____ RTK Tide _____ Tide Board _____

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
13:37	C06-46		16	2.0	
13:38	C06-43		196	2.4	
13:39	C06-40		16	2.0	
13:41	C06-37		196	2.5	
13:43	C06-37		16	2.5	
13:44	C06-34		196	2.5	
13:45	C06-27		16	2.5	
13:46	C06-24		196	2.5	
13:48	C06-17		16	2.0	
13:51	C07-22		25	2.6	
13:54	C07-025		205	2	
13:57	C07-028		25	2.1	
13:59	C07-025		205	2.2	
14:02	C07-042		25	2.2	
14:05	C07-046		205	2.0	
14:07	C07-050		25	2.3	
14:10	C07-054		205	2.4	
14:12	C07-058		25	2.0	
14:15	C07-062		205	2.3	
14:17	C07-066		25	2.2	

Prepared by: _____

Page 8 of 13

GBA MULTIBEAM SURVEY LOG

Date 6/17/10
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory _____

Echo Sounder Reson 8101

Matrix/LNW File C08 + C07

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) 5

General Remarks 14:20 JV Cast C08

People 3

HORZ/VERT CHECKIN
Time RTK Tide Tide Board

S.O.S./Draft 4900/3.4

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
14:20	C07-069		205	2.0	
14:22	C07-067		25	2.2	SM. AT. PICK UP
		Switch	C07		
14:30	C08-81		35	1.1	
14:35	C08-83		215		open Port Beams shoreline
14:37	C08-86		35		open STBD Beams 60°
14:44	C08-75		215	1.7	
14:49	C08-74		35	2.0	
14:53	C08-31		215	1.9	
14:57	C08-29		35	1.9	OPEN PORT BEAMS - SHORE - LOET NTK
15:00			35	2.0	RE-RUN - LOET NTK
15:04	C08-28		215	1.9	OPEN STBD BEAMS - SHORE
15:06	C08-36		215	1.9	
15:10	C08-40		35	1.7	
15:15	C08-43		215	1.7	
15:18	C08-46		35	1.9	
15:22	C08-49/50		215	1.7	
15:26	C08-53		35	1.7	
15:31	C08-56		215	1.7	
15:34	C08-59		35	1.7	

Prepared by: _____

Page 9 of 13

Project ID #	631-10A
Description	Passaic River Multibeam

Page 10 of 13

GBA MULTIBEAM SURVEY LOG

Date 8/17/10
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory Passaic SB

Echo Sounder Reson 8101

Matrix/LNW File _____

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) _____

General Remarks _____

People 3

HORZ/VERT CHECKIN
Time RTK Tide Tide Board

S.O.S./Draft 4909/1.2

17.53 - 0.7 - 0.6 Am 1 Hgt 2.5'

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
16:00		Bat check	5', 15', 10', 5'		
16:05	0330	330	304	1.3	
16:10		330	124		
16:12	0325	0325	304	1.3	
16:13		0325A	124		
16:15	0320	0320	305		
16:16		0320A	125		
16:18	0315 0315	0315	304		
16:19		0315A	124		
16:20	0310	0310	299	1.3	
16:21		0310A	119		
16:23	0305	0305	298	2.0	
16:24		0305A	118		
16:26	0300	0300	285		
16:27		0300A	105		
16:29	0295	0295	278		
16:30		0295A	98		
16:31	0290	0290	279		
16:32		0290A	99		

Prepared by: ECO

Page 11 of 13

GBA MULTIBEAM SURVEY LOG

Date 6/17/10 Project ID # 631-10A
 Vessel Name Sea Fix Description Passaic River Multibeam

Raw Data Directory PASSAIC SB Echo Sounder Reson 8101
 Matrix/LNW File _____ Positioning POSMV 320 w/ Leica RTK
 Average Boat Speed (kts) 7 General Remarks _____
 # People 3 HORZ/VERT CHECKIN _____
 S.O.S./Draft 4909/1.2 Time RTK Tide Tide Board _____

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
	0285	0285			
		0285A			
16:34		EAST SHORE		2.1 1.8	LONGITS COS - COB
16:43		CENTERLINE			LONGITS "
16:50		WEST SHORE			" "
17:02	0283	0283			
17:03		0283A		2.0	SB - XS
17:05	0277	0277		1.8	
17:06	"	0277A		1.8	
	0272	0272	289	1.8	
		0272A	82		
17:08		WEST BANK		1.4	LONGITS COS - COB
17:10		CENTERLINE			"
17:13		EAST BANK			"
17:17	0269	0269	18	1.4	SB - XS
17:18		0269A	278		
17:20	0266	0266	48	2.0	
17:23		0266A	278		
17:24		EAST BANK		2.3	LONGITS COS - COB
17:26		"			"
17:28		WEST BANK			"

Prepared by: _____

Page 12 of 13

GBA MULTIBEAM SURVEY LOG

Date 6/18/10
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory Passaic 2010.m3

Echo Sounder Reson 8101

Matrix/LNW File COY

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) _____

General Remarks

People 2

HORZ/VERT CHECKIN

Time RTK Tide Tide Board

S.O.S./Draft _____

7:46 -1.40 -1.35

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
<u>7:06</u>		<u>Position check @ Dock</u>			<u>Port Elizabeth</u>
			<u>579040.12</u>		<u>579041.75, 660439.06</u>
<u>7:46</u>		<u>Tide check @ Port</u>			<u>Clay ST Bridge Fill'n</u>
<u>8:04</u>	<u>COY-05</u>		<u>Fill'n</u>		
<u>8:05</u>	<u>COY-57</u>		<u>8°</u>		<u>RFSON Settings</u>
<u>8:08</u>	<u>COY-061</u>		<u>188°</u>		<u>RNG 20m</u>
<u>8:09</u>	<u>COY-66</u>		<u>8°</u>		<u>Pulse Rate @ 20p/s</u>
<u>8:11</u>	<u>COY-38</u>		<u>188°</u>		<u>Pulse Width 63-sec</u>
<u>8:12</u>	<u>COY-33</u>		<u>8</u>		<u>Tx Power 4</u>
<u>8:13</u>	<u>COY-28</u>		<u>188°</u>		<u>Autogain 4</u>
<u>8:14</u>	<u>COY-25</u>		<u>8°</u>		

SOUND VELOCITY CAST @ 09:20 =4891.7

Prepared by: ECN

Page 1 of 8

GBA MULTIBEAM SURVEY LOG

Date 6/18/10
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory _____

Echo Sounder Reson 8101

Matrix/LNW File C09 / C10

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) 5

General Remarks _____

People 3

HORZ/VERT CHECKIN

Time RTK Tide Tide Board

S.O.S./Draft 4891.7/3.4

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
9:28	C09-052		17	2.1	START C09
9:31	C09-049		197	2.0	
9:33	C09-046		17	2.1	
9:35	C09-043		197		BOAT - SUNK
9:38	C09-040		17	2.0	
9:40	C09-037		197	2.0	
9:42	C09-034		17	2.0	
9:43	C09-055		197	2.0	
9:47	C09-058		17	2.0	
9:50	C09-061		197		
9:52	C09-064		17	1.2	
9:54	C09-067		197	2.1	
9:57	C09-070		17	2.0	
10:00	C09-073		197	1.9	MOVED BOAT - PORT SIDE
10:03	C09-076		17	1.9	BOAT MOVED - STBD
10:05	C09-079		197	1.8	
10:10	C10- SV Cast C10				4892.7
10:12	C10-031		2	1.9	START C10
10:14	C10-029		182	1.9	
10:17	C10-026		2	1.8	

Prepared by: _____

Page 2 of 8

GBA MULTIBEAM SURVEY LOG

Date 6/12/10
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory _____

Echo Sounder Reson 8101

Matrix/LNW File C10 / C11

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) 5-6

General Remarks _____

People 3

HORZ/VERT CHECKIN

Time RTK Tide Tide Board

S.O.S./Draft 4892.7 / 3.4

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
10:18	C10-023		182	1.7	C10
10:21	C10-020		2	1.9	
10:23	C10-017		182	1.9	
10:27	C10-034		2	1.9	
10:28	C10-037		182	2.1 1.9	
10:31	C10-040		2	1.9	
10:33	C10-043		182	1.9	
10:35	C10-046		2	1.9	
10:38	C10-049		182	1.9	
10:41	C10-052		2	1.9	
10:44	C10-055		182	1.9	GAP PICKUP
10:44	C10-058		2	1.9	
	SU CAST	C11		3	10:45 - 4899
10:53	C11-034		22	1.8	START C11 - LOST ^{No Sound} RTK
10:58	C11-034		22	2.0	RE-RUN
10:59	C11-031		202	2.0	
11:01	C11-028		22	2.0	TRUE END (N)
11:03	C11-025		202	1.9	"
11:06	C11-037		22	1.9	

Prepared by: _____

Page 3 of 8

GBA MULTIBEAM SURVEY LOG

Date 6/18/10
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory _____

Echo Sounder Reson 8101

Matrix/LNW File C11 / D01

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) 5

General Remarks _____

People 3

HORZ/VERT CHECKIN

Time RTK Tide Tide Board

S.O.S./Draft 4899 / 3.4

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
11:07	C11-040		202	1.9	C11
11:09	C11-043		22	1.9	
11:11	C11-047		202	1.9	
11:15	C11-050		22	1.8	
11:17	C11-054		202	1.8	
11:19	C11-057		22		
11:21	C11-060		202	2.0	PARTIAL (N)
11:23	C11-063		22		PARTIAL (N)
11:24	C11-066		202	1.4	"
11:27	C11-068		22		"
START D01 - SU CAST @ 11:30 - 4898					
11:34	D01-096		41	1.9	START D01
11:39	D01-099		221	1.7	
11:43	D01-099		41	1.9	
11:47	D01-090		221	1.9	
11:52	D01-088		41		TREE
11:56	D01-083		221	2.4	"
12:01	D01-080		41		
12:06	D01-077		221		OPEN PORT BEAMS - SCOPES
12:12	D01-102		41	2.0	

Prepared by: _____

Page 4 of 8

GBA MULTIBEAM SURVEY LOG

Date 6/18/10
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory _____

Echo Sounder Reson 8101

Matrix/LNW File D01/ C09

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) 5

General Remarks

People 3

HORZ/VERT CHECKIN

S.O.S./Draft 4895/3.4

Time RTK Tide Tide Board

13:21 4.20 4.19

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
12:16	D01-105		221	2.4	BRIDGE
12:20	D01-108		41	1.9	LOST RTK - MID
12:29	D01-108		41	2.0	RUN N - 1/2
12:29	D01-112		221	1.9	BRIDGE - TREE BN
12:35	D01-116		41	2.2/1.7	
12:39	D01-119		221	2.1	LOST RTK
12:42	D01-119		221	1.8 → 1.8	RE-RUN ENTIRE - ^{LOST RTK} BAD(PART)
12:44	D01-119		221	1.8 mtr	RE-RUN PARTIAL
12:48	D01-122		41	1.8	
12:51	D01-125		221	1.8	
12:56	D01-128		41°	1.0	
13:00	D01-131		221°	1.0	
13:05	D01-134		41°	1.1	
13:11	D01-074A		221°	1.1	
	BANKS @ C09				- SV CAST @ 13:25 - 4910
13:34	C09-030		17°		C09 - BANKS - FALSE ^{START} @ FIRST-BAD
13:36	C09-029		197	2.4	
13:39	C09-027		17		BOAT - DOCK
13:42	C09-026		197	2.0	OPEN - STBD BEAMS
13:45	C09-081		17		BOAT

Prepared by: _____

Page 5 of 8

GBA MULTIBEAM SURVEY LOG

Date 6/18/10
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory _____

Echo Sounder Reson 8101

Matrix/LNW File C09/10/11

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) 4

General Remarks _____

People 3

HORZ/VERT CHECKIN

Time RTK Tide Tide Board

S.O.S./Draft _____

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
13:49	C09-081		197	2.0	BOAT
13:51	C09-084		17	2.4	TOO MANY MORNINGS - CAN'T NAVIGATE
13:58	C09-077		197	2.2	//
14:00	C09-083		17		
14:00	C10-014		2	2.3	C10 - BANK ← PORT BEAMS
14:09	C10-017		182		
14:10	C10-020		2		END SHORT - PILING
14:13	C10-055		182	1.9	END SHORT - DEBRIS
14:16	C10-057		182		
14:17	C10-060		2	2.2	BOAT BOAT
14:20	C10-063		182	1.1	
14:23	C10-064		2		
14:26	C10-066		182		OPEN PORT BEAMS - CAN'T GET CLOSER
14:31	C11-024		22	2.3	
14:34	C11-023		202		
14:36	C11-022		22	1.9	
14:41	C11-071		202		
14:42	C11-072		22	2.1	

Prepared by: _____

Page 6 of 8

Page 7 of 9

GBA MULTIBEAM SURVEY LOG

Date 6/18/2010
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory Passaic 2010 JB

Echo Sounder Reson 8101

Matrix/LNW File _____

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) _____

General Remarks 16:39 Position check @ CP6

People _____

HORZ/VERT CHECKIN
Time RTK Tide Tide Board

S.O.S./Draft 11.2

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
15:11		Bar check @	001		
15:15	375	0375	300	1.0	
15:16		0375A	126		
15:18	370	0370	310	1.0	
15:19		0370A	130		
15:21	365	0365	310	0.8	
15:22		0365A	130		
15:24	360	360	305°	0.8	
15:25		360A	125°		
15:27	355	0355	305°	0.8	
15:29	350	350	291	0.8	
15:32	345	0345	279°		
15:35	340	340	283°	0.8	mooring line
15:36		340A			
15:38	335	335	299°	0.8	
		Long Lines			
15:39		000-1539			West shore CP → D1
15:47		000-1547			Center line D1 → CP
15:53		000-1554			EAST SHORE CP → D1
16:02		Bar check			

Prepared by: ECO

Page 8 of 8

GBA MULTIBEAM SURVEY LOG

Date 6/19/10
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory _____

Echo Sounder Reson 8101

Matrix/LNW File _____

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) 5

General Remarks _____

People 3

HORZ/VERT CHECKIN

S.O.S./Draft 4911 / 2.4

Time RTK Tide Tide Board

9:20 -1.16 -1.17

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
<u>8:18</u>		<u>Position check @</u>		<u>GPG Dock</u>	
<u>8:53</u>		<u>SV Cast DO1</u>			
<u>8:58</u>		<u>DO1-105</u>	<u>221</u>	<u>1.2</u>	
<u>9:02</u>		<u>DO1-108</u>	<u>410</u>	<u>1.3</u>	
<u>9:07</u>		<u>DO1-110</u>	<u>2210</u>	<u>1.5</u>	
<u>9:10</u>		<u>DO1-113</u>	<u>410</u>	<u>1.3</u>	
		<u>Switch DO2</u>			
<u>9:16</u>		<u>DO2-53</u>	<u>320</u>	<u>1.3</u>	
<u>9:18</u>		<u>DO2-56</u>	<u>2120</u>	<u>1.4</u>	
<u>9:20</u>		<u>DO2-59</u>	<u>320</u>	<u>1.4</u>	
<u>9:22</u>		<u>DO2-62</u>	<u>2120</u>	<u>1.4</u>	
		<u>DO2-65</u>	<u>320</u>	<u>1.4</u>	
<u>9:28</u>		<u>DO2-51</u>	<u>212</u>	<u>1.4</u>	
<u>9:30</u>		<u>DO2-48</u>	<u>32</u>		
<u>9:31</u>		<u>DO2-46</u>	<u>212</u>	<u>1.4</u>	
<u>9:34</u>		<u>DO2-46</u>	<u>32</u>		<u>RE-RUN GAPS</u>
<u>9:36</u>		<u>DO2-43</u>	<u>212</u>		
<u>9:39</u>		<u>DO2-40</u>	<u>32</u>	<u>1.4</u>	
<u>9:40</u>		<u>DO2-38</u>	<u>212</u>	<u>1.4</u>	

Prepared by: ECP

Page 1 of 8

GBA MULTIBEAM SURVEY LOG

Date 6/19/10
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory _____

Echo Sounder Reson 8101

Matrix/LNW File D03

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) 4.5

General Remarks _____

People 3

HORZ/VERT CHECKIN

S.O.S./Draft 4911 / 3.4

Time RTK Tide Tide Board

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
9:43	D02-34		212		
9:44	D02-32		32		
9:45	D02-29		212		
9:46	D02-29		32	1.2	GAP FILL
					START D03
9:47	D03-45		354		
9:53	D03-52		174	2.3	
9:58	D03-55		354	1.8	
10:03	D03-58		174	1.8	
10:04	D03-61		354	1.8	
10:08	D03-49		174	1.8	
10:10	D03-46		354	1.9	
10:15	D03-43		174	1.7	
10:18	D03-40		354	1.9	
10:21	D03-37		174	1.9	
10:24	D03-34		354	1.9	
10:27	D03-31		174	1.9	
10:31	D03-28		354	2.1, 1.9	
10:34	D03-25		174	1.9	
10:38	D03-22		354	2.1	FILL GAP

Prepared by: _____

Page 2 of P

GBA MULTIBEAM SURVEY LOG

Date 6/19/10
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory _____

Echo Sounder Reson 8101

Matrix/LNW File D04

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) 5

General Remarks _____

People 3

HORZ/VERT CHECKIN

Time RTK Tide Tide Board

S.O.S./Draft 4895.7/3.4

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
	<u>SU</u>	<u>CAST C</u>	<u>10:40</u>	<u>-</u>	<u>4895.7</u>
<u>10:46</u>	<u>D04-33</u>		<u>7°</u>	<u>2.1</u>	<u>START D04</u>
<u>10:49</u>	<u>D04-30</u>		<u>187°</u>		<u>RUN LONGER THAN REACH</u>
<u>10:51</u>	<u>D04-36</u>		<u>7</u>	<u>2.0</u>	<u>LT INTO BRIDGE</u>
<u>10:53</u>	<u>D04-42</u>		<u>187</u>	<u>1.8</u>	
<u>10:55</u>	<u>D04-45</u>		<u>7</u>	<u>2.0</u>	
<u>10:57</u>	<u>D04-48</u>		<u>187</u>	<u>2.0</u>	
<u>10:59</u>	<u>D04-51</u>		<u>7</u>		
<u>11:02</u>	<u>D04-51</u>		<u>187</u>	<u>1.1</u>	<u>CLEAN GAPS</u>
<u>11:03</u>	<u>D04-31</u>		<u>7</u>	<u>1.9</u>	
<u>11:05</u>	<u>D04-27</u>		<u>187</u>	<u>2.0</u>	
<u>11:08</u>	<u>D04-25</u>		<u>7</u>	<u>1.9</u>	
<u>11:10</u>	<u>D04-22</u>		<u>187</u>	<u>1.8</u>	
<u>11:13</u>	<u>D04-19</u>		<u>7</u>	<u>1.5</u>	
<u>11:15</u>	<u>D04-17</u>		<u>187</u>	<u>1.4</u>	
<u>11:17</u>	<u>D04-14</u>		<u>7</u>		
<u>11:21</u>	<u>D04-50</u>		<u>7</u>	<u>1.4</u>	
<u>11:22</u>	<u>D04-50</u>		<u>7°</u>	<u>1.4</u>	
<u>11:24</u>	<u>D04-55</u>		<u>187°</u>		
<u>11:25</u>	<u>D04-52</u>				

Prepared by: _____

Page 3 of 8

GBA MULTIBEAM SURVEY LOG

Date 6/19/10
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory 005

Echo Sounder Reson 8101

Matrix/LNW File _____

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) 5

General Remarks _____

People 2

HORZ/VERT CHECKIN

Time RTK Tide Tide Board

S.O.S./Draft 4896 / 3.4

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
		<u>Under Bridge only</u>			
<u>11:27</u>	<u>005-34</u>		<u>26</u>	<u>1.4</u>	
<u>11:28</u>	<u>005-31</u>		<u>206</u>	<u>1.4</u>	
<u>11:30</u>	<u>005-28</u>		<u>26°</u>	<u>1.4</u>	
<u>11:31</u>	<u>005-37</u>		<u>206°</u>	<u>1.4</u>	
<u>11:33</u>	<u>005-42</u>		<u>26°</u>		
		<u>Clean air Lines</u>			
<u>11:35</u>	<u>005-43</u>				
<u>11:36</u>	<u>005-43A</u>		<u>20°</u>	<u>1.4</u>	
<u>11:39</u>	<u>005-46</u>		<u>206°</u>	<u>1.9</u>	
<u>11:43</u>	<u>005-49</u>		<u>26</u>	<u>1.4</u>	
<u>11:45</u>	<u>005-52</u>		<u>206</u>	<u>1.9</u>	
<u>11:49</u>	<u>005-41</u>		<u>26</u>	<u>1.3</u>	
<u>11:52</u>	<u>005-38</u>		<u>206</u>	<u>2.0</u>	
<u>11:56</u>	<u>005-35</u>		<u>26</u>		
<u>11:58</u>	<u>005-32</u>		<u>206</u>		
<u>12:02</u>	<u>005-29</u>		<u>26</u>	<u>1.2</u>	
<u>12:04</u>	<u>005-26</u>		<u>206</u>	<u>2.0</u>	
<u>12:08</u>	<u>005-23</u>		<u>26</u>	<u>1.8</u>	
<u>12:11</u>	<u>005-19</u>		<u>206</u>		

Prepared by: _____

Page 4 of 8

GBA MULTIBEAM SURVEY LOG

Date 6/19/10
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory D05/D02/103

Echo Sounder Reson 8101

Matrix/LNW File _____

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) 4.5

General Remarks _____

People 3

HORZ/VERT CHECKIN

S.O.S./Draft 4897 / 3.4

Time	RTK Tide	Tide Board
12:56	1.90	1.95

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
12:15	D05-16		206°	1.2	
12:18	D05-13		206	2.3	
		SV CAST @		12:25	- D06 - 4897
12:56		RTK TIDE CHECK @ Port h 3			
12:42	D02-	SV CAST @		12:45	D02 - EDGES
12:48	D02-68				Lost RTK
12:50	D02-65		212°		East Shore 70° Port / Trees RTK
12:53	D02-69		32		70° STBD TREES
12:56	D02--43A		212°		West Shore STBD 70°
13:01	D02-42		32°	1.2	
13:03	D02-39		212°	1.2	
13:05	D02-39		32°		
13:09	D02-34A		212°	1.2	West East Edge
		D03	Edges		
13:14	D03-56		354		East Shore Trees
13:17	D03-60		174	1.1	Port Beam 70° Trees
13:23	D03-61		354		STBD 70° Trees
13:28	D03-73		174	1.1	
13:30	D03-73		354	2.0	
13:32	D03-74		174	1.1	

Prepared by: SCD

Page 5 of 8

GBA MULTIBEAM SURVEY LOG

Date 6/19/10
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory 1

Echo Sounder Reson 8101

Matrix/LNW File D03/

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) 4

General Remarks

People 3

HORZ/VERT CHECKIN

Time RTK Tide Tide Board

S.O.S./Draft 3.4

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
13:34	D03-24		174°	1.1	BANKS
13:41	D03-27		174	2.0	
13:44	D03-35		174	1.5	
13:47	D03-32		174		! VERY SHAL!
13:48	D03-20			1.2	USE 70° - WALL OPEN PORT BEAMS - WALL
	13:56	SV Cast @	005		
	Switch	D05 Edges			
14:00	D05-134		20°	Wall	West Shore Port 70°!
14:03	D05-12		206°		West shore wall STD 70°
14:08	D05-53		20	1.5	E. SHORE
14:10	D05-56		206°	1.6	
14:14	D05-57		20	1.6	HEAVY TREES - RTK SPIKE - SHOT
14:18	D06-68		36°	2.4	START D06 - W BANK
14:22	D06-69		216	1.1	
14:25	D06-71		36	1.8	
14:28	D06-25		216	1.9	WEST BANK
14:31	D06-22		36	1.8	
14:34	D06-20		216	1.7	STD BEAMS OPEN

Prepared by: _____

Page 6 of 8

GBA MULTIBEAM SURVEY LOG

Date 6/19/20
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory _____
Matrix/LNW File D07/D08/D09
Average Boat Speed (kts) 4
People 3
S.O.S./Draft 13.4

Echo Sounder Reson 8101
Positioning POSMV 320 w/ Leica RTK

General Remarks _____
HORZ/VERT CHECKIN _____
Time RTK Tide Tide Board

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
14:44	D07-10		280	2.0	FALSE START C1ST
14:47	D07-09		208°	2.1	WEST BANK - COST RTK
14:50	D07-09		208	2.1 1.9	TO MANY TREES - OPEN STBD BEAMS
14:55	D07-52		28	2.1	EAST BANK
14:58	D07-53		208	2.0	
15:03	D07-55		28	1.7	
15:10	D08-43		350	1.7	D08 - WEST BANK
15:12	D08-40		215°	1.7	
15:14	D08-38		35	1.7	
15:16	D08-35		215	1.7	
15:19	D08-69		35	1.7	EAST BANK
15:20	D08-72		215	1.7	
15:23	D08-74		35	1.7	
15:25	D08-76		215	1.3	
15:27	D08-76A		35	2.0	OPENED STBD BEAMS - TREES
15:30	D09-18		18	1.7	WEST BANK D09
15:31	D09-16		198	1.8	

Prepared by: _____

GBA MULTIBEAM SURVEY LOG

Date 6/19/10
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory _____

Echo Sounder Reson 8101

Matrix/LNW File D09 & D05SB

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) 4

General Remarks _____

People 3

HORZ/VERT CHECKIN

S.O.S./Draft 3.4

Time RTK Tide Tide Board

16:35 9.2' 9.1'

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
15:32	D09-13		180	1.7	
15:34	D09-10		198	1.6	
15:35	D09-10		18	1.6	GAP FILL
15:36	D09-48		198	1.1	EAST SHORE
15:38	D09-51		18	2.4	
15:40	D09-54		198	2.3	
15:41	D09-57		18	1.6	
15:52	BORNEOIC				BOR CHECK
15:55	CROSS 05		298	2.6	SB LINES (XS)
15:56	CROSS 05A		118		
15:58	CROSS 06		295	2.2	
15:59	CROSS 06A		115	1.2	
16:01	CROSS 07		297	2.1	
16:02	CROSS 07A		117	2.0	
16:03	CROSS 08				
	CROSS 08A				
16:04	EAST		X	1.3	LONGITS - EAST SHORE
16:07	Q			2.0	
16:10	WEST			2.0	

Prepared by: _____

Page 8 of 8

GBA MULTIBEAM SURVEY LOG

Date 6/20/10
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory Passaic 2010 SB

Echo Sounder Reson 8101

Matrix/LNW File _____

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) 5

General Remarks _____

People 3

HORZ/VERT CHECKIN
Time RTK Tide Tide Board

S.O.S./Draft 4796/12

7:36 0.40 0.35

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
		POSITION CHK @	7:15	✓	
		TIDE CHK @	7:18	→	D 0.14' X CHECK @ NOT 15'
					SINGLE BEAM XS
7:36		TIDE check @	NOT by		
		single beam check lines			
07:45		Bar check	5'		
07:55	0368	368	310°	1.3	one of 2009 13
07:58		369A	130°	1.3	
08:00		361	312	1.5	
08:01		382A	128°		
08:01		384	209°	1.6	
08:01		387A	119	1.6	
08:04		389	275	1.6	Bow on Bottom
08:04		389A	95°	1.6	
08:05		389B	75°	1.1	
08:07		394	263°	1.6	
08:08		394B	83°	1.1	
08:11		CROSS 01	268		
08:12		01A	88		

Prepared by: MLD

Page 1 of 10

GBA MULTIBEAM SURVEY LOG

Date 6/20/10
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory PASSAIC 2005B

Echo Sounder Reson 8101

Matrix/LNW File _____

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) 5

General Remarks _____

People 3

HORZ/VERT CHECKIN

Time RTK Tide Tide Board

S.O.S./Draft 4898 / 1.2

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
8:14		CROSS 02	269°	1.2	
8:15		02A	89°		
8:17		CROSS 03	W		
8:18		03A	E		
8:19		CROSS 04	303°	1.2	
8:20		04A	123		
		Long Lines	004-2	002	
8:22		000-0822		1.2	East Bank South Bound Trees!
8:27		000-0827		1.6	Center channel
8:34		000-0834		1.7	
8:45		CROSS 08	306°	2.1	SB XS
8:46		08A	126°	1.3	
8:48		CROSS 09	308	1.3	
8:49		09A	128	1.3	
8:51		CROSS 10	298°	2.1	
8:52		10A	118	2.0	
8:54		CROSS 11	298	1.5	
8:55		11A	118	1.5	
8:57		CROSS 12	299	2.1	

Prepared by: 9.00

Page 2 of 12

GBA MULTIBEAM SURVEY LOG

Date 6/20/10
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory PASSAIC2010SB

Echo Sounder Reson 8101

Matrix/LNW File _____

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) 5

General Remarks _____

People 3

HORZ/VERT CHECKIN _____

Time RTK Tide Tide Board _____

S.O.S./Draft 4898/1.2

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
8:58		CROSS 12A	119°	1.6	SB XS
8:59		CROSS 13	311	1.5	
9:00		13A	121	2.1	
9:02		CROSS 14	305	1.5	
9:02		14A	125	1.5	
9:04		CROSS 15	287	1.5	
9:05		15A	107	1.5	
9:07		CROSS 16	286	1.3	
9:08		16A	76	1.6	
9:09		CROSS 17	248	1.5	
9:10		17A	68	2.1	
9:12		CROSS 18	253	1.5	
9:13		18A	73	1.5	
9:15		CROSS 19	258	2.1	
9:15		19A	78	1.3	
9:17		CROSS 20	275	1.4	
9:18		20A	95	1.3	
9:20		CROSS 21	292	1.4	
9:20		21A	112	2.0	
9:22		CROSS 22	279	2.0	

Prepared by: BGU

Page 3 of 12

GBA MULTIBEAM SURVEY LOG

Date 6/20/2010
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory Passaic 2010MB

Echo Sounder Reson 8101

Matrix/LNW File DOB/DOF

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) 5

General Remarks SV Cast DOB

People 3

HORZ/VERT CHECKIN
Time RTK Tide Tide Board

S.O.S./Draft 4902/3.4

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
10:13	SV Cast @ DOB				Reson settings
10:20	DOB-27		36°	1.0	RNG 20m
10:22	DOB-31		216	1.1	Power - 4
10:25	DOB-29		36°	1.1	Autogain = 4
10:28	DOB-34		216°	1.9	Pulse width = 63ms
10:31	DOB-37		36	1.9	
10:34	DOB-40		216	1.9	
10:36	DOB-44		36	1.9	
10:39	DOB-47		216	1.8	
10:42	DOB-50		36	2.1	
10:45	DOB-53		216	2.0	
10:47	DOB-56		36	1.8	
10:50	DOB-59		216	2.0	
10:52	DOB-62		36	2.0	
10:55	DOB-64		216	1.9	
10:58	DOB-32		36	1.9	FULL GAP
11:01	DOF-49		28	1.9	
11:04	DOF-46		208	1.8	
11:09	DOF-42		28	1.8	
11:13	DOF-39		208	1.4	

Prepared by: ECO

Page 5 of 12

GBA MULTIBEAM SURVEY LOG

Date B/20/10
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory PASSAIC 2010 MB
Matrix/LNW File D07/D08

Echo Sounder Reson 8101
Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) 5

People 3

S.O.S./Draft 4902/3.4

General Remarks

HORZ/VERT CHECKIN

Time RTK Tide Tide Board

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
11:17	D07 - 30		28	2.0	D07 REACH
11:21	D07 - 33		208	1.4	
11:25	D07 - 29		28	2.0	
11:27	D07 - 25		208	1.6	
11:31	D07 - 22		28	1.9	
11:34	D07 - 19		208	1.7	
11:38	D07 - 17		28	1.7	
11:42	D07 - 15		208	1.8	
11:46	D07 - 42		28	1.3	FILL GAPS
11:47	D07 - 48		208	1.3	"
11:48	D07 - 14		28	2.0	
11:51	D07 - 17		208	1.3	FILL GAP
	SV CAST				
			D08 -	11:55	
12:02	D08 - 66		215	1.2	START D08 MIP
12:04	D08 - 62		35	2.0	
12:05	D08 - 59		215	1.2	
12:07	D08 - 55		35	2.0	
12:09	D08 - 52		215		
12:11	D08 - 49		35	1.2	
12:13	D08 - 46		215	2.4	

Prepared by: BGL

Page 6 of 12

GBA MULTIBEAM SURVEY LOG

Date 6/20/10
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory PASSAIC 2010 MB

Echo Sounder Reson 8101

Matrix/LNW File D08/D09/E01

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) 5

General Remarks

People 3

HORZ/VERT CHECKIN

S.O.S./Draft 4912/3.4

Time RTK Tide 12:34 -0.10

Tide Board - 0.15

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
12:15	D08 - 70		35	2.3	
12:18	D09 - 21		18	1.2	START D09 MID
12:20	D09 - 24		198	2.0	
12:21	D09 - 28		18	2.0	
12:22	D09 - 31		198	1.9	
12:23	D09 - 34		18	2.2	
12:24	D09 - 37		198	1.9	
12:26	D09 - 40		18	1.9	
12:27	D09 - 43		198	1.9	
	TIDE CHK @ 12:34 - NUTLEY ✓				START E01
12:40	E01 - 048		166	1.8	
12:44	E01 - 051		346	2.2	POWER LINES N MID REACH
12:48	E01 - 044		166	1.6	
12:52	E01 - 059		346	1.8	WEDGE - E SIDE
12:55	E01 - 062		166	1.9	
12:58	E01 - 065		346	2.0	
13:00	E01 - 068		166	2.2	
13:02	E01 - 044		346	2.0	
13:05	E01 - 041		166	1.2	
13:10	E01 - 038		346	2.1	

Prepared by: BAC

Page 7 of 12

GBA MULTIBEAM SURVEY LOG

Date 6/20/10
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory PASSAIC2010MB

Echo Sounder Reson 8101

Matrix/LNW File E01/

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) 5

General Remarks

People 3

HORZ/VERT CHECKIN

Time RTK Tide

Tide Board

S.O.S./Draft 4912/3.4

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
13:13	E01	- 034	160	2.0	
13:18	E01	- 031	346°	1.1	
13:20	E01	- 027	166	1.1	
13:23	E01	- 022	341		
13:25	E01	- 019	166	1.1	
		Switch	E02	middle	
13:29	E02	- 26	2°	1.1	
13:31	E02	- 23 (E029)	182°	1.1	
13:33	E02	- 24	2°	1.1	
13:34	E02	- 21	182°	1.1	
13:35	E02	- 32	2°	1.1	
13:37	E02	- 35	182°	1.1	
13:39	E02	- 040	2°	1.1	
13:40	E02	- 43	182°	1.1	
13:42	E02	- 44	2°	1.2	
13:44	E02	- 50	182°	1.2	
13:45	E02	- 53	2°	1.1	
13:47	E02	- 56	182°	1.2	
13:49	E02	- 59	2°	1.1	
13:50	E02	- 62	182°	1.1	

Prepared by: 1366

Page 8 of 12

GBA MULTIBEAM SURVEY LOG

Date 6/20/2010
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory Passaic 2010 MB

Echo Sounder Reson 8101

Matrix/LNW File 005

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) 5

General Remarks

People 3

HORZ/VERT CHECKIN

Time RTK Tide Tide Board

S.O.S./Draft 49085/3.4

South of

South of Bellville Bridge

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
1357		005-16	26°	1.1	open Port
1400		005-14	200	1.3	open STBD
1402		005-12	200°		Extends To DOY open STBD
1404		005-55	26°	1.3	
1410		005-59	800		
1413		005-61	26°		Dropped RTK
1414		005-61A	26°		
1416		005-65	200°		
1417		005-66			open STBD Beam
1426		S V Cast	EO1		
		Sw/ach To	EO1		
1431		S V CAST	EO1	2.2	EO1 - BANKS COASTAL
1435	EO1	-015	346	2.1	
1436	EO1	-012	166	2.1	LOST RTK @ END (TRK)
1439	EO1	-012	166	2.1	
1442	EO1	-029	346	2.0	
1444	EO1	-071	346	1.9	E. BANK
1448	EO1	-072	166	1.6	
1452	EO1	-073	346	2.0	

Prepared by: SCD

Page 9 of 12

GBA MULTIBEAM SURVEY LOG

Date 6/20/10
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory PASSAIC MB2010
Matrix/LNW File E01/E02/E03/F01

Echo Sounder Reson 8101
Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) 3

People 3

S.O.S./Draft 4908.5/3.4

General Remarks
HORZ/VERT CHECKIN
Time RTK Tide Tide Board

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
14:5	E01	074	166	2.0	
14:59	E02	060	1°	1.7	E02 - E BANK
15:01	E02	063	181	2.0	
15:03	E02	067	1	1.3	
15:04	E02	078	181	1.7	
15:05	E02	019	181	1.7	W. BANK
15:08	E02	016	1°	1.7	
15:12	E03	94	24°	1.9	E03 - BANK (W)
15:13	E03	21	204	2.0	
15:15	E03	18	24	1.7	
15:16	E03	15	204	2.0	
15:19	E03	58	24	1.7	
15:20	E03	61	204	2.3	
15:22	E03	64	24	1.7	
15:24	E03	67	204	1.7	
15:25	E03	78	24	1.7	
15:28	F01	024	6°	1.7	F01
15:31	F01	021	186	1.3	
15:35	F01	020	6	1.8	OPENED PORT BEAMS (JULIUS)
15:37	F01	017	186	1.3	

Prepared by: BLC

Page 10 of 12

GBA MULTIBEAM SURVEY LOG

Date 6/20/10
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory PASSAIC2010MB

Echo Sounder Reson 8101

Matrix/LNW File F01/E03

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) 5

General Remarks

People 3

HORZ/VERT CHECKIN

S.O.S./Draft 4902.5/3.4

Time RTK Tide Tide Board

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
15:40	F01	- 014	6	2.3	
15:41	F01	- 011	186	1.3	
15:43	F01	- 54	186	2.1	E. BANK
15:46	F01	- 57	6	2.1	
15:49	F01	- 60	186	2.0	
15:53	F01	- 63	6	2.2	
15:56	F01	- 050	186	2.0	MID
15:59	F01	- 046	6	2.0	
16:02	F01	- 041	186	1.5	
16:04	F01	- 037	6	1.3	
16:08	F01	- 031	186	1.7	
16:11	F01	- 027	6	1.5	
16:16	E03	- 26	204	1.3	E03 - MID
16:18	E03	- 30	24	1.8	
16:19	E03	- 34	204		
16:20	E03	- 38	24	1.3	
16:21	E03	- 43	204		
16:22	E03	- 47	24	1.8	
16:23	E03	- 51	204	1.4	
16:24	E03	- 54	24	1.8	

Prepared by: BGL

Page 11 of 12

GBA MULTIBEAM SURVEY LOG

Date 6/20/10
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory PASSAIC2010MB

Echo Sounder Reson 8101

Matrix/LNW File F02

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) 5

General Remarks

People 3

HORZ/VERT CHECKIN

S.O.S./Draft 13.4

Time	RTK Tide	Tide Board
<u>16:59</u>	<u>4.70</u>	<u>4.60</u>

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
		<u>Switch</u>	<u>Reach</u>	<u>F02</u>	
<u>16:27</u>		<u>F02-53</u>	<u>358</u>	<u>1.4</u>	
<u>16:30</u>		<u>F02-56</u>	<u>178</u>	<u>1.6</u>	
<u>16:31</u>		<u>F02-57</u>	<u>358</u>	<u>1.4</u>	
<u>16:34</u>		<u>F02-62</u>	<u>178</u>	<u>1.4</u>	
<u>16:35</u>		<u>F02-63</u>	<u>358</u>	<u>1.4</u>	
<u>16:37</u>		<u>F02-26</u>	<u>178</u>	<u>1.4</u>	
<u>16:39</u>		<u>F02-21</u>	<u>358</u>	<u>1.5</u>	
<u>16:40</u>		<u>F02-18</u>	<u>178</u>	<u>1.3</u>	
<u>16:42</u>		<u>F02-15</u>	<u>358</u>	<u>1.5</u>	
<u>16:43</u>		<u>F02-29</u>	<u>178</u>	<u>1.1</u>	
<u>16:45</u>		<u>F02-31</u>	<u>358</u>	<u>1.3</u>	
<u>16:47</u>		<u>F02-35</u>	<u>178</u>	<u>1.0</u>	
<u>16:48</u>		<u>F02-39</u>	<u>358</u>	<u>1.3</u>	
<u>16:50</u>		<u>F02-43</u>	<u>178</u>	<u>1.3</u>	
<u>16:51</u>		<u>F02-47</u>	<u>358</u>	<u>1.4</u>	
<u>16:53</u>		<u>F02-51</u>	<u>178</u>	<u>1.4</u>	
<u>16:55</u>		<u>SV Cast @ F02</u>			
<u>16:57</u>		<u>RTK TIDE check @ Notley</u>			
<u>16:12</u>		<u>Position check @ cfo</u>			

Prepared by: BGL

Page 12 of 12

GBA MULTIBEAM SURVEY LOG

Date 6/21/10
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory Passaic 2010SR

Echo Sounder Reson 8101

Matrix/LNW File _____

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) _____

General Remarks _____

People _____

HORZ/VERT CHECKIN

S.O.S./Draft 9903/1.2

Time RTK Tide Tide Board

8:10 1.10 1.08

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
<u>8:10</u>		<u>Tide & Position checks @ CP6</u>			
<u>8:30</u>		<u>Bar check</u>	<u>5', 12', 10', 5'</u>		
<u>8:35</u>		<u>CROSS 22</u>	<u>272</u>	<u>1.7</u>	
<u>8:36</u>		<u>22A</u>	<u>79°</u>	<u>1.5</u>	
<u>8:38</u>		<u>CROSS 23</u>	<u>274</u>	<u>1.3</u>	
<u>8:40</u>		<u>23A</u>	<u>94</u>	<u>1.3</u>	<u>CROSS 21 accidentally logged for 23</u>
<u>8:42</u>		<u>CROSS 24A</u>	<u>273</u>	<u>1.3</u>	
<u>8:42</u>		<u>24B</u>	<u>93</u>	<u>1.3</u>	
<u>8:45</u>		<u>CROSS 25</u>	<u>275</u>	<u>1.4</u>	
<u>8:46</u>		<u>25A</u>	<u>75</u>	<u>1.3</u>	
<u>8:48</u>		<u>CROSS 26</u>	<u>291</u>	<u>1.3</u>	
<u>8:48</u>		<u>CROSS 26A</u>	<u>101</u>	<u>1.3</u>	
<u>8:51</u>		<u>CROSS 27</u>	<u>103</u>	<u>1.3</u>	
<u>8:52</u>		<u>27A</u>	<u>283</u>	<u>1.3</u>	
<u>8:54</u>		<u>CROSS 28</u>	<u>286</u>		
<u>8:54</u>		<u>28A</u>	<u>286</u>	<u>1.3</u>	
<u>8:55</u>		<u>28B</u>	<u>108°</u>	<u>1.3</u>	
<u>8:57</u>		<u>CROSS 29</u>	<u>289</u>	<u>1.3</u>	
<u>8:58</u>		<u>29A</u>	<u>109</u>	<u>1.3</u>	

Prepared by: EC D

Page 1 of 14

GBA MULTIBEAM SURVEY LOG

Date 6/24/10
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory Passaic 2010 SD

Echo Sounder Reson 8101

Matrix/LNW File _____

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) _____

General Remarks _____

People 3

HORZ/VERT CHECKIN
Time RTK Tide Tide Board

S.O.S./Draft 4903/1.2

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
8:59		CROSS 30	310	1.3	
9:00		30A	130	1.3	
9:02		CROSS 31	335	1.3	
9:03		CROSS 31A	155	1.3	
9:05		CROSS 32	341	1.3	
9:06		32A	161	1.3	
9:07		CROSS 33	343	1.3	
9:08		33A	163	1.4	
9:10		CROSS 34	344	1.3	
9:11		34A	164	1.4	
9:13		CROSS 35	338	1.3	
9:14		35A	158	1.3	
9:15		CROSS 36	335	1.3	
9:16		36A	155	1.3	
9:18		CROSS 38	318	1.4	
9:19		38A	138	1.1	
9:20		CROSS 39	312	1.4	
9:21		39A	132	1.1	

Prepared by: ECO

Page 2 of 14

GBA MULTIBEAM SURVEY LOG

Date 6/21/10
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory Passaic 2010 R

Echo Sounder Reson 8101

Matrix/LNW File F01/E01

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) 5

General Remarks

People 3

HORZ/VERT CHECKIN

Time RTK Tide Tide Board

S.O.S./Draft 4910/3.4

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
10:08	F01	- 032	6°	1.7	
10:11	F01	- 029	186°	1.9	
10:15	F01	- 027	6	1.9	
10:18	F01	- 021	186	2.1	
10:21	F01	- 027	6	1.9	FILL GAPS
10:24	F01	- 035	186	1.9	
10:27	F01	- 038	6	1.9	
10:30	F01	- 048	186	1.9	
10:33	F01	- 045	6	2.1/1.9	
10:36	F01	- 048	186	2.1	
10:39	F01	- 050	6	2.1	
10:42	F01	- 053	186	2.0	
10:45	F01	- 055	6	2.0	7m
10:49	F01	- 056	186	2.0	FILL GAPS
10:51	F01	- 051	6	1.9	//
10:53	F01	- 032	186	2.3	α
10:57	F01	- 055	166	1.9	FILL GAPS
10:58	F01	- 028	346	1.9	u

Prepared by: BLC

Page 4 of 14

GBA MULTIBEAM SURVEY LOG

Date 6/21/10
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory PASSAIC 2010 MB

Echo Sounder Reson 8101

Matrix/LNW File F03/F02/F04

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) 5

General Remarks HORZ/VERT CHECKIN

People 3

Time RTK Tide Tide Board

S.O.S./Draft 4914/3.4

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
11:03	F02 - 046		358		UNDER BRIDGE
11:05	F02 - 049		178	2.0	
11:06	F02 - 48		358	1.7	
11:10	F02 - 45		178	1.8	
11:12	F02 - 34		358	2.0	
11:14	F02 - 28		178	1.8	
11:16	F02 - 22		358	1.8	
11:17	F02 - 20		178	2.5	
11:19	F03 - 27		12	1.6	START F03 - mb
11:23	F03 - 25		192	1.7	
11:26	F03 - 22		12	1.7	
11:30	F03 - 34		192	1.9	
11:34	F03 - 37		12	1.9	
11:37	F03 - 40		192	2.0	
11:40	F03 - 43		12	1.9	
11:44	F03 - 46		192	2.0	
11:53	F03 - 40		12	1.2	FILL GAPS
11:56	F04 - 035		35	2.0	
11:57	F04 - 037		215		HYPACK CRASH
12:02	F04 - 037		35		RE-RUN

Prepared by: BLC

Page 5 of 14

GBA MULTIBEAM SURVEY LOG

Date 6/21/10
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory PASSAIC 2010 MB

Echo Sounder Reson 8101

Matrix/LNW File F04/G01

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) 5

General Remarks

People 3

HORZ/VERT CHECKIN

S.O.S./Draft 49/4/3.4

Time RTK Tide

Tide Board

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
12:03	F04	- 040	215	2.4	
12:04	F04	- 041	35	2.4	
12:06	F04	- 034	215	1.2	
12:08	F04	- 032	35	2.4	
12:10	F04	- 030	215	2.0	
12:11	F04	- 028	35	2.3	
12:13	F04	- 025	215	1.2	
12:15	F04	- 022	35	2.0	
12:16	F04	- 019	215		
12:17	F04	- 016	35	2.0	
12:19	F04	- 034	215	1.9	
12:20	F04	- 013	35	1.9	
	SV	CAST C G01	- 12:20 ~	49/7.3	
12:28	G01	- 049	2370	2.1	START G01 - MID
12:29	G01	- 047	57	1.8	
12:31	G01	- 046	237	2.1/1.9	
12:32	G01	- 043	57	1.9	
12:33	G01	- 041	237	1.8	
12:34	G01	- 038	57	1.6	
12:35	G01	- 036	237	1.8	

Prepared by: BFC

Page 6 of 14

GBA MULTIBEAM SURVEY LOG

Date 6/21/10
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory PASSAIC 2010M B

Echo Sounder Reson 8101

Matrix/LNW File G01/G02

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) 5

General Remarks

People 3

HORZ/VERT CHECKIN

S.O.S./Draft 4917/3.4

Time RTK Tide Tide Board

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
12:37	G01	033	57°	1.8	
12:38	G01	031	237	2.0	
12:39	G01	028	57	1.6	
12:40	G01	026	237	1.9	
12:43	G02	050	74	1.7	HDOP SPIKE
12:48	G02	048	254	2.9	HYPACK CRASH
12:54	G02	048	74	2.0	RE-RUN
12:58	G02	042	254	2.0	
13:03	G02	041	74	2.1	
13:06	G02	039	254	2.0	
13:11	G02	037	74	2.2	
13:17	G02	036	254	2.3	
13:16	G02	031	74	1.1	
13:18	G02	039	254	1.1	
13:21	G02	032	74	1.1	
13:24	G02	0394	254	1.1	Gap Fills
13:27	G02	051	74°	1.1	
13:30	G02	055	254°	1.1	

Prepared by: BGL

Page 7 of 14

GBA MULTIBEAM SURVEY LOG

Date 6/21/10
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory Passaic 2010 MB
Matrix/LNW File 602

Echo Sounder Reson 8101
Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) _____

General Remarks _____
HORZ/VERT CHECKIN _____
Time RTK Tide Tide Board

People _____

S.O.S./Draft 4910 / 34

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
13:34		602-057	74°	1.1	
13:36		602-060	271°	1.1	
13:40		602-053	74°	1.2	Gap Fills
		SWITCH	603		South of Bridge
13:43		603-042	66°	1.2	upto Bridge only
13:45		603-039	246°	1.5	
13:46		603-036	66°	1.2	
13:48		603-034	246	1.5	
13:49		603-031	66°	1.2	
13:50		603-043	246	1.3	
13:52		603-047	66°	1.2	
13:53		603-050	246°	1.2	
13:55		603-053	66°	1.1	
13:57		603-056	246	1.3	
13:58		603-060	66	1.5	South of Bridge
					North of Bridge
14:01		603-46	246	1.1	
14:03		603-44	246	1.1	
14:04		603-40	246	1.1	
14:06		603-38	246	1.1	

Prepared by: EW

Page 2 of 14

GBA MULTIBEAM SURVEY LOG

Date 6/21/2010
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory Passaic 2010 MB

Echo Sounder Reson 8101

Matrix/LNW File 0603

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) _____

General Remarks _____

People 3

HORZ/VERT CHECKIN
Time RTK Tide Tide Board @ NUTLEY

S.O.S./Draft 4910/3.4

14:23 1.10 1.16

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
14:08	603-	34	246	1.1	
14:11	603-	50A	246	1.2	
14:12	603-	55	246	1.3	North Bridge ↑
	603-	59	246	1.8	
14:23	TIDE check @ NUTLEY				
14:28	SV cast @ 63				
	Under Bridges				
					↓
14:30	603-	38	246		
14:34	603	42	66		
14:35	603	40	246		
14:36	603	44	66°		
14:38	603	56	246		
14:39	603	57	66°		
14:42	604-	45	35		
14:43	604-	49	215		
14:45	604-	53	35°		
14:46	604-	57	215°		
14:48	604	61	35		
14:49	604	65	215°		
14:56	604	69	3		

Under Bridges

Under Bridges

Prepared by: ECO

GBA MULTIBEAM SURVEY LOG

Date 6/21/2010
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory PASSAIC2010MB
Matrix/LNW File F01/F03/F04

Echo Sounder Reson 8101

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) 4

People 3

S.O.S./Draft 49/8.6/3.4

General Remarks
HORZ/VERT CHECKIN
Time RTK Tide Tide Board

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
15:09	F01 -	056	6	1.7	
15:11	F01 -	060	186	1.7	
15:14	F01 -	064	6	1.7	OPENED STD BEAMS - WALL/ROCK
15:18	F01 -	070	186	2.0	
15:21	F01 -	019	6	1.9	
15:24	F01 -	014	186	2.4	
15:30	F03 -	48	12	2.0/1.6	F03 - BANKS
15:34	F03 -	051	192	2.2	
15:38	F03 -	55	12	2.2	HYPACK CRASH
15:43	F03 -	55	192	1.4	RE-RUN
15:47	F03 -	58	12	2.0	
15:50	F03 -	60	192	2.0	N-END
15:54	F03 -	23	12	1.3/2.0	
15:58	F03 -	70	192	2.1	HEAVY TREES - CANT GET CLOSER
16:02	F03 -	16	12	2.1	
16:07	F04 -	010	35	2.1	F04 - BANKS
16:09	F04 -	008	215	1.3	
16:11	F04 -	041	35	1.8	

Prepared by: BGL

Page 10 of 14

GBA MULTIBEAM SURVEY LOG

Date 6/21/10
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory PASSAIC 2010 MB

Echo Sounder Reson 8101

Matrix/LNW File F04/G01/G02

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) 4

General Remarks HORZ/VERT CHECKIN

People 3

Time RTK Tide Tide Board

S.O.S./Draft 4918.6/3.4

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
16:13	F04	- 044	215	1.8	
16:15	F04	- 048	35	1.6	
16:17	F04	- 050	215	1.8	
16:19	F04	- 054	35	1.7	
16:20	F04	- 052	215	2.5	
16:23	G01	- 051	57	1.4	
16:24	G01	- 054	237	1.6	
16:25	G01	- 058	57	1.7	
16:26	G01	- 062	237	2.5	
16:27	G01	- 024	57	1.4	
16:28	G01	- 021	237	2.6	
16:31	G02	- 026	74	1.4	
16:36	G02	- 027	254	2.6	TREES - HYPACK CRASH
16:41	G02	- 024	74	1.5	
16:47	G02	- 026	254	1.6	
16:49	G02	- 065	254	1.7	
16:53	G02	- 059	74	2.2	
16:57	G02	- 067	254	1.4	TREES - E. BANK

Prepared by: BGC

Page 11 of 14

GBA MULTIBEAM SURVEY LOG

Date 6/21/10
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory _____

Echo Sounder Reson 8101

Matrix/LNW File 402/403

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) 4

General Remarks _____

People 3

HORZ/VERT CHECKIN _____

Time RTK Tide Tide Board

S.O.S./Draft 498.6/3.4

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
17:02	402	-064	74	2.1	
17:04	402	-068	254	2.2	
17:07	402	-057	74	2.2	
17:12	403	-63	24	2.0	
17:13	403	-67	246	1.4	TREES
17:14	403	-70	24	2.3	"
17:16	403	-73	246	1.2	
17:17	403	-26	24	2.0	
17:19	403	-23	246		
17:22	403	-32	246	1.4	
17:23		-28	240	1.2	
17:23		-26	2460	1.2	
17:25		-19	24	1.2	
17:26		-22	246	1.2	
17:27		-20	240		
17:27		-20	246		
17:28	403	18	24	1.2	
	403	57	246		
	403	62	24	1.3	open STD Beams

Prepared by: BGL

GBA MULTIBEAM SURVEY LOG

Date 6/21/2010
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory Passaic 2010 MB

Echo Sounder Reson 8101

Matrix/LNW File G04

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) _____

General Remarks _____

People 3

HORZ/VERT CHECKIN

Time RTK Tide Tide Board

S.O.S./Draft 49'7" / 3.4

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
17:33	G04-	33	35	1.2	
17:35	G04-	30	215	1.2	
17:36	G04-	29	35	1.2	
17:37	G04-	31	215	1.3	
17:40	G04-	26	35°	1.3	
17:41	G04-	23	215	1.3	
17:43	G04-	52	35	1.7	DO NOT USE
17:44	G04-	52A	35°	1.3	
17:46	G04-	55	215°	1.6	
17:48	G04-	58	35°	1.6	
17:50	G04-	61	215°	1.6	
	G04-	64	35°	1.0	open STBD beams
17:53	G04	72	215		open Port beams
17:54	G04	75	35		open STBD beams
17:57	G04	51	215	1.6	
17:59	G04	47	35	1.0	
	G04	49	215		
18:03	G04	37	35	1.0	
18:05	G04	40	215	1.6	

Prepared by: EC

Page 13 of 14

GBA MULTIBEAM SURVEY LOG

Date 6/21/10
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory _____

Echo Sounder Reson 8101

Matrix/LNW File _____

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) _____

General Remarks

People _____

HORZ/VERT CHECKIN

Time RTK Tide Tide Board

S.O.S./Draft _____

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
18:09	604-45A		215	1.0	
18:10	604 42		215	1.0	
18:12	604-39		215	1.0	
18:13	604-36		215	1.0	
18:14	604-33A		215	1.0	
18:16	604-30		215	1.0	
18:18	604-62		215	1.2	
18:19	604 67		215	1.2	
18:21	604 69A		215	1.1	
18:22	604 60		215	1.3	
18:24	604-56		215	1.1	
18:25	604 61C		215	1.0	
18:26	SV cast @ 604				

Prepared by: ELW

Page 14 of 14

GBA MULTIBEAM SURVEY LOG

Date 6/22/2010
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory Passaic 2010SD

Echo Sounder Reson 8101

Matrix/LNW File ULPR 0105 Lines

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) _____

General Remarks _____

People _____

HORZ/VERT CHECKIN
Time RTK Tide Tide Board

S.O.S./Draft 4903/1.2

7:35 2.60 2.59

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
	<u>07:45</u>	<u>Bar check</u>		<u>5', 15', 10' 5'</u>	
<u>7:49</u>		<u>CROSS 40</u>	<u>288</u>	<u>1.3</u>	
<u>7:50</u>		<u>404</u>	<u>108</u>	<u>1.5</u>	<u>18 DOPT unde Trees</u>
<u>7:52</u>		<u>CROSS 41</u>	<u>284</u>	<u>1.6</u>	
<u>7:53</u>		<u>41A</u>	<u>104</u>	<u>1.6</u>	
<u>7:55</u>		<u>CROSS 42</u>	<u>289</u>	<u>1.6</u>	
<u>7:55</u>		<u>42A</u>	<u>104</u>	<u>1.6</u>	
<u>7:58</u>		<u>CROSS 43</u>	<u>292</u>	<u>1.7</u>	
<u>7:58</u>		<u>43A</u>	<u>102</u>	<u>1.7</u>	
<u>8:00</u>		<u>CROSS 44</u>	<u>293</u>	<u>1.1</u>	
<u>8:01</u>		<u>44A</u>	<u>103</u>	<u>1.7</u>	
<u>8:03</u>		<u>CROSS 45</u>	<u>281</u>	<u>1.7</u>	
<u>8:04</u>		<u>45A</u>	<u>101</u>	<u>1.7</u>	
<u>8:05</u>		<u>CROSS 46</u>	<u>273</u>	<u>1.7</u>	
<u>8:06</u>		<u>46A</u>	<u>93</u>	<u>1.7</u>	
<u>8:07</u>		<u>CROSS 47</u>	<u>260</u>	<u>1.8</u>	
<u>8:08</u>		<u>47A</u>	<u>80</u>	<u>1.7</u>	
<u>8:10</u>		<u>CROSS 48</u>	<u>242</u>	<u>1.7</u>	
<u>8:10</u>		<u>48A</u>	<u>62</u>	<u>1.7</u>	

Prepared by: ELC

Page 1 of 14

GBA MULTIBEAM SURVEY LOG

Date 6/22/2010
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory Passaic SB
Matrix/LNW File _____

Echo Sounder Reson 8101
Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) 5

People 3

S.O.S./Draft 4903/1.2

General Remarks

HORZ/VERT CHECKIN

Time RTK Tide Tide Board

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
7:12		CROSS-49	258	1.7	High PDOPS under bridge
7:13		49A	98	1.7	
7:15		CROSS 50	255	1.2	
7:15		50A	75A	1.6	
7:17		CROSS 51	239	1.6	
7:18		51A	59	1.6	
7:19		CROSS 52	266	1.0	
7:20		52A	86	1.6	
7:21		CROSS 53	300	1.2	
7:28		53A	120	1.5	
7:24		CROSS 54	289	1.5	
7:24		54A	119	1.5	
		Long Lines	Bridge to bridge		
7:26		000-0825	=	1.7	East shore (away from trees)
7:36		000-0836	=	1.5	CENTER LINE
7:49		000-0849	=	2.1	WEST SHORE
		PAR CHECK @ 9:05	→ 5, 10, 15		
		SU CAST @ 9:08	HDI		

Prepared by: ECD

Page 2 of 14

GBA MULTIBEAM SURVEY LOG

Date 6/22/10
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory PASSAIC 2010 MB

Echo Sounder Reson 8101

Matrix/LNW File H01/H02

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) 5

General Remarks

People 3

HORZ/VERT CHECKIN

Time RTK Tide

Tide Board

S.O.S./Draft 49(8.8) / 3.4

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
9:11	H01-	54	13°	1.4	START H01 - MID
9:17	H01-	50	193°	1.4	
9:21	H01-	57	13		
9:27	H01-	47	193		
9:31	H01-	44	13	2.2	
9:37	H01-	41	193		
9:41	H01-	38	13	1.2	
9:46	H01-	35	193	1.9	
9:50	H01-	32	13	2.0/1.8	
9:57	H02-	23	2°	1.9	START H02 - MID
9:59	H02-	20	182°	1.9	
10:01	H02-	26	2	1.9	
10:04	H02-	29	182	1.2	
10:06	H02-	32	2	2.1/1.9	
10:09	H02-	35	182	1.9	
10:11	H02-	39	2	1.9	
10:14	H02-	42	182	2.1	TREE - SHORT HDOP SPIKE
10:	H02-	30	2	1.9	FILL GAP

Prepared by: BGC

Page 3 of 14

GBA MULTIBEAM SURVEY LOG

Date 6/22/10
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory PASSAIC 2010 MB

Echo Sounder Reson 8101

Matrix/LNW File H03/H04

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) 5

General Remarks

People 3

HORZ/VERT CHECKIN

S.O.S./Draft 4918.3/3.4

Time RTK Tide Tide Board

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
10:18	H03	-22	332	1.9	
10:21	H03	-19	152	1.9	
10:23	H03	-16	332	2.1	
10:25	H03	-14	332	2.1	
10:26	H03	-13	152	2.2	FILL GAP
10:27	H03	-25	332	1.9	
10:30	H03	-28	152	1.6	FLOATING HDOP-TREES
10:32	H03	-31	332	1.6	"
10:34	H03	-34	152	1.6/2.1	"
10:36	H03	-37	332	2.1	"
10:38	H03	-41	152	1.5	"
10:40	H03	-44	332		"
10:43	H04	-30	344	2.0	
10:45	H04	-32	164	2.3	
10:47	H04	-36	344		
10:49	H04	-38	164		
10:51	H04	-41	344		NEAR TREES - HDOP ↓
10:53	H04	-44	344		
10:55	H04	-47	344		
10:58	H04	-23	164	1.6	

Prepared by: BGC

Page 4 of 14

GBA MULTIBEAM SURVEY LOG

Date 6/22/10
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory PASSAIC 2010 MB
Matrix/LNW File H04/H05/H06

Echo Sounder Reson 8101
Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) 5

People 3

S.O.S./Draft 4918.3/3.4

General Remarks

HORZ/VERT CHECKIN

Time RTK Tide Tide Board

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
11:00	H04 - 20		344	1.6	
11:02	H04 - 16		164		TREES
		SU CAST	C 11:05		4921.6
11:09	H05 - 33		338		START H05 - MID
11:11	H05 - 36		158	1.6	
11:13	H05 - 38		338	2.0/1.7	
11:16	H05 - 42		158	1.6	
11:17	H05 - 44		338		
11:19	H05 - 47		158	1.6/1.9	TREES
11:20	H05 - 30		158	1.9	
11:22	H05 - 27		338		
11:25	H05 - 24		158	1.7	
11:27	H05 - 20		338		TREE - HDOP ↑↓
11:29	H05 - 18		158	1.9	
11:32	H05 - 15		338		LOST RTK
11:33	H05 - 43		158	2.8	
11:34	H05 - 43		338	1.9	
	H06				H06 - MID

Prepared by: BGL

Page 5 of 14

GBA MULTIBEAM SURVEY LOG

Date 6/22/2010
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory PASSAIC 2010 MB
Matrix/LNW File 4921.6 / 2.4
Average Boat Speed (kts) 5
People 3
S.O.S./Draft H06/1107

Echo Sounder Reson 8101

Positioning POSMV 320 w/ Leica RTK

General Remarks
HORZ/VERT CHECKIN
Time RTK Tide Tide Board

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
11:38	H06	43	5°	1.3	
11:40	H06	46	185°	2.7	TREES
11:41	H06	40	5°		
11:42	H06	38	185		
11:43	H06	35	5	1.8	
11:44	H06	32	185	1.8	
11:45	H06	29	5		
11:46	H06	26	185	1.8	
11:48	H06	23	5	2.6	
11:49	H06	20	185	1.8	
11:51	H06	17	5	2.6	TREES
11:52	H06	14	185	1.8	
11:54	H07	39	28	2.5	NO MATRIX
11:56	H07	39	28	1.2	RE-RUN
11:58	H07	36	208	2.4	BRIDGE & TREES - HDOP 7L
12:00	H07	42	28	2.4	"
12:01	H07	33	208	1.5/2.4	
12:03	H07	30	28	2.4	
12:05	H07	27	208	1.5	

Prepared by: BGC

Page 6 of 14

GBA MULTIBEAM SURVEY LOG

Date 6/22/2010
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory PASSAIC2010MB

Echo Sounder Reson 8101

Matrix/LNW File H07

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) 5

General Remarks

People 3

HORZ/VERT CHECKIN

S.O.S./Draft 492.6/3.4

Time RTK Tide Tide Board

12:34 -1.39 -1.46

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
12:06	H07-24		28	2.0	
12:08	H07-21		208	1.5	
12:09	H07-18		28	2.3	
12:11	H07-15		208	1.9	TREES - HDOP ↑
12:12	H07-12		28	2.3	" "
12:17	H07-40		28	2.2	UNDER BRIDGE - LAST PTK
12:18	H07-40		208	2.2	
12:20	H07-37		28	2.2	
12:21	H07-34		208		
12:34		PTK	TIDE	check	@ CPG
12:38	H07-34		208		
12:40	H07-31		28		
12:42	H07-30A		208		Under Bridge
12:45	H07-27A		208	1.2	High Dops
12:47	H07-30B		28°	1.	
	SV CAST	③ H07			13:09 - 4933.4

Prepared by: BGL

Page 7 of 14

GBA MULTIBEAM SURVEY LOG

Date 06/22/2010
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory PASSAIC2010 MB

Echo Sounder Reson 8101

Matrix/LNW File H07/H08

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) 5

General Remarks HORZ/VERT CHECKIN

People 3

Time RTK Tide Tide Board

S.O.S./Draft 49.33.4
49.6/3.4

18.4

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
13:14		H07-30C	208	1.7	
13:15		H07-30D			
13:16		H07-27B	208	1.2	
13:18		H07-27C	208	1.2	
13:20		H07-29	208°	1.2	
13:21		H07-21	28°	1.2	
13:23		H07-18A	208	1.1	
13:24		H07-15A	28°		
13:25		H07-12A	208		
13:26		H07-07A	28°	1.1	
13:28		H07-33A	208	1.2	
13:29		H07-36A	28°	2.7	
		Su2/10A	H08		
13:30		H08-45	90	1.5	
13:34		H08-42	189°	2.1	
13:38		H08-39	9	1.5	
13:41		H08-37	189	2.2	
13:46		H08-34	9	2.3	
13:49		H08-31	189	1.1	
13:52		H08-28	9	1.3	

Prepared by: ECO

Page 8 of 14

GBA MULTIBEAM SURVEY LOG

Date 6/22/10
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory PASSAIC 2010 MBS

Echo Sounder Reson 8101

Matrix/LNW File H08/

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) 5

General Remarks HORZ/VERT CHECKIN

People 3

Time RTK Tide Tide Board

S.O.S./Draft 49 3.4 / 3.4

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
13:56		H08-25	189	2.3	
14:00		H08-22	9	1.8	
14:05		H08-19	189		
14:08		H08-16	9		
14:12		H08-48	189		LOST RTK
14:13		H08-48A	189	2.3	RE RUN LOST RTK
14:17		H08-44	9	2.0	LOST RTK
14:18		H08-44A	9	1.8	RE RUN - LOST RTK
14:19		H08-44B	9	1.7	" "
14:19		H08-44	9	1.7	FILL GAPS
14:23		H08-47	189	2.0	HDOP SPIKES - TREES
14:30		H09-39	180	2.1	START H09 - MID
14:33		H09-36	198	2.0	
14:36		H09-42	18	1.9	
14:40		H09-33	198	1.6	
14:44		H09-31	18	2.1	
14:48		H09-28	198	1.7	
14:51		H09-25	18	2.0	
14:54		H09-22	198	0.8	

Prepared by: BLC

Page 9 of 14

GBA
MULTIBEAM SURVEY LOG

Date 20 June 22 2010
Vessel Name Sea Fix

Project ID #	631-10A
Description	Passaic River Multibeam

Raw Data Directory Passaic 2010 MB

Echo Sounder Reson 8101

Matrix/LNW File 409

Positioning POSMV 320 w/ Leica RTK

Average Boat
Speed (kts)

General Remarks

People 3

HORZ/VERT CHECKIN

Time	RTK Tide
------	----------

Tide Board

S.O.S./Draft 4933 // 1.25

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
1458	H02	20	18°	0.8	
1502	H09	19	198	1.1	
1503	H09	14	18°	2.3	
1504	H09	43	198°	1.0	
1509	H09	47	17°	0.8	
1515	H09	18	198°	0.8	
1519	SV	Cast	H09		
1520		Bar check			
1526		Cross 62	280	1.2	
1527		62A		1.4	
1528		Cross 61	285		
1529		61A	109°		
1532		Cross 60	291	1.3	
1533		60A	109	1.2	
1535		Cross 59	289	1.2	
1536		59A	108	1.1	
1538		Cross 58	282	1.4	
1538		58	102	1.4	
1540		Cross 57	281	1.4	
1541		57A	99	1.4	

Prepared by: ECD

Page 10 of 14

GBA MULTIBEAM SURVEY LOG

Date June 22 2010
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory Passaic 2010SB

Echo Sounder Reson 8101

Matrix/LNW File H01

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) 5

General Remarks

People 3

HORZ/VERT CHECKIN

Time RTK Tide Tide Board

S.O.S./Draft 4939 / 62
4944.6/2.4

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
1512		CROSS 56	277		
1543		564	77°		
1545		CROSS 55			
1548		1547 WEST LONG			
1554		1554 CENTER			
1601		1601 WEST LONG			
1605		Ba. check			
		Multibeam edges			- 50 LAST - 4922.6
1614		H01-60	13°	1.4	START H01 EDGES
1621		H01-31	193°	2.6/1.2	
1634		H01-28	13	1.3	OPEN PORT BEAMS - GANT GET (M2)
1640		H01-62	193	2.9/1.3	
		Hit mb head on rock			
		check for any charges to load config			
		Roll Test shows us to -2.30° from -2.50			

Prepared by: B4

Page 11 of 14

GBA MULTIBEAM SURVEY LOG

Date 6/22/10
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory PASSAIC 2010 MB
Matrix/LNW File ~~4922.6~~

Echo Sounder Reson 8101
Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) 5
People 2
S.O.S./Draft 4922.6/3.4

General Remarks
HORZ/VERT CHECKIN
Time RTK Tide Tide Board

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
17:15		H02-17	30	1.2	
17:16		H02-14	105	1.2	open 27BD beams
17:20		H02-11	183 50		open Port Side
17:22		H02-12	183 30	2.0	
17:24		H02-09	183		USE
17:25		H02-45	183		open Port Side
17:26		H02-47		1.3	open 57BD side beams
17:32		H03-46	232		open STD 7:00 4.74
17:34		H03-48	152	1.2	open Port
17:36		H03-17A	132	1.6	open Port
17:37		H03-17	152	1.2	open STD
17:42		H03-15	332	2.3	
17:45		H04-18	344	1.3	
17:48		H04-14	244 164	1.4	open Port
17:50		H04-48	244	1.4	open STD
17:52		H04-50	164	1.4	open 40 Port
17:54		H04-48	344	1.8	open STD
17:57		H05-44	332	1.3	
18:00		H05-46	158	2.5	

Prepared by: ECD

Page 12 of 12

GBA MULTIBEAM SURVEY LOG

Date 6/22/10
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory PASSAIC2010 MB
Matrix/LNW File H05/H06/H07/H08

Echo Sounder Reson 8101
Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) 5

General Remarks

People 3

HORZ/VERT CHECKIN

S.O.S./Draft 4922.6/3.4

Time RTK Tide Tide Board

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
18:02	H05	- 49	338	1.7	TREES
18:04	H05	- 12	158	1.9	TREES - W. BANK
18:10	H06	- 49	50	2.3	
18:12	H06	- 51	185	1.2	
18:14	H06	- 10	50	2.2	
18:16	H06	- 08	185	1.6	
18:19	H07	- 10	28	2.2	OPEN PORT BEAMS - CRACK TREES
18:21	H07	- 43	208	2.2	E. BANK
	H08		28	1.2	
18:26	H07	- 43	208	1.9	
18:28	H07	- 45	208	2.2/1.9	
18:31	H07	- 09	208	1.8	
18:34	H07	- 06	208	1.8	
18:35	H08	- 16	90	1.8	OPEN PORT BEAMS - LONG. W. BANK
18:41	H08	- 14	189	1.7	OPEN STBD BEAMS
18:46	H08	- 47	90	2.0	E. BANK

Prepared by: 260

Page 13 of 14

GBA MULTIBEAM SURVEY LOG

Date 6/22/2010
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory Passaic 2010 MB
Matrix/LNW File H08

Echo Sounder Reson 8101
Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) _____

General Remarks _____

People 3

HORZ/VERT CHECKIN
Time RTK Tide Tide Board

S.O.S./Draft 2080 / 3.11

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
18:49		H08-50	189	1.0	
18:53		H08-53	9	1.0	
18:58		H09-49	180	0.9	W08 576D 1000 1000 1000
19:02		H09-50	180	1.1	1000 1000 1000
19:06		H09-51	180		1000 1000 1000
19:08		H09-52	180		1000 1000 1000
19:10		H09-53	180		1000 1000 1000
19:12		H09-54	180		1000 1000 1000
19:14		H09-55	180		1000 1000 1000
19:16		H09-56	180		1000 1000 1000
19:18		H09-57	180		1000 1000 1000
19:20		H09-58	180		1000 1000 1000
19:22		H09-59	180		1000 1000 1000
19:24		H09-60	180		1000 1000 1000
19:26		H09-61	180		1000 1000 1000
19:28		H09-62	180		1000 1000 1000
19:30		H09-63	180		1000 1000 1000
19:32		H09-64	180		1000 1000 1000
19:34		H09-65	180		1000 1000 1000
19:36		H09-66	180		1000 1000 1000
19:38		H09-67	180		1000 1000 1000
19:40		H09-68	180		1000 1000 1000
19:42		H09-69	180		1000 1000 1000
19:44		H09-70	180		1000 1000 1000
19:46		H09-71	180		1000 1000 1000
19:48		H09-72	180		1000 1000 1000
19:50		H09-73	180		1000 1000 1000
19:52		H09-74	180		1000 1000 1000
19:54		H09-75	180		1000 1000 1000
19:56		H09-76	180		1000 1000 1000
19:58		H09-77	180		1000 1000 1000
20:00		H09-78	180		1000 1000 1000
20:02		H09-79	180		1000 1000 1000
20:04		H09-80	180		1000 1000 1000
20:06		H09-81	180		1000 1000 1000
20:08		H09-82	180		1000 1000 1000
20:10		H09-83	180		1000 1000 1000
20:12		H09-84	180		1000 1000 1000
20:14		H09-85	180		1000 1000 1000
20:16		H09-86	180		1000 1000 1000
20:18		H09-87	180		1000 1000 1000
20:20		H09-88	180		1000 1000 1000
20:22		H09-89	180		1000 1000 1000
20:24		H09-90	180		1000 1000 1000
20:26		H09-91	180		1000 1000 1000
20:28		H09-92	180		1000 1000 1000
20:30		H09-93	180		1000 1000 1000
20:32		H09-94	180		1000 1000 1000
20:34		H09-95	180		1000 1000 1000
20:36		H09-96	180		1000 1000 1000
20:38		H09-97	180		1000 1000 1000
20:40		H09-98	180		1000 1000 1000
20:42		H09-99	180		1000 1000 1000
20:44		H09-100	180		1000 1000 1000

Prepared by: CO

Page 14 of 14

GBA MULTIBEAM SURVEY LOG

Date 6/23/
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory Passaic 2010 MB

Echo Sounder Reson 8101

Matrix/LNW File H10/111

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) 4

General Remarks

People 2

HORZ/VERT CHECKIN

S.O.S./Draft 49/4.4/3.4

Time RTK Tide Tide Board

6:27 3.48 3.51

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
	<u>6:27</u>	<u>Tide @ Position</u>	<u>check</u>	<u>@</u>	<u>C PG Dock</u>
	<u>6:31</u>	<u>Sv cast @</u>	<u>H10</u>		
<u>6:37</u>	<u>6:37</u>	<u>H10-38</u>	<u>40</u>	<u>2.4/1.2</u>	
<u>6:39</u>		<u>H10-40</u>	<u>184</u>	<u>1.8/1.6</u>	
<u>6:41</u>		<u>H10-43</u>	<u>4</u>	<u>1.3</u>	
<u>6:43</u>		<u>H10-45</u>	<u>184</u>	<u>1.8</u>	<u>TREES - HDOP ↑↓</u>
<u>6:45</u>		<u>H10-49</u>	<u>4</u>	<u>1.7</u>	<u>" "</u>
<u>6:47</u>		<u>H10-51</u>	<u>184</u>	<u>2.8</u>	<u>Lost RTK</u>
<u>6:46</u>		<u>H10-53</u>	<u>184</u>	<u>2.4</u>	<u>TREES</u>
<u>6:50</u>		<u>H10-15</u>	<u>4</u>	<u>2.4/1.6</u>	<u>LOW BANK</u>
<u>6:52</u>		<u>H10-12</u>	<u>184</u>	<u>1.7</u>	<u>WALL - OPEN STEP</u>
<u>6:55</u>		<u>H10-11</u>	<u>4</u>	<u>2.3</u>	<u>TREES/WALL - OPEN PORT</u>
<u>6:58</u>		<u>H11-16</u>	<u>346</u>	<u>1.6</u>	
<u>6:59</u>		<u>H11-19</u>	<u>166</u>	<u>2.8/1.5</u>	
<u>7:01</u>		<u>H11-14</u>	<u>346</u>	<u>1.6</u>	
		<u>H11-21</u>			<u>RTK HDOP TOO HIGH</u>
<u>7:03</u>		<u>H11-41</u>	<u>346</u>	<u>1.4</u>	
<u>7:06</u>		<u>H11-43</u>	<u>346</u>	<u>2.1</u>	

Prepared by: ECO

Page 1 of 5

GBA MULTIBEAM SURVEY LOG

Date 6/23/10
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory PASSAIC2010MB

Echo Sounder Reson 8101

Matrix/LNW File H11/H12

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) 4

General Remarks

People 4

HORZ/VERT CHECKIN

Time RTK Tide

Tide Board

S.O.S./Draft 49/4.4/3.4

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
7:08		H11-45	346	1.6	TREES
7:11		H11-40	166	1.5/1.7	
7:12		H11-42	346	1.7	
7:13		H11-44	166	1.5/2.7	
7:14		H11-46	346	1.4	
7:16		H11-17	166	1.9	LOST RTK
7:17		H11-17	166	1.5/3.2	HEAVY TREES - "
7:		H11-17	166		BAD SATS - RUN LATER
7:20		H12-34	10	1.4	
7:23		H12-37	190	1.4	
7:27		H12-39	100	1.3	
7:30		H12-41	190	1.3	
7:34		H12-43	100	1.4	
7:36		H12-45	190	1.4	
7:38		H12-26	100	1.4	
7:41		H12-18	190	1.4	
7:45		H12-20	100	1.7	
7:48		H12-22	190	1.6	
7:53		H12-24	100	1.6	

Prepared by: BKL

Page 2 of 5

GBA MULTIBEAM SURVEY LOG

Date 6/23/10 Project ID # 631-10A
 Vessel Name Sea Fix Description Passaic River Multibeam

Raw Data Directory PASSAIC2010MB Echo Sounder Reson 8101
 Matrix/LNW File H12/ Positioning POSMV 320 w/ Leica RTK
 Average Boat Speed (kts) 4.5 General Remarks _____
 # People 4 **HORZ/VERT CHECKIN** _____
 S.O.S./Draft 4910.4 / 3.4 Time RTK Tide Tide Board _____

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
7:59		H12-29	190	2.1	
8:03		H12-31	10°	1.7	HDOP SPIKES - Lost RTK
8:04		H12-08	190	2.1	
8:07		H12-30	10	1.7	
8:09		H12-22	190	2.1	
8:12		H12-45	10	1.6	
8:14		H11-19	166	1.6	
8:15		H11-22	346	1.6	
8:16		H11-18	166	1.6	
8:17		H11-20	346	3.4	
8:18		H11-16	166	1.6	
8:19		H11-18	346	1.5	
8:20		H11-33	166	1.5	
8:21		H11-37	346	1.7	
8:24		H11-23	346	2.1	
8:26		H11-27	166	1.5/2.1	
8:27		H11-31	346	2.1	
8:29		H11-35	166	1.5/2.1	
8:30		H11-38	346	2.1	

Prepared by: BFC

Page 3 of 5

GBA MULTIBEAM SURVEY LOG

Date 6/23/10 Project ID # 631-10A
 Vessel Name Sea Fix Description Passaic River Multibeam

Raw Data Directory PAESSAIC 2010 MJS Echo Sounder Reson 8101
 Matrix/LNW File H10 Positioning POSMV 320 w/ Leica RTK
 Average Boat Speed (kts) 5 General Remarks _____
 # People 4 **HORZ/VERT CHECKIN** _____
 S.O.S./Draft 49/4.4/3.4 Time RTK Tide Tide Board _____

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
8:33		H10-18	184	2.3	
8:35		H10-22	4	1.4	
8:37		H10-26	184	2.1	
8:38		H10-30	4	2.1	
8:39		H10-34	184	2.1/1.3	
		H10			
8:43		H11-41	346		BRIDGE LINES
8:44		H11-46	166	2.1	UNDER BRIDGE
8:45		H11- 47 27	346	2.1	BAD RTK HDOP
8:47		H11-23	166	2.3	
8:47		H11-18	346	2.5	
		BR			
9:55		Branches E	0	1071	
9:57		CROSS 63	272	1.3	
9:58		63H	92	1.3	
9:00		CROSS 64	257	1.3	
9:00		64A	77	1.3	
9:03		CROSS 65	253	1.4	
9:05		65H	73	1.4	

Prepared by: BKL

Page 4 of 5

Description **Passaic River Multibeam**

S.O.S./Draft 4939/2

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
9:06		CROSS 66	291		
9:07		66A	111		
9:08		CROSS 67	294		
9:09		67A	104		
9:12		CROSS 68	287		
9:13		68A	107		
9:14		CROSS 69	312		
9:15		69A	132		
		Long Lines	North of Bridge		
9:16		000-0916			East Bank
9:20		000-0920			Center Line
9:23		000-0923			West Bank
		Long Lines	South of Bridge		
9:28		000-0928			West Bank
9:30		000-0930			Central
9:32		000-0932			East Bank
9:59		HD-36	4°		MR Gap Cilia

Page 5 of 5

GBA MULTIBEAM SURVEY LOG

Date 6/23/2010
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory Passaic Patch

Echo Sounder Reson 8101

Matrix/LNW File _____

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) _____

General Remarks Closing Patch & Performance

People 3

HORZ/VERT CHECKIN
Time RTK Tide Tide Board

S.O.S./Draft _____

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
		<u>ROLL Test 2010</u>			<u>Reson 75ms</u>
	<u>001-1203</u>		<u>N</u>	<u>1.2</u>	<u>-2.40, -2.35 50m Range</u>
	<u>001-1204</u>		<u>S</u>		
	<u>002-1206</u>		<u>N</u>	<u>1.2</u>	<u>-2.30, -2.40</u>
	<u>002-1207</u>		<u>S</u>		
	<u>003-1208</u>		<u>N</u>	<u>1.2</u>	<u>-2.35, -2.40</u>
	<u>003-1210</u>		<u>S</u>		
		<u>Pitch & Yaw 3</u>			
	<u>001-1230</u>			<u>↓</u>	
	<u>001-1231</u>			<u>↑</u>	
	<u>002-1234</u>			<u>↓</u>	
	<u>002-1235</u>			<u>↑</u>	
	<u>003-1236</u>			<u>↓</u>	
	<u>003-1237</u>			<u>↑</u>	
	<u>004-1239</u>			<u>↓</u>	
	<u>004-1240</u>			<u>↑</u>	
	<u>005-1242</u>			<u>↓</u>	
	<u>005-1243</u>			<u>↑</u>	

Prepared by: _____

Page 1 of 5

GBA
MULTIBEAM SURVEY LOG

Date 6/23
Vessel Name **Sea Fix**

Project ID # 631-10A

Description **Passaic River Multibeam**

Raw Data Directory Passaic 2010 Park

Echo Sounder **Reson 8101**

Matrix/LNW File PerFormance

Positioning POSMV 320 w/ Leica RTK

**Average Boat
Speed (kts)** _____

General Remarks

HORZ/VERT CHECKIN

People

Time	RTK Tide
------	----------

Tide Board

S.O.S./Draft

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
		Leica . Performance			MB (Ant Hgt 7.40)
1253	001	1253			
1255	002	1255			
1256	003	1256			
1258	004	1258			
1259	005	1259			
	008	1300			Do not use
1301	008	1301			
1302	009	1302			
13:03	010	1303			
13:04	011	1304			
13:05	12	13:05			
13:07	010	13:07			Bear Hwy 18 (Battered)
13:08	003	13:08			Bear Hwy

Prepared by: _____

Page 2 of 5

GBA
MULTIBEAM SURVEY LOG

Date 6/23/10
Vessel Name Sea Fix

Project ID # 631-10A

Description **Passaic River Multibeam**

Raw Data Directory

Echo Sounder	Reson 8101
--------------	------------

Matrix/LNW File

Positioning POSMV 320 w/ Leica RTK

**Average Boat
Speed (kts)**

General Remarks GRA Performance MB

HORZ/VERT CHECKIN

People 3

Time	RTK Tide	Tide Board
------	----------	------------

S.O.S./Draft *l*

[illegible]

Prepared by: 700

Page 3 of 5

GBA
MULTIBEAM SURVEY LOG

Date 6/23/10
Vessel Name **Sea Fix**

Project ID # 631-10A

Description **Passaic River Multibeam**

Raw Data Directory SR

Echo Sounder Reson 8101

Matrix/LNW File

Positioning POSMV 320 w/ Leica RTK

**Average Boat
Speed (kts)** _____

General Remarks Per Formative GBA

HORZ/VERT CHECKIN

People

Time	RTK Tide	Tide Board
------	----------	------------

S.O.S./Draft 4964 11.2

[illegible]

Prepared by: ZCD

Page 4 of 5

GBA
MULTIBEAM SURVEY LOG

Date 6/23/2010
Vessel Name **Sea Fix**

Project ID # **631-10A**

Description **Passaic River Multibeam**

Raw Data Directory

Echo Sounder Reson 8101

Matrix/LNW File _____

Positioning POSMV 320 w/ Leica RTK

**Average Boat
Speed (kts)** _____

General Remarks SR Per Formance 1e/c

HORZ/VERT CHECKIN

People

Time	RTK Tide	Tide Board
------	----------	------------

S.O.S./Draft _____

[illegible]

Prepared by: _____

Page 5 of 5

GBA MULTIBEAM SURVEY LOG

Date 6/23/2010
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory Passaic 2010 MB

Echo Sounder Reson 8101

Matrix/LNW File _____

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) _____

General Remarks _____

People _____

HORZ/VERT CHECKIN

Time RTK Tide Tide Board

S.O.S./Draft _____

16:33 2.95 3.00

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
	<u>16:33</u>	<u>- Tide Check</u>	<u>@ Port</u>		
	<u>16:35</u>	<u>- Sound Cast</u>	<u>@ MOB</u>		
<u>16:39</u>	<u>A08-116</u>		<u>296</u>	<u>1.4</u>	<u>up to RR Bridge</u>
<u>16:42</u>	<u>A08-113</u>		<u>116°</u>	<u>1.2</u>	
<u>16:44</u>	<u>A08-110</u>		<u>296</u>	<u>1.2</u>	
<u>16:46</u>	<u>A08-107</u>		<u>116</u>	<u>1.4</u>	
<u>16:48</u>	<u>A08-105</u>		<u>296°</u>	<u>1.4</u>	
<u>16:50</u>	<u>101</u>		<u>296</u>	<u>1.4</u>	
<u>16:53</u>	<u>A08-116A</u>		<u>296°</u>	<u>1.4</u>	
<u>16:55</u>	<u>A08-121</u>		<u>116</u>	<u>1.2</u>	
<u>16:57</u>	<u>A08-124</u>		<u>296°</u>	<u>1.2</u>	
<u>16:59</u>	<u>A08-127</u>		<u>116</u>	<u>1.2</u>	
<u>17:01</u>	<u>A08-130</u>		<u>296°</u>	<u>1.2</u>	
<u>17:02</u>	<u>A08-134</u>		<u>116</u>	<u>1.2</u>	
<u>17:04</u>	<u>A08-139</u>		<u>296</u>	<u>1.2</u>	
<u>17:06</u>	<u>A08-144</u>		<u>116</u>	<u>1.2</u>	
<u>17:08</u>	<u>A08-148</u>		<u>296°</u>	<u>1.2</u>	
<u>17:10</u>	<u>A08-154</u>		<u>296</u>	<u>1.2</u>	
<u>17:12</u>	<u>A08-161</u>		<u>296°</u>		

Prepared by: EC D

Page 1 of 2

GBA MULTIBEAM SURVEY LOG

Date 6/23/2010
Vessel Name Sea Fix

Project ID # 631-10A
Description Passaic River Multibeam

Raw Data Directory _____

Echo Sounder Reson 8101

Matrix/LNW File _____

Positioning POSMV 320 w/ Leica RTK

Average Boat Speed (kts) _____

General Remarks _____

People _____

HORZ/VERT CHECKIN

Time RTK Tide Tide Board

S.O.S./Draft _____

12:55 4.12 4.10

UTC Time	MB RNG	File	Line AZ	HDOP	Remarks
1713	A06	106	116	1.2	
1715	A06	110	296	1.3	
1717	A08	173	116	1.2	
1719	A08	176	296	1.2	
1722	A08	179	116	1.2	
1724	A06	182	296	1.2	
1731	A05	129	185°	1.2	
1733	A05	129A	185°	1.2	Restart
1739	A05	129B	96	1.3	
		Rap 1 lee 5' 20', 10',			
		Single Beam check lines			
1753		0091	207°	1.6	
1754		0091A	27°	1.6	
1756		0086	216	1.0	
1758		0086A	36°	1.0	
1800		0091B	207°	1.0	
1915		Position	check @ Dock		

Prepared by: SCM

Page 2 of 2

Sound Velocity Profile Logs

Date	Time	Northing	Easting	Desc
06/09/10	17:40:32	685002.21	596870.48	
06/10/10	9:18:26	685072.07	596920.58	A02
06/10/10	11:01:43	686604.83	596713.39	A03
06/10/10	14:18:37	689003.30	597225.35	A04
06/10/10	18:10:19	689410.07	597429.10	A04
06/11/10	8:20:27	686524.83	596873.81	A02
06/11/10	11:14:39	690879.40	597785.47	A05
06/11/10	14:33:20	693991.17	598261.55	A07
06/11/10	15:28:49	695239.05	597539.83	A07
06/12/10	8:52:54	690989.83	597781.39	A05
06/12/10	10:20:28	693474.39	598340.61	A06
06/12/10	11:20:06	694819.77	597951.75	A08
06/12/10	12:49:16	695665.35	596312.63	B01
06/12/10	14:03:59	695529.40	594812.48	B01
06/13/10	7:31:56	695143.36	597623.14	A08
06/13/10	9:42:28	695717.11	595209.44	B01
06/13/10	11:25:11	695544.01	595009.15	B02
06/13/10	12:50:50	695347.64	593181.81	B03
06/13/10	14:05:41	695312.61	593343.82	B03
06/15/10	7:40:48	694427.71	591277.64	B04
06/15/10	10:13:01	694766.24	591715.78	B03
06/15/10	11:34:17	693005.21	590571.96	B05
06/15/10	13:38:24	692370.98	589611.44	B06
06/15/10	15:03:52	693212.45	590708.66	B05
06/16/10	7:47:17	692500.71	586791.90	B07
06/16/10	8:55:49	692474.73	586855.41	B08
06/16/10	10:39:54	693661.57	585662.80	C01
06/16/10	11:53:21	693531.69	585789.71	C02
06/16/10	12:15:55	693537.28	585789.18	C01
06/17/10	8:34:11	696813.92	584736.40	C03
06/17/10	9:33:38	697817.76	584785.45	C04
06/17/10	12:50:20	701447.34	585317.62	C06
06/17/10	14:26:04	702511.16	585818.65	C08
06/17/10	15:52:10	702151.03	585531.68	C08
06/18/10	7:59:45	697820.76	584745.45	C04
06/18/10	9:19:33	704034.48	586880.79	C09
06/18/10	10:08:37	704893.68	587093.44	C10
06/18/10	11:29:26	706533.15	587661.03	D01
06/18/10	15:09:06	707774.71	588754.46	D01
06/18/10	10:45:04	706191.33	587448.91	C11
06/19/10	8:53:09	707484.92	588482.86	D01
06/19/10	10:40:02	710803.34	589415.48	D04
06/19/10	12:24:00	712766.58	590305.61	D06
06/19/10	12:42:51	708265.85	589239.54	D02
06/19/10	13:56:15	711927.77	589930.71	D05
06/19/10	15:45:04	716259.31	592235.87	D09
06/20/10	10:13:03	712411.49	592235.87	D06
06/20/10	11:53:09	715213.21	592235.87	D08
06/20/10	14:26:25	716322.12	592235.87	E01
06/20/10	16:56:54	720753.85	592235.87	F02
06/21/10	10:00:31	721143.27	592235.87	F02
06/21/10	14:28:18	724343.45	592235.87	G03
06/21/10	18:28:24	725397.61	592235.87	G04
06/22/10	9:05:16	725170.89	592235.87	H01
06/22/10	11:05:42	729737.75	592235.87	H05
06/22/10	13:10:39	732004.66	592235.87	H07
06/22/10	15:16:31	733552.04	592235.87	H09
06/22/10	16:23:42	725029.53	592235.87	H01a
06/23/10	6:31:53	734972.26	592235.87	H10
06/23/10	8:49:13	736048.20	592235.87	H11
06/23/10	16:35:15	695139.17	597733.81	A08
06/23/10	17:38:15	692989.88	598358.57	A05

Daily Horizontal Position Checks

Date	Time	Northing	Easting	Location
06/10/10	7:22:39	660438.94	579042.49	EM DOCK
06/10/10	20:34:48	660438.21	579042.26	EM DOCK
06/11/10	7:04:17	660438.64	579042.30	EM DOCK
06/11/10	18:05:36	660438.58	579042.17	EM DOCK
06/12/10	8:15:39	660438.64	579042.30	EM DOCK
06/12/10	16:55:44	660438.82	579042.53	EM DOCK
06/13/10	7:00:55	660438.82	579042.16	EM DOCK
06/13/10	16:32:49	660439.61	579042.25	EM DOCK
06/14/10	8:01:08	660439.06	579042.12	EM DOCK
06/15/10	7:01:56	660438.76	579041.98	EM DOCK
06/15/10	17:29:06	660438.64	579041.80	EM DOCK
06/16/10	7:04:21	660439.18	579041.65	EM DOCK
06/16/10	16:55:28	660438.82	579042.03	EM DOCK
06/17/10	7:02:21	660439.55	579042.21	EM DOCK
06/17/10	18:27:01	660439.06	579042.12	EM DOCK
06/18/10	7:05:51	660440.94	579040.12	EM DOCK
06/18/10	7:06:50	660439.06	579041.75	EM DOCK
06/18/10	16:34:23	733784.93	597070.46	CPG DOCK
06/19/10	8:18:22	733784.38	597071.07	CPG DOCK
06/19/10	16:35:07	733783.53	597071.16	CPG DOCK
06/20/10	7:13:15	733783.78	597070.93	CPG DOCK
06/20/10	17:11:27	733782.74	597070.98	CPG DOCK
06/21/10	8:10:05	733783.65	597070.75	CPG DOCK
06/21/10	18:45:27	733783.59	597070.65	CPG DOCK
06/22/10	7:35:51	733783.78	597070.79	CPG DOCK
06/22/10	19:29:29	733783.23	597070.89	CPG DOCK
06/23/10	6:26:58	733783.72	597070.84	CPG DOCK

Daily Vertical Tide Checks

Date	Time	Northing	Easting	Description	RTK	BOARD
06/10/10	9:10:40	695108.35	597797.17	PORT	2.44	2.50
06/10/10	14:10:37	695151.22	597782.76	PORT	-0.70	-0.65
06/10/10	20:03:14	695156.04	597815.80	PORT	4.45	4.50
06/11/10	8:00:13	695156.34	597801.21	PORT	3.33	3.40
06/11/10	13:34:21	695147.30	597790.21	PORT	-0.94	-0.90
06/11/10	17:35:42	695169.82	597801.70	PORT	2.95	2.95
06/12/10	8:48:13	695223.40	597739.17	PORT	3.60	3.65
06/12/10	11:13:23	695140.81	597776.80	PORT	1.93	1.90
06/12/10	16:17:28	695149.41	597785.68	PORT	-1.00	-0.90
06/13/10	7:29:06	695165.13	597757.11	PORT	2.35	2.40
06/13/10	8:59:39	695181.90	597828.48	PORT	3.85	3.85
06/13/10	16:09:04	695139.02	597812.46	PORT	-1.35	-1.30
06/15/10	7:33:47	695171.70	597745.36	PORT	-0.37	-0.30
06/15/10	11:20:23	695162.58	597797.53	PORT	4.10	4.20
06/15/10	16:54:10	695166.45	597793.91	PORT	-1.15	-1.10
06/16/10	7:31:54	695171.37	597810.01	PORT	-1.80	-1.75
06/16/10	12:03:41	695182.19	597825.94	PORT	4.10	4.10
06/16/10	16:13:39	695153.15	597809.21	PORT	0.12	0.10
06/17/10	8:18:29	695143.91	597805.14	PORT	-1.50	-1.50
06/17/10	12:43:18	702182.72	585768.44	PATH	3.81	3.76
06/17/10	17:53:00	695116.69	597815.47	PORT	-0.70	-0.60
06/18/10	7:46:52	695173.11	597819.15	PORT	-1.40	-1.35
06/18/10	13:21:45	702204.73	585774.18	PATH	4.20	4.19
06/18/10	16:42:24	733783.84	597070.79	CPG	3.00	2.90
06/19/10	8:20:04	733784.26	597071.07	CPG	-1.16	-1.17
06/19/10	12:36:16	702182.09	585776.25	PATH	1.90	1.95
06/19/10	16:35:20	733783.41	597071.16	CPG	4.20	4.10
06/20/10	7:36:19	720788.19	592072.15	NUTLEY	0.40	0.35
06/20/10	12:34:11	720728.52	592061.14	NUTLEY	-0.10	-0.15
06/20/10	16:59:33	720740.24	592047.25	NUTLEY	4.70	4.60
06/21/10	8:09:03	733783.84	597070.51	CPG	1.10	1.08
06/21/10	14:23:04	720829.87	592107.87	NUTLEY	1.10	1.16
06/21/10	18:45:27	733783.59	597070.65	CPG	3.81	3.73
06/22/10	7:35:51	733783.78	597070.79	CPG	2.61	2.59
06/22/10	12:34:10	733850.69	596945.27	CPG	-1.39	-1.46
06/22/10	19:29:29	733783.23	597070.89	CPG	4.27	4.26
06/23/10	6:26:58	733783.72	597070.84	CPG	3.48	3.51
06/23/10	9:55:28	733776.39	596976.44	CPG	1.38	1.41
06/23/10	16:33:47	695171.44	597798.42	PORT	2.95	3.00
06/23/10	17:59:38	695168.78	597814.41	PORT	4.12	4.10

APPENDIX 5

Portable Disk including:

**Survey Report,
AutoCad Drawings,
Hypack Files,
Field Notes,
ASCII Data,**



BATHYMETRIC SURVEY

Field Report

**SITE VISIT
SUMMARY OF FINDINGS
JUNE 8-11, 2010
AND JUNE 23, 2010**

LOWER PASSAIC RIVER, NEWARK, NJ

Prepared by:

AECOM
5757 Woodway, Suite 101 W
Houston, TX 77057

Amended June 29, 2010

**BATHYMETRIC SURVEY
FIELD REPORT
SITE VISIT
SUMMARY OF FINDINGS
JUNE 8-11, 2010
AND JUNE 23, 2010**

PROJECT:

Lower Passaic River Restoration Project, AECOM Environment, Project Number 60139067

PURPOSE:

The AECOM Houston office was tasked with providing oversight for a multibeam and single beam hydrographic survey of the Lower Passaic River between river miles 0-14. The survey is conducted periodically in support of the ongoing Lower Passaic River Study Area (LPRSA) Remedial Investigation / Feasibility Study. Two main objectives were identified for the June 8-11, 2010 site visit. The first objective was confirmation that Gahagan & Bryant Associates, Inc. (GBA) equipment setup and calibration was consistent with industry procedures and standards. The second objective was the oversight of survey data collection between river miles 0-2. A second site visit was conducted on June 23, 2010 to provide survey oversight between river miles 13-14.

SURVEY LOCATION:

The survey location is comprised of an area of Newark Bay and the Lower Passaic River between river miles 0-14, Newark, NJ.

Multibeam patch test conducted in Newark Bay - (approximate location Lat. 40° 39' 38"N, Long . 074° 08' 46"W). See Process section. June 8, 2010, Tuesday

Performance test conducted in Newark Bay - (approximate location Lat. 40° 39' 38"N, Long . 074° 08' 46"W). See Process section. June 8, 2010, Tuesday

EQUIPMENT AND SOFTWARE:

The equipment used aboard the Gahagan & Bryant Associates Inc. (GBA) 25' survey vessel SeaFix during the site visit, patch test and performance test was consistent with that listed in the

company's Technical Proposal dated April 29, 2010. The equipment included the Reson 8101 multibeam echosounder, Odem Mark III depth recorder, Trimble RTK positioning system, Applanix-TSS POS-MV and HYPACK/HYSWEEP data collection/processing software. In addition an Applied Microsystems velocity probe was used for sound velocity measurements and a disc type aluminum plate was used for bar check calibrations. GBA personnel included Ed DeAngelo, Travis Schmidt, Paul Seaboldt and Blair Carlson.

PROCESS:

First Site Visit (June 8-11, 2010)

June 8, 2010, Tuesday, 0700-1800

- GBA performed a patch test in Newark Bay which consisted of a small survey of a series of lines designed to reveal residual biases in pitch, roll, yaw and latency. The offsets and delays that were determined for each of the biases were then used to correct and calibrate the multi-beam system. Static offset measurements and checks were made in Baltimore, MD prior to mobilizing and once again when the vessel was on site in Newark, NJ. The weather conditions were good with temperatures at 65°-70°, clear skies and calm seas during the testing process.

- A quality assurance performance test was conducted in Newark Bay in the general vicinity of the patch test. Separate multibeam and single beam surveys were run and the overlapping data compared to evaluate the multibeam data quality. This check provided a statistical estimate of the data accuracy. The quality control calibration and performance test were processed and adjusted aboard the survey vessel prior to any multibeam data collection.

June 9, 2010, Wednesday, 0700-1900,

- Verify horizontal and vertical control with both Trimble and Leica positioning systems.

- Install and level the tide staff at tide station “Port” located at approximate river mile 2.2.

- Begin collecting multibeam data and single beam cross section and longitudinal line data between approximate river miles -0.25 - 0.5.

June 10, 2010, Thursday, 0700-2030

- Collect multibeam data and single beam cross section and longitudinal line data between approximate river miles 0.5 - 1.5.

June 11, 2010, Friday, 0700-1830

- Collect multibeam data and single beam cross section and longitudinal line data between approximate river miles 1.5 - 2.3.

Second Site Visit (June 23, 2010)

June 23, 2010, Wednesday, 0630-1930

- Collect multibeam data and single beam cross section and longitudinal line data between approximate river miles 13-14.
- Establish tide gauge offset points at approximate river mile 0.9 and 14. The offset points will be used in leveling tide gauge stilling wells.
- A patch test was performed at the approximate location of the June 8, 2010 test. The resulting residual biases calculated were identical to those generated during the first site visit.
- A quality assurance performance test was conducted at the approximate location of the June 8, 2010 test. The results of this test were not available at the time this report was written. GBA will provide the results in their survey report. Both Trimble and Leica positioning systems were used during the test to provide a check of the horizontal and vertical control system.
- Collect multibeam data and single beam cross section and longitudinal line data in the area of river mile 2. A portion of this reach near the river bank had been too shallow due to low tide conditions while surveying on June 11, 2010.



GBA SURVEY VESSEL SEAFIX
WITH MULTIBEAM DOCKED AT THE
ELIZABETH CITY MARINA



MULTIBEAM SONAR HEAD
MOUNTED ABOARD THE SEAFIX



BARCHECK BEING CONDUCTED
ABOARD THE SEAFIX ON
THE LOWER PASSAIC RIVER



TIDE STAFF "PORT" AT
APPROXIMATE RM 2.2 ON THE
LOWER PASSAIC RIVER



TIDE GAUGE STILLING
WELL OFFSET POINT
AT APPROXIMATE
RIVER MILE 0.9 ON
THE LOWER PASSAIC
RIVER

RESULTS:

The quality assurance performance test conducted during the June 8-11, 2010 site visit yielded a mean difference of 0.04' between the multi-beam survey and the single beam survey run over the same location. This compares favorably with the U.S. Army Corps of Engineers, EM 1110-2-1003, Chapter 3, Table 3.1, Hard Bottom Material classification of $\pm 0.1'$ maximum allowable bias.

The 95% confidence level in 60' of water was 0.55' which is less than the $\pm 1.0'$ maximum allowable difference as indicated in the U.S. Army Corps of Engineers, EM 1110-2-1003, Chapter 3, Table 3-1 under the Hard Bottom Material classification for depths greater than 40'.

The results of the quality assurance performance test conducted during the June 23, 2010 site visit were not available at the time this report was written. GBA will provide the results in their survey report.

Horizontal position checks were performed at the dock at the beginning and end of each day to reveal any potential positioning errors.

A tide staff was installed on June 9, 2010 at river mile 2.2. The station designated "PORT" was established as a check for the RTK tides used while surveying this portion of the river. Checks were made against the staff a minimum of twice per day. Additionally a point designated "CPG1" was established prior to the second site visit on the steel sheet pile bulkhead adjacent to a floating dock at the Cooperating Parties Group (CPG) offices (approximate river mile 13.4). Point "CPG1" was used as a reference mark for measuring to the water surface and provided a check for the RTK tides used while surveying in this area of the river.

During both site visits single beam bar checks were performed within the project area as a method of calibration for acoustic depth measurements. A difference between the bar depth and an echosounder depth represented corrections that needed to be made to subsequent recorded depths. Bar checks were performed at a minimum of twice per day. Checks were made at 5' depth intervals. A multibeam bar check was conducted in Baltimore, MD prior to mobilizing and once again when the vessel was on site in Newark, NJ.

Sound velocity profiles were collected during both site visits using a velocity probe to measure changes in the water column such as temperature and salinity that affect data quality. Velocity profiles were taken in the work area at the beginning of data collection on each reach. This resulted in multiple velocity profiles being collected each day.

CONCLUSION:

The equipment calibration and procedures used by GBA during both site visits substantially conforms to the applicable accuracy standards, quality control and quality assurance requirements as listed in the U.S. Army Corps of Engineers, EM 1110-2-1003, Chapter 3, Table 3-1. The maximum allowable biases listed in the results section of this report are from the Navigation & Dredging Support Surveys Hard Bottom Material Classification (Table 3.1) which generally has the most stringent accuracy requirements.

CONTACT:

Questions regarding the technical aspects of this report should be addressed to:

AECOM
5757 Woodway, Suite 101W
Houston, TX 77057

Attention: John Gaskin
Telephone: 713-267-3247
Fax: 713-267-3295
Email: john.gaskin@aecom.com

Laura Kelmar
AECOM Project Manager
2 Technology Park Drive
Westford, MA 01886-3140

Subject: Review of Hydrographic Survey Report prepared by Gahagan & Bryant Associates, Inc (GBA) for Spring 2010, Lower Passaic River, Newark, NJ, submitted September 30, 2010. Items marked with an asterisk and in italics indicate the action GBA took to resolve the deficiency.

PURPOSE:

Quality Assurance review of the report referenced above to ensure accurately detailed daily field operations and data processing procedures.

BACKGROUND:

GBA performed a multi-beam and single beam hydrographic survey of the Lower Passaic River, in the vicinity of Newark, NJ between river miles 0-14 during the spring of 2010. These surveys are conducted periodically in support of the ongoing Lower Passaic River Study Area (LPRSA) Remedial Investigation / Feasibility Study. I was present for two separate site visits during the duration of the survey operations resulting in the report referenced above. My initial site visit included the survey dates of June 8-11, 2010 and my final visit included the survey date of June 23, 2010. I was present during these site visits to observe and confirm that GBA survey equipment setup and calibration was consistent with industry procedures and standards and to provide survey oversight between river miles 0-2 and 13-14.

RESULTS:

- The equipment listed in the report by GBA for the multi-beam and single beam hydrographic survey is consistent with the equipment listed in the company's Technical Proposal dated April 29, 2010 and with that used during my site visits.
- The survey report states that sound velocity profiles and vertical positioning checks were made at the beginning, midpoint and end of the survey day as well as horizontal positioning checks at the beginning and end of each survey day. There exist some instances where these checks were not listed in the Daily Multi-Beam Survey Log (see logs from June 9, 11, 13, 21, 23 for sound velocity profiles, June 8-10, 19, 21, 22 for horizontal positioning checks and June 18, 21, 22 for vertical positioning checks).
** Tables listing horizontal position checks, vertical tide checks and sound velocity profiles have been added as pages 201-203 of the revised September 30, 2010 report.*

- The electronic copy of the Daily Multi-Beam Survey Log for June 22, 2010, page 10 of 14, is not included in the report.
** This page is now included in the revised September 30, 2010 report.*
- The Daily Multi-Beam Log for June 22, 2010, page 11, indicates the multi-beam sensor head hit a rock, as a result tests were run to determine if any changes had occurred to the system. There appears to be no reference to these tests in the report.
** This is addressed on page 21 of the revised September 30, 2010 report under Section 6, Daily Overview of Survey Operations (June 22, 2010).*
- The quality assurance performance tests were conducted on June 8, 17, and 23. The results of each test shown on pages 15-17 of the report are listed below:

The performance test conducted on June 8 yielded the following results: Maximum outlier = 0.64', Mean difference = - 0.08' and 95% Confidence = 0.43'.

The performance test conducted on June 17 yielded the following results: Maximum outlier = 0.76, Mean difference = -0.07' and 95% Confidence = 0.44'

The performance test conducted on June 23 yielded the following results: Maximum outlier = 0.85', Mean difference = -0.03' and 95% Confidence = 0.44'

The maximum allowed tolerances as indicated in the U.S. Army Corps of Engineers Standards, EM 1110-2-1003, Chapter 3, Table 3-1 under the Hard Bottom Material classification are:

Maximum outlier = 1.0'
Mean difference = < 0.1'
95% Confidence = $\pm 1.0'$

The maximum allowed tolerances for the Soft Bottom Material classification are:

Maximum outlier = 1.0'
Mean difference = < 0.2'
95% Confidence = $\pm 2.0'$

The results of each of the three performance test conducted by GBA are within the tolerances allowed by the USACE standards.

- The raw data was reviewed for obvious outliers then processed through all phases with Hysweep software. There is no specific information detailing each phase of this processing.
** A more detailed explanation of the processing phases has been added on pages 8-9 of the revised September 30, 2010 report under Section 4, Overview of Office Processing Procedures.*

- GBA overlaid single beam cross section data with multi-beam data to ensure the accuracy of the data sets. There is no mention of the results of the comparison.
** The comparison between single beam cross section data and multi-beam data is addressed on page 19 of the revised September 30, 2010 report under Section 5, Single Beam Cross Check Lines.*
- The report states once the multi-beam data was edited and verified it was formulated into final products, such as contours and binned data. There appears to be no mention of the specifics regarding bin size and contour intervals and how they were generated in this section.
** The binned data sizes and contour interval are listed on page 9 of the revised September 30, 2010 report under Section 4, Overview of Office Processing Procedures.*

CONTACT:

Questions regarding the technical aspects of this review should be addressed to:

AECOM
5757 Woodway, Suite 101W
Houston, TX 77057

Attention: John Gaskin
Telephone: 713-267-3247
Fax: 713-267-3295
Email: john.gaskin@aecom.com